OCL Documentation

Christian Damus, Adolfo Sánchez-Barbudo
Herrera, Axel Uhl, Edward Willink and contributors

Copyright 2002 - 2014

Chapter 1. Overview and Getting Started

For a quick demonstration of OCL enrichment of an Ecore meta-model with computed constraints go to Getting Started.

A PDF version of this documentation is available at OCL 5.0.0 Documentation.

1.1. What is OCL?

- *EMF is Modeled Structure*

The Eclipse Modeling Framework (*EMF*) supports the definition of structural meta-models and the subsequent use of models conforming to these meta-models. EMF also supports generating of Java code to represent the meta-models. Additional Java code can be provided to add behavior to the structural meta-models.

- *OCL is EMF and Modeled Behavior*

OCL provides a modeling language that allows the behavior to be embedded within the structural meta-models or provided as a complement to those meta-models. As a modeling language, OCL understands the models and so OCL code is much more compact than the equivalent Java. OCL code can be statically checked, whereas the corresponding Java code often uses reflection and so cannot be checked.

Eclipse OCL is an implementation of the OMG OCL 2.4 specification for use with Ecore and UML meta-models.

1.2. How Does It Work?

OCL is a programming language, so you will want to edit it, execute it and debug it.

1.2.1. Editing

Eclipse OCL supports entry of semantically checked OCL expressions

- embedded within Ecore using the OCLinEcore editor
- as complementary documents using the Complete OCL editor
- interactive entry and evaluation using the Interactive OCL console.
- programmatic entry and evaluation using the Java API

EMF supports entry of unchecked OCL

- embedded within Ecore using the Sample Ecore Editor properties view

Eclipse UML supports entry of unchecked OCL

- embedded within UML OpaqueExpressions using the UML Model Editor properties view

Papyrus supports entry of semantically checked OCL expressions

- embedded within UML OpaqueExpressions using the Essential OCL editor

1.2.2. Execution

Eclipse OCL supports OCL execution

- interactive entry and evaluation using the Interactive OCL console.
- programmatic entry and evaluation using the Java API

EMF support for generated models enables OCL execution of

- constraints, operation bodies and property initializers using the Java API

EMF support for dynamic models enables OCL execution of

- constraints using the Validation Delegate API

- operation bodies using the [Invocation Delegate](#) API
- property initializers using the [Setting Delegate](#) API
- queries using the [Query Delegate](#) API

All OCL execution is normally interpreted and starts from the OCL source text (Concrete Syntax). There is therefore a first time parsing overhead to create the compiled form (Abstract Syntax). The compiled form is cached to avoid repeated parsing costs.

Altenatively the direct Java code generator may be used as described in the [Code Generator Tutorial](#).

1.2.3. Debugging

Since OCL is used embedded in a larger environment, debugging is not easy to provide for OCL in isolation. The [OCL debugger](#) provides a variety of launch mechanisms that enable re-use of model element and/or constraint selections.

Alternatively the following approaches may be useful within other toosl

- use the hover-text in the semantic editor to understand the expression types
- use the quick-fixes in the semantic editor for possible corrections
  - if the same fix is suggested more than once, try restarting the editor
- use the completion assist in the semantic editor for possible syntaxes
- use intermediate invariants to check partial results
- use the optional explanation messages for an invariant to provide a 'printf'
- use the [Interactive OCL](#) console to practice a problematic expression on a model

1.2.4. Testing

Once again, since OCL is used embedded in a larger environment, testing is not easy to provide for OCL in isolation. The following approaches may be useful.

- use the [Interactive OCL](#) console to practice sub-expressions of a problematic expression on a model

The Eclipse OCL development uses an extended JUnit framework that allows the Eclipse OCL code to be tested by assertions such as:

```
assertQueryInvalid(null, "let b : Boolean = null in true and b");
assertQueryResults(null, "Set{'b'}", "Set{'a', 'b', 'c'} - Set{'c', 'a'}");
```

(The null first argument may be a context object.)

See the org.eclipse.ocl.examples.xtext.tests plugin for further details.

1.3. Eclipse OCL is Extensible

The Classic Eclipse OCL is used as a component in a variety of other Eclipse projects such as Acceleo, BIRT, GMF, Modisco, QVTo. Ecore models are used directly, which leads to some internal difficulties.

A new Unified Eclipse OCL is evolving that exploits Xtext and uses Ecore models indirectly via a UML-aligned Pivot models. This provides a choice between the classic APIs that offer limited forward functionality, and the experimental new APIs that will be promoted to non-experimental form in the Mars release.

The new code already offers a fully modeled Standard Library that can be extended or replaced. The new OCL grammars are extended internally from Essential OCL to OCLinEcore or Complete OCL, and externally to QVT Core and QVT Relational. The associated Concrete Syntax to Abstract Syntax mapping is not yet model-driven and so harder to extend.

Full model-driven extensibility is planned for the Mars release.

1.4. Who Uses OCL and Eclipse OCL?

The OCL specification is defined by the *OMG*. It originally evolved as part of *UML* where it is used for the detailed mathematical aspects that are not appropriate for graphical exposition. OCL 2.0 was split off from UML 2.0 in recognition of its greater utility.

Within the OMG context, OCL has been re-used as the foundation for the MOFM2T(Model to Text) Model-to-Text transformation language and the *QVT* Model-to-Model transformation language. Eclipse implementations of these are available as the Acceleo and QVT Operational projects.

Eclipse OCL is an implementation of the OCL specification for use in conjunction with EMF and in particular Ecore and UML2 meta-models. As the behavioral extension for EMF, Eclipse OCL can be used wherever EMF can.

As a specification language, OCL is frequently used when the behavior of models is formally specified.

The use of OCL as an execution language has been hindered by the quality of tool support. Beyond the research domain, many usages have been proprietary. One advanced proprietary usage at SAP has been contributed to Eclipse OCL and is available as the Impact Analyzer. This supports strategic planning of run-time notifications so that derived model properties can be updated efficiently in response to a change to a model. Thousand-fold speed improvements are achievable on large models using OCL rather than Java because OCL has a formal model-based semantics that is amenable to analysis.

The use of OCL in general is eased by the provision of good editors exploiting Xtext to provide comprehensive semantic feedback in a familiar editing style.

The use of OCL for execution is enhanced by providing direct Java code generation for OCL embedded in models. This should alleviate many of the performance concerns for interpreted execution of embedded OCL.

Debugging of OCL execution is now possible using the OCL debugger and the OCL Console can be used for OCL experimentation.

1.5. Who is Behind Eclipse OCL?

Eclipse OCL is an Open Source project. The original code for OCL 1.x was contributed by IBM. It has evolved to support OCL 2.x under the auspices of Eclipse.

There is now a significant personnel and corporate overlap between the Eclipse OCL committers and the OMG OCL *RTF* and so Eclipse OCL is pioneering solutions to many of the under-specification problems in the OCL specification.

You can expect future changes in OMG OCL to have an implementation in Eclipse OCL to demonstrate their viability. It is likely that the next version of the OCL specification will use Eclipse OCL and M2T(Model to Text) tooling to eliminate inconsistencies. Eclipse OCL is currently in use to check that the OCL used in the UML 2.5 specification is syntactically and semantically correct.

Direct tooling of the UML 2.5 and OCL 2.5 specifications for the Mars Eclipse release may demonstrate that the OCL aspects of the specifications is also functionally consistent.

1.6. Getting Started

For a very quick demonstration of OCL, you may follow this very abbreviated version of the OCLinEcore tutorial, where you can find Installation instructions. Once you have the OCL Examples and Editors feature installed you may follow these instructions to get an insight into the capabilities of OCL and the Eclipse OCL tooling.

Invoke **File->New->Project...** then select **Examples** then **OCL (Object Constraint Language) Plugins** then **OCLinEcore Tutorial** and **Finish** to create a small example project called **org.eclipse.ocl.examples.project.oclinecoretutorial**. It contains

- **model/Tutorial.ecore** - a small Library meta-model

- **model/Tutorial.xmi** - an even smaller Library model

- **model/Tutorial.genmodel** - a gebnerator for Java code

Select **model/Tutorial.ecore** and use the right button to invoke **Open With->OCLinEcore Editor**. This gives you a textual view of the Ecore file with embedded OCL invariants such as the Book constraint

```
invariant SufficientCopies:
  library.loans->select((book = self))->size() <= copies;
```

This invariant is named SufficientCopies. It

- navigates from the implicit self (a Book)

- via the library
- to its loans which it searches
- to select those loans that satisfy the predicate
  - loaned book is equal to the self Book
- the size (number) of loans is computed
- and compared to the number of copies of the self Book

The invariant is satisfied if it evaluates true; i.e. if the number of loans is less than or equal to the number of copies.

You can see this invariant at work, by selecting **model/Tutorial.xmi** and using the right button to invoke **Open With->Sample Reflective Ecore Model Editor**. This gives you a tree view of a small library model.

Expand the root element and then select the **Library lib** element and use the right button menu to invoke **Validate**. You should get a pop-up reporting problems during Validation. Click **Details** and you will see that one of the problems is with the **SufficientCopies** invariant we have just looked at. If you browse the Properties View for **model/Tutorial.xmi**, you can verify that there are three loans but only two copies for the offending Book.

You may evaluate custom OCL queries interactively. From the editor for **Tutorial.xmi**, invoke **OCL->Show Xtext OCL Console** from the context menu. Select **Book b2** in the editor, then in the bottom line of the console enter the OCL expression **loans.member** and then Enter. The results are shown in the panel and identify that all three loans are by **Member m3**.

The expression **loans.member** is an abbreviated form of **self.loans->collect(aLoan : Loan | aLoan.member)** and demonstrates OCL's ability to perform many useful navigations over multi-element properties. The expression

- navigates from self, the Book b2 selection
- to its loans, using Book::loans which is a derived property defined in OCL
- for each of the loans, the iterator variable, aLoan, is assigned to the loan and
  - the body, aLoan.member is evaluated to return the member making the loan
- the resulting members are collected to return a collection result
- the result is displayed on three lines in the results panel

You can step through execution using the OCL debugger. In the Console View type PageUp to restore the earlier text entry, then with **Book b2** still selected in the editor, click the debug icon in the Console tool bar. The debugger should open automatically, but if it doesn't, use **Window->Show View->Debug** from the Eclipse menu bar. The Variables View shows model elemnt values. Click F5 or Step Into a few times to progress execution.

You have now seen

- an Xtext editor that embeds OCL directly in Ecore models to provide programmed enrichment
- execution of OCL while validating a model using conventional Ecore tooling
- an interactive Console for custom OCL evaluations
- execution of a derived property defined in OCL
- the ability of OCL to express operations on multi-elements compactly
- the ability to debug OCL execution and browse data

You have not

- written any Java code
- generated any plugins
- needed to start an additional Eclipse session

Please follow the tutorials, examples and reference material for further information.

Chapter 2. Users Guide

The core functionality of OCL that supports expressions over models is called the Essential OCL. This language is of very limited use by itself since there is no way in which the models can be provided. Essential OCL is therefore extended in various ways to provide this missing context.

The [Complete OCL](#) provides a language for a document in which OCL complements an existing meta-model with invariants, and additional features.

[OCLinEcore](#) embeds OCL within the annotations of an Ecore model to enrich that model.

UML supports the use of OCL constraints as a form of OpaqueExpression, and UML tools such as Papyrus support those constraints for UML models.

The Eclipse OCL project provides four OCL languages to support these usages.

- [Essential OCL](#) provides the core extensible capability of specifying expressions for models.
- [Complete OCL](#) provides the ability to use OCL in a self-standing document to complement an existing meta-model with invariants, and additional features.
- [OCLinEcore](#) enables OCL to be embedded within an Ecore meta-model to add invariants for classifiers, bodies for operations and computed values for properties.
- [OCLstdlib](#) supports the definition of the standard and custom OCL Standard Libraries.

2.1. The two Eclipse OCLs

The Eclipse OCL project is making a transition to a new underlying infrastructure.

2.1.1. The Classic Eclipse OCL metamodels

The Classic code base emphasized utility for Java programmers. It originally supported Ecore meta-models and evolved to support UML as well. An OCL Console was added to support interactive experimentation with OCL expressions.

Interactions with the QVTd project resulted in a refactoring of the grammars so that they could be extended for use by QVT. At the same time the grammars were migrated to use LPG 2.

The dual support for Ecore and UML was achieved by a shared generic meta-model in which the distinctions between Ecore and UML meta-models were accommodated by substantial (often ten parameter) template parameters lists. Sometimes these lists are hidden by derived bindings, but sometimes the full lists are exposed. This gives rather cumbersome Java code for the OCL developers and OCL consumers alike.

The classic evaluator is tightly coupled to Ecore which might appear efficient, but the lack of separation of OCL-specification semantics from Java-implementation semantics makes accurate implementation of equality in nested collections hard to achieve.

The classic code endeavored to comply with OCL specification despite significant ambiguities in the specification, but since the classic code evolved from an OCL 1.x compliance and Ecore utility there are a number of areas where accurate OMG compliance is hard to achieve.

The classic code is provided primarily by the following plugins

- org.eclipse.ocl
- org.eclipse.ocl.ecore
- org.eclipse.ocl.uml

2.1.2. The Unified or Pivot Eclipse OCL metamodel

The Unified or Pivot metamodel is a prototype for a resolution of a number of fundamental problems with the OCL 2.4 specification. The Pivot metamodel is derived from the UML metamodels for UML and OCL to provide a unified metamodel for UML with executable semantics.

In practice, when using the Pivot metamodel for Ecore or UML metamodels, a Pivot metamodel instance is created on the fly to provide the unified merged OCL functionality for the Ecore or UML metamodel instances.

From the specification perspective, the Pivot metamodel

- is UML-aligned
- supports modeling of the OCL standard library
- supports 'merging' of additional Complete OCL definitions
- supports an interchangeable XMI representation
- supports a fully reflective oclType()

From the Eclipse perspective, the Pivot metamodel

- hides Ecore differences with respect to EMOF
- hides MDT/UML2 differences with respect to UML
- allows much of the semantics to be defined by a single library model
- allows user extension and replacement of the library model
- allows for exact OMG compliance

At the same time, the Values package that forms part of the specification has been implemented. This allows a clear separation of OCL-semantics, and although the extra object apparently wrapping each value might appear to incur overheads, we expect to streamline this so that the new structure is accurate and faster.

The unified code is provided primarily by plugins that share the prefix

- org.eclipse.ocl.examples

2.1.3. The transition

This transition started in the Helios (3.0) release for which Xtext editors were provided for OCLinEcore, Complete OCL and the OCL Standard Library. There was then no Pivot meta-model and so the editors offered only syntactic validation. It was not possible to persist an AST as XMI or to evaluate code that had been parsed by the Xtext parsers. It was necessary to re-parse with the LPG parsers.

In the Indigo (3.1) release, the Pivot metamodel prototype was introduced and used to support semantic validation within the Xtext editors. The OCL Standard Library was realised using the Pivot metamodel and a new highly extensible evaluator was implemented. These facilities are used by the new OCL Xtext Console.

Therefore when using the OCL Xtext Console the contributing tools are

- Essential OCL Xtext editor
- Pivot MetaModel
- OCL-2.5.oclstdlib library
- Pivot Evaluator
- Pivot Debugger

When using the classic OCL Console the contributing tools are

- LPG parser and hand-coded Syntax Helper
- Ecore (or UML) metamodel bindings
- Hand coded library implementation
- Classic evaluator

Since these tools are different there may be occasions where the increased OMG compliance of the Pivot metamodel gives different behavior to the classic metamodels.

In the Juno (3.2/4.0) release, there is a preliminary Java code generator for the Pivot metamodel so that all the parsing overheads and significant parts of the execution overheads of OCL embedded in Ecore models occurs at genmodel time rather than during execution.

In the Kepler (3.3/4.1) release, the code generator was substantially improved and a number of internal APIs have evolved accordingly. UML support was improved to facilitate usage within Papyrus, and extensibility was improved for use by QVTd.

In the Luna (3.4/5.0) release, further code generation improvements have been made and major new User Interface capabilities added. There is at last an OCL debugger and a Constraint Validity View.

In the Mars (1.0/6.0) release, the transition should be complete and many org.eclipse.ocl.examples.* plugins will be renamed to org.eclipse.ocl.*. All functionality should use the new Pivot metamodel by default. However the classic Ecore and UML support will remain for compatibility.

2.1.4. APIs

Eclipse OCL has two different styles of APIs

2.1.4.1. Tool APIs

The major tool APIs originally provided by the org.eclipse.ocl.OCL class have evolved only slightly to org.eclipse.ocl.ecore.OCL and org.eclipse.ocl.uml.OCL for the classic metamodels and org.eclipse.ocl.examples.pivot.OCL for the Pivot metamodel.

These APIs support the use of OCL as a tool to parse and evaluate constraints and queries.

These APIs will change very little; just the package changes according to the chosen metamodel representation.

2.1.4.2. Internal APIs

The internal parsing APIs were made public in 1.3.0 to support parser extension by QVT. These APIs are very tightly coupled to a particular LPG implementation of a particular OCL grammar formulation. It is extremely difficult to replicate these APIs for the ANTLR grammar that underlies the Xtext editors. It is also doubtful whether these APIs can be preserved as the OCL specification is clarified to more clearly specify what words are reserved and what is extensible.

It is therefore unlikely that the internal APIs for the classic metamodels will be replicated for the Pivot metamodel. However since an LPG grammar is significantly (ten-times) smaller and perhaps a bit faster (two-times) it is planned to provide an automated Xtext to LPG translation so that a smaller LPG grammar can populate the same auto-generated Concrete Syntax structures as the ANTLR grammar.

This functionality is intended to form part of a new grammar extension API that will enable OCL-extending languages such as QVT to re-use and extend not only the grammar but also all the semantic scope resolution and concrete to abstract syntax mappings.

2.1.4.3. Versions

Eclipse version numbering policy requires that a major version change occurs when any re-exported component has a major version number change. Consequently when Eclipse UML moved from to UML 2.4 support (4.0.0) and again to UML 2.5 (5.0.0) a corresponding chnage was forced on the Classic UML support and this is the number that then applies to the whole of Eclipse OCL. However the Ecore dependencies are unchanged and so Ecore dependent releases have advanced more slowly; 3.2 accompanying 4.0 and now 3.4 accompanying 5.0.

This is probably just as confusing for the developers as for consumers. It is however necessary to ensure that the minor changes in the Classic Ecore functionality are not presented as major changes to consumers.

2.2. The Essential OCL Language

The core functionality of OCL that supports expressions over models is called the Essential OCL. This language is of very limited use by itself since there is no way in which the models can be provided.

Essential OCL is extended in various ways to provide this missing context.

The Complete OCL provides a language for a document in which OCL complements an existing meta-model with invariants, and additional features. Complete OCL is part of the OMG OCL specification.

OCLinEcore embeds OCL within the annotations of an Ecore model to enrich that model. OCLinEcore is defined an Eclipse OCL. It is not part of the OMG OCL specification.

UML supports the use of OCL constraints as a form of OpaqueExpression, and UML tools such as Papyrus support those constraints for UML models.

2.2.1. Syntax

The Eclipse OCL realization of the Essential OCL grammar is provided in the following subsections, starting with the expression terms and then elaborating the operators.

2.2.1.1. Grammar Implementation

The grammar used by the Xtext editors may be found at:

/src/org/eclipse/ocl/examples/xtext/essentialocl/EssentialOCL.xtext

in the org.eclipse.ocl.examples.xtext.essentialocl plugin.

2.2.1.2. Grammar Approach

The OCL 2.4 grammar is ambiguous and consequently has disambigating rules. How those disambiguating rules are applied is an implementation detail.

The disambiguating approach taken in Eclipse OCL is to parse an unambiguous larger language that unifies all the ambiguities. Subsequent semantic validation distinguishes between the ambiguities and diagnoses expressions from the larger language that are not valid OCL expressions.

From a technical point of view this makes the grammar simpler and more regular, and the implementation more modular and configurable by the library model.

From a user's point of view, slightly wrong expressions may be syntactically valid and so semantic validation may produce a more helpful diagnostic. However completion assist may offer illegal expressions from the larger language.

2.2.1.3. OCL Expression

The Exp syntax defines an OCL expression.

Expressions consist of a variety of operators and expression terms that are defined at the top level by an InfixedExp. We will first define the terms of an expression and then define the various forms of operators that bind expression terms together.

2.2.1.4. PrimaryExp

The PrimaryExp syntax identifies the basic building blocks of an OCL expression.

Literals such as

- PrimitiveLiteralExpCS - `true` or `3.14159`
- CollectionLiteralExpCS - `Set{1..5}`
- TupleLiteralExpCS - `Tuple{name:String='me',at:String='here')`
- TypeLiteralExpCS - `Integer` or `Set<Integer>`

The context object

- SelfExpCS - `self`

Compound expressions such as

- NestedExpCS - `(x)`

- [IfExpCS](#) - `if x then y else z endif`
- [LetExpCS](#) - `let x : Integer in x + x`

Navigation expressions such as

- [NavigatingExpCS](#) - `x` or `x.Y::z->iterate(a:Integer;acc:Integer|acc+a)`

2.2.1.5. SelfExp

The SelfExp syntax supports the use of the prevailing context object in an expression.

2.2.1.6. PrimitiveLiteralExp

The PrimitiveLiteralExp syntax supports the use of a known value in an expression.

The value may be

- [NumberLiteralExpCS](#) - `4` or `3.14159`
- [StringLiteralExpCS](#) - `'a string'`
- [BooleanLiteralExpCS](#) - `true` or `false`
- [UnlimitedNaturalLiteralExpCS](#) - `*`
- [InvalidLiteralExpCS](#) - `invalid`
- [NullLiteralExpCS](#) - `null`

2.2.1.7. NumberLiteralExp

The NumberLiteralExp syntax supports the use of a numeric value in an expression.

A numeric value is

- an integer such as `4`
- fixed point number such as `3.1`
- floating point number such as `12.8e-5`.

A numeric value does not have a leading `-`; negative numbers are parsed as the application of a unary negate operator to a positive number.

A numeric value may not have a trailing decimal point.

A numeric value may not have a redundant leading zero.

2.2.1.8. StringLiteralExp

The StringLiteralExp syntax supports the use of a string value in an expression.

A string is specified as a character sequence between single quotes.

e.g. `'This is a string'`

The standard Java and C backslash escapes can be used for awkward characters such as a single quote.

\b -- #x08: backspace BS

\t -- #x09: horizontal tab HT

\n -- #x0a: linefeed LF

\f -- #x0c: form feed FF

\r -- #x0d: carriage return CR

\" -- #x22: double quote "

\' -- #x27: single quote '

\\ -- #x5c: backslash \

\x Hex Hex -- #x00 to #xFF

\u Hex Hex Hex Hex -- #x0000 to #xFFFF

2.2.1.9. BooleanLiteralExp

The BooleanLiteralExp syntax supports the use of boolean values in an expression.

The Boolean values are `true` and `false`.

2.2.1.10. UnlimitedNaturalLiteralExp

The UnlimitedNaturalLiteralExp syntax supports the use of the non-numeric unlimited value in an expression.

The Non-numeric unlimited value is `*`. Other UnlimitedNatural values are NumberLiteralExpCS.

2.2.1.11. InvalidLiteralExp

The InvalidLiteralExp syntax supports the use of an invalid value in an expression.

The invalid value is `invalid`.

2.2.1.12. NullLiteralExp

The NullLiteralExp syntax supports the use of a null or unspecified value in an expression.

The null value is `null`.

2.2.1.13. CollectionLiteralExp

The CollectionLiteralExp syntax supports the creation of a collection of values for use in an expression.

A collection literal comprises the CollectionType followed by braces enclosing a comma-separated list of zero or more CollectionLiteralParts.

e.g. `Sequence{1,2,4..6}`

Note that null, collection and tuple values are permitted in collections but that invalid values are not. A collection 'containing' an invalid value is flattened to the invalid value.

2.2.1.14. CollectionLiteralPart

The CollectionLiteralPart syntax supports the use of a value or range of values in a collection of values.

A single item collection literal part may be any expression (except invalid). e.g. `1+2`

A multi-item collection literal part comprises the inclusive range of values between two integer limits.

`1..3` is the three values `1`, `2`, `3`.

`1..-1` is the three values `1`, `0`, `-1`.

2.2.1.15. TupleLiteralExp

The TupleLiteralExp syntax supports the use of a tuple of named expression values in an expression.

A tuple literal comprises the `Tuple` keyword followed by braces enclosing a comma-separated list of one or more TupleLiteralParts.

`Tuple{year:Integer='2000',month:String='January',day:Integer='1'}`

2.2.1.16. TupleLiteralPart

The TupleLiteralPart syntax supports the use of a named expression value in a tuple of such values.

The part comprises the name, an optional type and a value. If the type is omitted, it is inferred from the value.

`leapyear : Boolean = true`

2.2.1.17. TypeLiteralExp

The TypeLiteralExp syntax supports the use of types as values in an expression. This is useful for expressions such as `myCollection.oclAsType(Set<MyType>)`.

A TypeLiteralExp comprises a TypeLiteral.

2.2.1.18. NestedExp

The NestedExp syntax supports the use of an inner expression as a term in an outer expression ensuring that the operator precedence of the inner expression is not affected by the outer expression,

A nested expression is just an expression surrounded by parentheses.

2.2.1.19. IfExp

The IfExp syntax supports the use of a conditional choice of expression value in an expression.

An if expression comprises a condition expression to be tested followed by a then-expression to be evaluated if the condition is true and an else-expression for evaluation if the expression is false.

```
if this.size > that.size then this else that endif
```

Note that the else-expression is required and so there is no ambiguity when multiple if expressions are nested.

2.2.1.20. LetExp

The LetExp syntax supports the introduction of local variables to facilitate re-use of intermediate results within an expression.

A let expression comprises the let keyword followed by one or more comma-separated let variables and then the in keyword and the in-expression to be evaluated with the help of the extra variables.

Each let variable comprises a name, an optional type and an expression to initialize the variable. If the type is omitted, it is inferred from the initializer.

```
let test : String = 'prefix[contents]suffix',
    start : Integer = test.indexOf('['),
    finish : Integer = test.indexOf(']')
in test.substring(start,finish)
```

The let syntax has no terminating keyword such as endlet and so there is an ambiguity for for instance `1 + let b : Integer = 2 in b + 4`. The ambiguity is resolved as `1 + let b : Integer = 2 in (b + 4)` by selecting the longest possible in-expression.

2.2.1.21. NameExp

The NameExp syntax supports the use of the name of a model element such as a property, operation or type in an expression.

A name expression comprises a name optionally prefixed by double-colon separate path names.

The first name is an UnrestrictedName, that is a name that does not clash with any OCL reserved words such as `else` or built-in types such as `String`. Subsequent names are UnreservedName allowing the re-use of built-in type names but not reserved words.

2.2.1.22. IndexExp

The IndexExp syntax supports the application of qualifiers to a model property to distinguish the source or select a particular association.

A NameExp identifying a model property is optionally qualified by a first list of qualifiers and a second list of qualifiers.

This syntax is experimental and the qualifiers are not yet supported for evaluation.

2.2.1.23. NavigatingExp

The NavigatingExp syntax supports the navigation of models using model properties, operations and iterations.

An IndexExp identifying a potentially qualified model feature is optionally followed by a parenthesized arguments. If the parenthesized arguments are omitted the model feature should be a Property. If the arguments are present the model feature should be an iteration or operation.

The diverse syntaxes specified by OCL 2.4 for OperationCallExpCS and IteratorExpCS create ambiguities that are difficult to parse. The merged grammar used by Eclipse OCL gathers argument contributions without imposing premature validation.

The parenthesized arguments may be empty, or may comprise one or more parameters, optional accumulators and optional bodies.

The comma-separated list of parameters starts with a NavigatingArgCS, followed by any number of NavigatingCommaArgCS.

```
simpleCall(simpleArgument)
```

The optional comma-separated list of accumulators are introduced by a semi-colon-prefixed NavigatingSemiArgCS, followed by any number of NavigatingCommaArgCS.

```
some->iterate(p; anAccumulator : Integer = 0 | p.size())
```

The optional comma-separated list of bodies are introduced by a vertical-bar-prefixed NavigatingBarArgCS, followed by any number of NavigatingCommaArgCS.

```
some->exists(p | p.size())
```

2.2.1.24. NavigatingArg

The NavigatingArg syntaxes supports the parsing of potential parameters, accumulators and bodies for use in NavigatingExps.

Each syntax supports an optional type and an optional initializer for an expression.

2.2.1.25. PrefixedExp

The PrefixedExp syntax supports the application of zero or more prefix unary operators to an expression.

The prefix operator precedes an expression: `-4` or `not(this or that)`

The unary operators are

- `-` negate
- `not` logical complement

2.2.1.26. InfixedExp

The InfixedExp syntax supports the application of zero or more infix binary operators between expression terms.

The infix operators separate expression terms: `1 + 2 / 3 * 4 / 5 + 6.`

The infix operators are

- The [NavigationOperators](#)
- `*, /` multiply and divide

- `+`, `-` add and subtract
- `<`, `<=`, `>=`, `>` relational comparisons
- `=`, `<>` equality and inequality
- `and` logical and
- `or` inclusive or
- `xor` exclusive or
- `implies` logical implication

The precedence and associativity of the operators is defined by the OCL Standard Library model, not by the grammar. The OCL 2.4 library precedence is as presented above with all operators left associative. The example above is therefore interpreted as `(1 + (((2 / 3) * 4) / 5)) + 6`.

2.2.1.27. NavigationOperators

The NavigationOperators operators are

- `.` for object navigation
- `->` for collection navigation

2.2.1.28. TypeExp

The TypeExp syntax supports the use of types as expressions.

A type expression may be a

- TypeNameExpCS - a user-defined type
- TypeLiteralCS - a built-in or aggregate type

2.2.1.29. TypeNameExp

The TypeNameExp syntax supports the use of a user-defined types as a declaration or expression.

A name expression comprises the name of a type optionally prefixed by double-colon separate path names.

The first name is an UnrestrictedName, that is a name that does not clash with any OCL reserved words such as `else` or built-in types such as `String`. Subsequent names are UnreservedName allowing the re-use of built-in type names but not reserved words.

2.2.1.30. TypeLiteral

The TypeLiteral syntax supports the use of built-in or aggregate types as declarations or expressions.

A Type literal may be a

- PrimitiveTypeCS
- CollectionTypeCS
- TupleTypeCS

2.2.1.31. PrimitiveType

The PrimitiveType syntax supports the definition of a built-in type for use in a declaration or expression.

The built-in types are

- Boolean
- Integer
- Real
- String
- UnlimitedNatural
- OclAny
- OclInvalid
- OclVoid

2.2.1.32. CollectionType

The CollectionType syntax supports the definition of a collection type for use in a declaration or expression.

A collection type comprises the CollectionTypeIdentifier followed by a [Type Expression](#) defining the type of the collection elements.

`Set(String)` or `Sequence<Bag<Integer>>`

The built-in CollectionTypeIdentifiers are

- Collection
- Bag
- OrderedSet
- Sequence
- Set

OCL 2.4 specifies the use of parentheses to surround the element type. Eclipse OCL additionally allows angle brackets as specified by UML and as may be required to support more general templated types.

2.2.1.33. TupleType

The TupleType syntax supports the definition of a tuple type for use in a declaration or expression.

A tuple type comprises the `Tuple` keyword followed by a comma-separated list of one or more [TupleParts](#).

OCL 2.4 specifies the use of parentheses to surround the parts. Eclipse OCL additionally allows angle brackets as specified by UML and as may be required to support more general templated types.

```
Tuple<year:Integer,month:String,day:Integer>
```

2.2.1.34. TuplePart

The TuplePart syntax supports the definition of an element of a TupleType.

The part comprises the name and a type and a value.

```
leapyear : Boolean
```

2.2.1.35. UnreservedName

The Essential OCL reserved words are and, else, endif, false, if, implies, in, invalid, let, not, null, or, self, then, true, xor. These can only be used as names when escaped as in _'self'.

2.2.1.36. UnrestrictedName

The Essential OCL restricted words are the reserved words above and the OCL reserved type names which are Bag, Boolean, Collection, Integer, Lambda, OclAny, OclInvalid, OclMessage, OclSelf, OclVoid, OrderedSet, Real, Sequence, Set, String, Tuple, UnlimitedNatural. An UnrestrictedName can be used in any context. The reserved type names can be used following a :: qualification, Without qualification unrestricted names must be escaped as _'Boolean'.

Lambda is used in experimental syntax that realizes iterator bodies as lambda-expressions.

2.3. The OCLinEcore Language

Ecore Abstract Syntax supports the use of OCL embedded within EAnnotations.

The OCLinEcore language provides a textual Concrete Syntax that makes both Ecore and OCL accessible to users. Examples may be found in OCLinEcore Library Metamodel and OCLinEcore Helpers.

The OCLinEcore tooling provides a rich editing environment based on Xtext with strong semantic checking.

OCLinEcore is more than just an editor for OCL in Ecore, it is useful for

- providing a coherent textual view of an Ecore meta-model
- providing syntax sugar for some Ecore conventions
- editing and validating OCL
- integrating OCL into Ecore

It is planned to take the syntactic sugar further and provide full support for all class-related UML concepts. The language therefore uses UML as its point of reference wherever possible.

The OCLinEcore tooling may be used directly on *.ecore files, or on their *.oclinecore textual counterparts.

Please follow the OCLinEcore tutorial for an introduction to the language and its tooling.

2.3.1. Syntax

The OCLinEcore syntax has a consistent structure influenced by the informal definitions in OMG specifications and by the Ecore hierarchy. Most Ecore concepts are represented by a syntax of the form:

- optional primary adjectives
- mandatory keyword
- mandatory name facet
- further facets
- an optional braced clause of secondary adjectives
- an optional braced clause of elements

- composed elements
- annotations
- constraints

Thus in:

```
abstract class Example extends Base { interface } { ... }
```

- `abstract` is a primary adjective
- `class` is a keyword
- `Example` is the name facet
- `extends Base` is a further facet
- `{ interface }` supports the secondary interface adjective.
- `{ ... }` provides a nested context for class content.

2.3.1.1. Grammar Implementation

The grammar used by the Xtext editors may be found at:

/src/org/eclipse/ocl/examples/xtext/oclinecore/OCLinEcore.xtext

in the org.eclipse.ocl.examples.xtext.oclinecore plugin. The OCLinEcore grammar extends the Essential OCL grammar.

2.3.1.2. Module

The Module syntax supports the overall structure of an Ecore file

The definition of the module comprises

- optional module declaration
- optional specification of the OCL Standard libraries
- optional import of referenced Ecore or UML or OCLinEcore resources
- a hierarchy of [Packages](#)

Zero or more external libraries may be imported so that their definitions are merged to form a composite library of basic and extended evaluation capability.

The implicit import of the default OCL Standard Library is suppressed, if any library is imported. The default library may be extended by specifying it as the first library import.

```
library ocl : 'http://www.eclipse.org/ocl/3.1.0/OCL.oclstdlib'
```

The namespace URI of the first library package defines the namespace URI of the composite library. The namespace URI of subsequent library imports may not conflict, but may be null.

Zero or more external metamodels may be imported.

2.3.1.3. Package

The Package syntax supports a nested hierarchy of packages and classifiers

A Package has a name and optionally a namespace prefix and namespace URI.

The content of a Package may comprise Packages, Classifiers and Annotations.

2.3.1.4. Classifier

The Classifier syntax supports the definition of types within a Package.

A Classifier may be

- a Class
- a DataType
- an Enumeration with associated EnumerationLiterals

2.3.1.5. DataType

The DataType syntax supports the definition of an EDataType.

A DataType has a name and optionally template parameters and an instance class name.

A DataType may be serializable; by default it is not.

The content of a DataType may comprise invariants and Annotations.

2.3.1.6. Enumeration

The Enumeration syntax supports the definition of an EEnum.

An Enumeration has a name and optionally template parameters and an instance class name.

An Enumeration may be serializable; by default it is not.

The content of an Enumeration may comprise enumeration literals, invariants and Annotations.

2.3.1.7. EnumerationLiteral

The EnumerationLiteral syntax supports the definition of an EEnumLiteral.

An EnumerationLiteral has a name and optionally a value.

The content of an EnumerationLiteral may comprise Annotations.

2.3.1.8. Class

The Class syntax supports the definition of an EClass.

- optional abstract prefix
- optional extension of other classifiers
- optional invariants, annotations, features and operations

A Class may be abstract has a name and optionally template parameters.

(NB, the 'abstract' prefix is optional, even though the figure indicates that it is mandatory.)

A Class may extend one or more other Classes that may be specialized using the template parameters.

A Class may have an instance class name, and may also be declared to be an interface.

The content of a Class may comprise Annotations, Operations, StructuralFeatures and invariants.

2.3.1.9. StructuralFeature

The StructuralFeature syntax supports the definition of the StructuralFeatures.

A StructuralFeature may be

- an [Attribute](#)
- a [Reference](#)

2.3.1.10. Attribute

The Attribute syntax supports the definition of an EAttribute; a Property with a DataType value.

An Attribute may be static and has a name.

The `static` qualifier supports declaration of static properties which are supported by UML and OCL. Note that Ecore does not support static properties.

The `definition` qualifier is an obsolete experimental syntax for Complete OCL definitions.

An Attribute may may have a [Type](#) and multiplicity.

An Attribute may a simple initializer and a variety of qualifiers:

- `derived` specifies a derived attribute (default `!derived`)
- `id` specifies that the attribute provides the identifier if its class (default `!id`)
- `ordered` specifies that the attribute elements are ordered (default `!ordered`)
- `readonly` specifies that the attribute elements are readonly (not changeable) (default `!readonly`)
- `transient` specifies that the attribute elements are computed on the fly (default `!transient`)
- `unique` specifies that there are no duplicate attribute elements (default `unique`)
- `unsettable` specifies that attribute element may have no value (default `!unsettable`)
- `volatile` specifies that the attribute elements are not persisted (default `!volatile`)

The content of an Attribute may comprise Annotations, initial and derived constraints.

A simple constant value may be defined using the initializer. A computed value requires the use of a constraint. If both initial and derived constraints are present, the initial constraint is ignored.

The defaults for multiplicity lower and upper bound and for `ordered` and `unique` follow the UML specification and so corresponds to a single element Set that is `[1] {unique,!ordered}`. Note that UML defaults differ from the Ecore defaults which correspond to an optional element OrderedSet, that is `[?] {ordered,unique}`.

2.3.1.11. Reference

The Reference syntax supports the definition of an EReference; a Property with a Class value.

An Reference may be static and has a name and optionally an opposite name.

The `static` qualifier supports declaration of static properties which are supported by UML and OCL. Note that Ecore does not support static properties.

The `definition` qualifier is an obsolete experimental syntax for Complete OCL definitions.

A Reference may may have a Type and multiplicity.

```
= ─ SINGLE_QUOTED_STRING

{   composes
    !composes
    derived
    !derived
    ordered
    !ordered
    readonly
    !readonly
    resolve
    !resolve
    transient
    !transient
    unique
    !unique
    unsettable
    !unsettable
    volatile
    !volatile
    ,  }
```

A Reference may a simple initializer and a variety of qualifiers:

- `composes` specifies a composed (containing) reference (default `!composes`)
- `derived` specifies a derived reference (default `!derived`)
- `ordered` specifies that the reference elements are ordered (default `!ordered`)
- `readonly` specifies that the reference elements are readonly (not changeable) (default `!readonly`)
- `resolve` specifies that the reference elements proxies may need resolution (default `!resolve`)
- `transient` specifies that the reference elements are computed on the fly (default `!transient`)
- `unique` specifies that there are no duplicate reference elements (default `unique`)
- `unsettable` specifies that reference element may have no value (default `!unsettable`)
- `volatile` specifies that the reference elements are not persisted (default `!volatile`)

```
{   AnnotationElementCS
    key  UnrestrictedName  ,  UnrestrictedName  :
    InitialConstraintCS
    DerivedConstraintCS
    }
    ;
```

The content of a Reference may comprise keys, [Annotations](), initial and derived [constraints]().

A simple constant value may be defined using the initializer. A computed value requires the use of a constraint. If both initial and derived constraints are present, the initial constraint is ignored.

The defaults for multiplicity lower and upper bound and for `ordered` and `unique` follow the UML specification and so corresponds to a single element Set that is `[1] {unique,!ordered}`. Note that UML defaults differ from the Ecore defaults which correspond to an optional element OrderedSet, that is `[?] {ordered,unique}`.

2.3.1.12. Operation

The Operation syntax supports the definition of an EOperation.

An Operation may be static and has a name and optionally template parameters.

The `static` qualifier supports declaration of static operations which are supported by UML and OCL. Note that Ecore does not support static operations.

The `definition` qualifier is an obsolete experimental syntax for Complete OCL definitions.

An Operation has zero of more [Parameters]().

An Operation may have a return [Type]() and multiplicity.

An Operation may declare zero or more throw [Exceptions]().

An Operation may have a variety of qualifiers:

- `derived` specifies a derived operation (default `!derived`)

- `ordered` specifies that the returned elements are ordered (default `!ordered`)

- `unique` specifies that there are no duplicate returned elements (default `unique`)

The content of an Operation may comprise Annotations, precondition, postcondition and body constraints.

The `static` qualifier supports declaration of static operations which are supported by UML and OCL. Note that Ecore does not support static operations.

The `definition` qualifier is an obsolete experimental syntax for Complete OCL definitions.

The defaults for multiplicity lower and upper bound and for `ordered` and `unique` follow the UML specification and so corresponds to a single element Set that is `[1] {unique,!ordered}`. Note that UML defaults differ from the Ecore defaults which correspond to an optional element OrderedSet, that is `[?] {ordered,unique}`.

2.3.1.13. Parameter

The Parameter syntax supports the definition of an EParameter.

A Parameter has a name, optional "Type:#OCLinEcore-TypeRef and multiplicity

A Parameter may have a variety of qualifiers:

- `ordered` specifies that the returned elements are ordered (default `!ordered`)

- `unique` specifies that there are no duplicate returned elements (default `unique`)

The content of a Parameter may comprise Annotations.

The defaults for multiplicity lower and upper bound and for `ordered` and `unique` follow the UML specification and so corresponds to a single element Set that is `[1] {unique,!ordered}`. Note that UML defaults differ from the Ecore defaults which correspond to an optional element OrderedSet, that is `[?] {ordered,unique}`.

2.3.1.14. Types

The Type syntax supports the definition of EType and EGenericType in conjunction with an ETypedElement. The syntax is very similar to Java.

PrimitiveTypeRefCS provides access to the built-in OCL types and their corrsponding Ecore counterparts

OCL type	Ecore type
Boolean	EBoolean
Integer	EBigInteger
Real	EBigDecimal
String	EString
UnlimitedNatural	EBigInteger

TypedTypeRefCS provides for user defined types and their template parameterisation.

2.3.1.15. AnnotationElement

The AnnotationElement syntax supports the definition of an EAnnotation hierarchy with details, references and contents.

An AnnotationElement may be Annotation or Documentation.

2.3.1.16. Annotation

The Annotation syntax supports the definition of an EAnnotation hierarchy with details, references and contents.

An Annotation has a source URI, which may be specified without quotes if the URI is just a name.

An Annotation may have Details.

The content of an Annotation may comprise

- Annotations
- content elements
- names that reference other elements

2.3.1.17. Detail

The Detail syntax supports the definition of a detail of an EAnnotation.

A detail comprises a detail key and optional value.

2.3.1.18. Documentation

The Documentation syntax is an experimental syntactic sugar for a genmodel annotation.

It is likely to be replaced by a Javadoc-style comment that will be persisted in Ecore.

2.3.1.19. Constraints

The Constraints syntax supports the embedding of OCL expressions as invariants for classes, as preconditions, postconditions or bodies for operations and initial or derived values for properties.

The integration occurs through the *SpecificationCS* rule that invokes an ExpCS. (The alternative *UnquotedString* is an implementation detail that supports the import from Ecore where the OCL is in unparsed textual form rather than an analyzed syntax tree.)

A class invariant may be `callable` to specify that the Ecore representation is to use the EOperation rather than EAnnotation representation.

A class invariant optionally supports a second OCL expression as a parenthesis on the invariant name. This parenthesized expression is invoked when an invariant fails in order to provide a user-defined failure message. Whether this message is an error or a warning is determined by the evaluation of the invariant:

2.3.1.20. Terminals

The OCLinEcore grammar extens the Esstial OCL grammar which should be consulted for definition of INT, and ExpCS.

2.3.1.21. Names

An Unrestricted name is any name other than the OCL reserved keywords. See UnrestrictedName.

An Unreserved name is any name other than the OCL reserved keywords above or the OCL reserved types. See [UnreservedName](#).

If you need to use any of these names or non-alphanumeric names, you must use the escaped string syntax for a name: e.g. `_'true'`. The usual Java backslash escapes, with the exception of octal are supported: `_'new-lines\n\x0a\u000a'`

2.3.1.22. Comments

Single line comments are supported by ignoring all text following `--`.

Multi line comments are supported by ignoring all text within `/* ... */`.

Documentation comments are supported for all text within `/** ... */`. Unfortunately no documentation EAnnotation is currently created.

2.3.2. Limitations

OCLinEcore supports the full capabilities of Ecore, however the support for upper and lower bounds on generic types has not been adequately tested.

OCLinEcore provides primary syntaxes for some Ecore conventions such as genmodel annotations and constraints; much more support is needed for feature maps.

2.4. The Complete OCL Language

The Complete OCL provides a language for a document in which OCL complements an existing meta-model with invariants, and additional features.

2.4.1. Syntax

The Complete OCL syntax is defined by the OMG OCL 2.4 specification.

The syntax comprises keywords such as `context` followed by appropriate names and punctuation and OCL expressions.

With the exception of `endpackage` there is no terminating punctuation and so the consequences of a syntax error can be quite far-reaching while editing a document. Concentrate on the first error.

A substantial example of Complete OCL may be found by installing the [RoyalAndLoyal Example Project](#).

2.4.1.1. Grammar Implementation

The grammar used by the Xtext editors may be found at:

/src/org/eclipse/ocl/examples/xtext/completeocl/CompleteOCL.xtext

in the org.eclipse.ocl.examples.xtext.completeocl plugin. The Complete OCL grammar extends the Essential OCL grammar.

2.4.1.2. Complete OCL Document

The Document syntax defines a Complete OCL document, for which *.ocl is the default extension.

A Complete OCL document may

• import meta-models to be complemented

• include additional Complute OCL documents

• specify one or more Standard Library documents

and then provide complements for one of more Packages, Classifiers or Features.

The import, include and library declarations are Eclipse OCL extensions. The OCL 2.4 specification provides no mechanism for a Complete OCL document to reference external material.

The primary definitions of each meta-model may be imported by specifying the URI of a Package and optionally an alias for that Package.

The import may be from a *.ecore, *.uml or *.oclinecore file.

Additional documents complementing meta-model may be included by specifying the URI of the Complete OCL document.

Zero or more external libraries may be imported so that their definitions are merged to form a composite library of basic and extended evaluation capability.

The implicit import of the default OCL Standard Library is suppressed, if any library is imported. The default library may be extended by specifying it as the first library import.

```
library ocl : 'http://www.eclipse.org/ocl/3.1.0/OCL.oclstdlib'
```

The namespace URI of the first library package defines the namespace URI of the composite library. The namespace URI of subsequent library imports may not conflict, but may be null.

2.4.1.3. PackageDeclaration

The PackageDeclaration syntax identifies a Package to be complemented.

The package keyword is followed by the optionally qualified name of the package to be complemented.

The name is followed by the declaration contexts to be complemented and finally an endpackage keyword.

2.4.1.4. ContextDecl

The ContextDecl syntax identifies a model element to be complemented.

A complemented context may be a

- Classifier Context
- Operation Context
- Property Context

2.4.1.5. ClassifierContextDecl

The ClassifierContextDecl syntax identifies a Classifier to be complemented.

The context keyword is followed by an optional declaration of the name of the context variable. If omitted the context variable is named self.

Then the optionally qualified name of the classifier to be complemented is defined. Qualification is required if the classifier context is specified directly as part of the document. Qualification may be omitted when the classifier context is specified as part of a package declaration.

Finally the content of the classifier context may comprise

- **Def** to define an additional feature
- **Inv** to define an invariant

2.4.1.6. Def

The Def syntax defines an additional Feature for a Classifier.

The definition may define a static feature with a feature name.

A further name may be specified for no very obvious purpose other than symmetry with an invariant. The optional name is not used.

A parenthesized **parameter** list must be specified to define an operation and omitted for a property definition.

Then the property or optional operation return **type** is specified followed by the **specification** of the property initializer or operation body.

An additional definition is usable within an OCL expression as if it was defined in the complemented meta-model. For the purposes of reflection the additional appear as part of the complemented meta-model, however they remain complements and are not persisted with that meta-model.

2.4.1.7. Inv

The Inv syntax defines an invariant for a Classifier.

The inv keyword is followed by an optional invariant name an optional violation message and the **specification** of the invariant.

The optional name may be used by validation environments to identify the invariant in a control panel and in diagnostic messages.

The optional violation message provides an OCL expression that may be used by a validation environment to provide a custom message to explain a broken invariant. The severity of the invariant violationm may be controlled by the value of the invariant expression.

- true indicates that the invariant was satisfied

- false indicates that the invariant was violated with warning severity

- null indicates that the invariant was violated with error severity

- invalid indicates that the invariant failed to evaluate

In the Indigo release, the local variables of the invariant are not accessible to the violation message expression. This will be changed in a future release.

In the Indigo release, custom messages are available when a CompleteOCLEObjectValidator is used as the EValidator. This is not the case for validation in the Sample Ecore Editor and so a default message using the invariant name and the failing object is provided.

2.4.1.8. OperationContextDecl

The OperationContextDecl syntax identifies an Operation to be complemented.

The context keyword is followed by the optionally qualified name of the operation to be complemented. Qualification is always required since the operation context may be specified as part of the document or a package declaration but not a classifier.

The name is followed by a parenthesized parameter list.

Finally an optional return type and the operation constraints are specified. The operation constraints may comprise

- a Body to define operation body

- Pre to define a precondition on the operation

- Post to define a postcondition on the operation

Any number of preconditions and postconditions can be specified. Only one body is permitted.

2.4.1.9. Parameter

The Parameter syntax identifies a Parameter of an Operation to be complemented.

A parameter comprises an optional name and Essential OCL type declaration.

The parameter name may be omitted for Operation Contexts if the parameter name is not used by any of the constraints.

The parameter name is required for Operation Definitions.

Note that the type declarations are Essential OCL types such as `Sequence<String>` rather than UML's and OCLinEcore's `String[*] {ordered !unique}`. There are plans to unify these syntaxes.

2.4.1.10. Body

The Body syntax defines the body for a complemented Operation.

The body keyword is followed by an optional name and the body specification.

The optional name is not used.

2.4.1.11. Post

The Post syntax defines a postcondition for a complemented Operation.

The post keyword is followed by an optional name and the postcondition specification.

The optional name may be used by a validation environment to identify a failing postcondition.

The Indigo release parses and persists postconditions but does not evaluate them.

2.4.1.12. Pre

The Pre syntax defines a precondition for a complemented Operation.

The pre keyword is followed by an optional name and the precondition specification.

The optional name may be used by a validation environment to identify a failing precondition.

The Indigo release parses and persists preconditions but does not evaluate them.

2.4.1.13. PropertyContextDecl

The PropertyContextDecl syntax identifies a Property to be complemented.

The context keyword is followed by the optionally qualified name of the property to be complemented. Qualification is always required since the property context may be specified as part of the document or a package declaration but not a classifier.

Finally the property type and the property constraints are specified. The property constraints may comprise

- an Init to specify an initialization
- a Der to specify a derivation

An initialization is specified to define the property value when the property is created.

A derivation is specified to define the property value at all times.

It does not therefore make sense to specify both an an initial and an all-time value. If both are specified the derivation is used.

2.4.1.14. Init

The Init syntax defines an initial value for a complemented Property.

The init keyword and colon are followed by the initial value specification.

2.4.1.15. Der

The Der syntax defines a derived value for a complemented Property.

The der keyword and colon are followed by the derived value specification.

2.4.1.16. Specification

The Specification syntax provides an OCL expression to specify some aspect of a complemented model.

The specification comprises and Essential OCL Expression.

2.4.1.17. NavigatingExp

The NavigatingExp syntax defines enhancements to the Essential OCL NavigatingExp syntax.

The name of a model element may have a further @pre qualification for use within an operation postcondition. It allows the postcondition to access the value on entry to an operation.

`?` may be specified as the argument in a navigating expression to indicate unknown values when testing sent messages.

2.4.1.18. NavigationOperators

The Essential OCL NavigationOperators are extended to support

- `^` to test whether a message has been sent message
- `^^` to reference the content of a message

2.4.1.19. UnreservedName

The Complete OCL reserved words are unchanged from Essential OCL, consequently a Complete OCL Unreserved name is the same as an Essential OCL UnreservedName.

2.4.1.20. UnrestrictedName

The Complete OCL has two additional built-in types: `OclMessage` and `OclState`. These names and the Essential OCL RestrictedNames are not available without qualification or escaping.

2.5. The OCL Standard Library Language

The OCL Standard Library Language is used to define the OCL Standard Library, for which *.oclstdlib is the default extension.

The standard library can be replaced or extended.

The source for the OCL Standard Library may be found at model/OCL-2.5.oclstdlib in the org.eclipse.ocl.examples.library plugin.

2.5.1. Syntax

2.5.1.1. Grammar Implementation

The grammar used by the Xtext editors may be found at:

/src/org/eclipse/ocl/examples/xtext/oclstdlib/OCLstdlib.xtext

in the org.eclipse.ocl.examples.xtext.oclstdlib plugin. The OCL Standard Library grammar extends the Essential OCL grammar.

2.5.1.2. OCL Standard Library Document

The Library syntax defines an OCL Standard Library document, for which *.oclstdlib is the default extension.

Zero or more library documents may be imported for use within the composite library whose name must be specified.

A namespace prefix and namespace URI may optionally be specified.

The body of the document comprises

- optional module declaration
- optional specification of the OCL Standard libraries
- optional import of referenced Ecore or UML or OCLinEcore resources
- Precedences
- a hierarchy of Packages
- a hierarchy of Classifiers
- Annotations

Zero or more external libraries may be imported so that their definitions are merged to form a composite library of basic and extended evaluation capability.

The default library may be extended by specifying it as the first library import.

```
library 'http://www.eclipse.org/ocl/3.1.0/OCL.oclstdlib'
```

The namespace URI of the first library package defines the namespace URI of the composite library. The namespace URI of subsequent library imports may not conflict, but may be null.

2.5.1.3. Precedence

The Precedence syntax defines the precedence and associativity of infix operators.

Each entry in a list of precedences names a precedence level taht can then be used by an infix operator. Each level can be either left or right associative.

Multiple lists of precedence levels can be merged from imported libraries provided the lists are interleaveable with conflict or ambiguity.

2.5.1.4. Package

The Package syntax defines a nested hierarchy of packages and classifiers .

A Package has a name and optionally a namespace prefix and namespace URI.

The content of a Package may comprise Packages, Classifiers and Annotations.

2.5.1.5. Class and Classifier

The Class and Classifier syntax define a type within a Package.

A Class has a name and optionally template parameters. A class may also name the metatype such as `PrimitiveType` that the Class is an instance of.

A Class may extend one or more other Classes that may be specialized using the template parameters.

The content of a Class may comprise Operations, Properties, Invariants and Annotations.

2.5.1.6. Inv

The Inv syntax defines an invariant constraint.

2.5.1.7. Operation

The general Operation syntax defines a conventional Operation or Iteration.

2.5.1.8. LibOperation

The LibOperation syntax defines a conventional Operation.

An Operation may be static and has a name and optionally template parameters.

An Operation has zero of more Parameters.

An Operation has a return Type. An infix operation may specify a precedence level. An operation may specify the name of a Java class implementing the org.eclipse.ocl.examples.library.LibraryOperation interface. This class is used when evaluating the operation.

The content of an Operation may comprise Preconditions, Postconditions and Annotations.

The `static` qualifier supports declaration of static library operations such as `allInstances()` that are invoked on types rather than objects.

2.5.1.9. LibIteration

The LibIteration syntax defines an Iteration.

An Iteration has a name and optionally template parameters.

An Iteration has one or more comma-separated [Iterators](#).

Optionally following a semicolon, an Iteration has one or more comma-separated [Accumulators](#).

Optionally following a bar, an Iteration has one or more comma-separated [Parameters](#).

An Iteration has a return Type. An Iteration may specify the name of a Java class implementing the org.eclipse.ocl.examples.library.LibraryIteration interface. This class is used when evaluating the iteration.

The content of an Iteration may comprise [Preconditions](#), [Postconditions](#) and Annotations.

2.5.1.10. Iterator

The Iterator syntax defines an Iterator.

2.5.1.11. Accumulator

The Accumulator syntax defines an Accumulator.

2.5.1.12. Parameter

The Parameter syntax defines a Parameter.

2.5.1.13. Pre

The Pre syntax defines a precondition constraint.

PreCS — pre — UnrestrictedName — : — SpecificationCS — ;

2.5.1.14. Post

The Post syntax defines a postcondition constraint.

PostCS — post — UnrestrictedName — : — SpecificationCS — ;

2.5.1.15. LibProperty

The LibProperty syntax defines an Property.

LibPropertyCS — static — property — Name — : — TypedRefCS

An Property may be static and has a name and a Type.

=> — SINGLE_QUOTED_STRING — { — AnnotationElementCS — } — ;

A Property may specify the name of a Java class implementing the org.eclipse.ocl.examples.library.LibraryProperty interface. This class is used when evaluating the iteration.

The content of a Property may comprise Annotations.

2.5.1.16. Specification

The Specification syntax integrates an OCL Expression as the specification of a constraint.

SpecificationCS — ExpCS

2.6. Editors

The four editors are all generated using Xtext, and so exhibit similar behavior to other Eclipse editors.

The standard facilities are

- syntax coloring
- folding
- outline view
- hover text
- syntax validation
- semantic validation

The following facilities have partial functionality

- go to definition
- content assist
- templates
- quick fixes
- find references

The following facilities have little or no functionality

- rename element
- final validation

2.6.1. Syntax coloring

The editors use similar colors to JDT.

- green for comments
- bold purple for keywords
- grey for numbers
- blue for strings

Additionally

- italics for text referencing a definition

References for which the name of the definition matches a keyword use italics in the same way as other cross references. Names of a definition matching a keyword use bold purple in the same way as keywords.

The syntax coloring may be changed using the **Window->Preferences->OCL** pages.

2.6.2. Validation

Syntax errors are detected and offending text is underlined with accompanying annotations and problem markers.

If there are no syntax errors, semantic validation is performed with similar feedback of problems. Semantic validation is not performed when there are syntax errors since a single syntax error may provoke many hundreds of semantic errors. These can make the original syntax error difficult to resolve.

The use of the well-formedness rules for a final validation of the Abstract Syntax is only partially implemented, since correction of the OCL in the OMG specifiucation is still work in progress.

By default, the Xtext nature is not added to projects using OCL editors and so no builder runs in the background creating problem markers for OCL files. This is generally beneficial when you have many files for which the over-enthusiastic rebuilds waste build time, or experimental files for which the many errors clutter the Problem View.

If your OCL is good quality, you may activate the Xtext nature and builder by selecting the project and then invoking **Configure->Add Xtext Nature**.

2.6.3. Hover Text

Hover text has been implemented to provide feedback on the usage and type of expression terms. For instance hovering over the size operation in the example below reveals that it is an Operation for the Loan specialization of Collection .

(Note that the Class specialization for Loan is incorrectly shown again as an Operation specialization.)

2.6.4. Content Assist

Typing **Ctrl** and **Space** activates the Content Assist pop-up to offer suggestions as to what might be typed to the right of the cursor.

2.6.5. Code Templates

Code templates are provided for many of the major constructs and some expression elements.

You may define your own templates. If you would like to contribute them, please raise a Bugzilla.

2.6.6. Open Declaration

It is possible to navigate to a definition provided an editor is already open for the definition.

2.7. Console

There are two interactive OCL consoles that enable OCL expressions to be evaluated on a model.

The classic **Interactive Console** may be created by invoking **OCL->Show OCL Console** from the right button menu of some model editors such as the **Sample Ecore Model Editor**. Alternatively the **Console** view may be created by **Window->Show View->Console** followed by selecting **Interactive OCL** from the **Open Console** pull-down in the **Console** View tool bar. See the OCLinEcore Tutorial for detailed step-by-step pictures.

The Pivot **Interactive Xtext Console** may be similarly created by **OCL->Show Xtext OCL Console** from the menu or **Interactive Xtext OCL** from the pull-down.

The two consoles should exhibit similar behaviors, however not all facilities of the classic console have yet been reproduced on the new.

The Console, shown in the bottom half of the figure, comprises a combined Title and Tool Bar, Results Panel and Entry Panel.

2.7.1. Context Object Selection

Expressions are evaluated with respect to a context object `self` that has a corresponding metamodel type. This object is defined by selecting any widget whose implementation is adaptable to an EObject.

Therefore selecting an EAttribute in the Sample Ecore Editor will make the selected EAttribute `self` and EAttribute the metamodel type. In the figure selecting the Member named m1 in the Sample Reflective Ecore Model Editor has made Member the select type of `self` and m1 the selected context object. For the Pivot Console there is additional support to use selections from the Outline of an Xtext editor or Variables View of the OCL Debugger as the context object.

The Pivot Console displays the selected object and type in the Console title.

The classic Console relies on the platform selection mechanism to show the selected object in the overall Eclipse Status display at the bottom left of the workspace window. This display may be lost when the selection is changed to a non-EObject selection.

2.7.2. Editing

The bottom panel supports entry and evaluation of a multi-line expression. The expression is evaluated when **Enter** is entered.

The classic Console has hand-coded syntax highlighting and context assist that may be activated by typing **Ctrl** + **Space**.

The Pivot Console uses the Xtext EssentialOCL editor and largely auto-generated syntax highlighting, error indications, hover text, quick fixes and context assist that may be activated by typing **Ctrl** + **Space**.

The content assist for the Pivot Console has not yet been customized, so the classic Console content assist is probably more comprehensive, however the Pivot Console shares the same library definitions as the other editors and so is more consistent.

2.7.3. Editor Keys

The **Page-Up** and **Page-Down** keys may be used to scroll through the history of input commands enabling previous commands to be re-used. Use of the Page keys is necessary since the input is potentially multi-line and so **Up** and **Down** navigate over the multiple lines.

2.7.4. Results

The larger middle panel displays the results of each evaluation in a scrolling window.

2.7.5. Tool Bar

2.7.5.1. Ecore/UML binding

The classic Console provides a selection to determine whether the context object has a type defined by an Ecore or UML metamodel. This selection is not required for the Pivot Console which automatically converts Ecore or UML models to Pivot models.

2.7.5.2. M1/M2

The classic Console provides a selection to determine whether the selected metamodel binding is that for objects (M2) or types (M1). This selection is not needed for the Pivot Console since the Pivot metamodel is an instance of itself.

2.7.5.3. Clear Console

The standard clear console functionality clears the results pane.

2.7.5.4. Close Console

The standard close console functionality closes the current console.

2.7.5.5. Debug

Starts the OCL Debugger using the current mouse selection as self and the text in the Console input as the exopression to execute.

2.7.5.6. Load/Save an expression

The classic Console provides an ability to save and reload edited expressions as XMI files. The XMI is a pragmatic Eclipse Ecore realisation of the OCL specification for which XMI interchange is not realisable.

The Pivot Console provides a similar ability to save and reload edited expressions as XMI files. The XMI is a prototype that might evolve and be adopted by a future version of the OCL specification. *This functionality has not been properly tested.*

2.8. Validity View (new in Luna)

The standard EMF validation capabilities provide a useful overview of problems:

• as markers in the source model,

• as markers in the Problems View,

• in Pop-up dialogs.

The **Validity View** provides a much more detailed view of the problems and so assists in debugging bad models and/or bad constraints.

The **Validity View** may be shown by invoking **OCL->Show Validity View** from the right button menu of some model editors such as the **Sample Ecore Model Editor**. Alternatively the **Validity View** view may be created by **Window->Show View->Other... OCL->Validity View**.

The left-hand pane titled Model Elements provides a tree view of the Resources in a ResourceSet in a similar fashion to the Sample Ecore Editor. However an additional child element (in blue italics) is added for each constraint applicable to its parent element. Checkboxes enable or disable the element from re-validations and JUnit-like status icons show the status of the most recent validation. Hovertext provides further detail.

The right-hand pane titled Metamodel Constraints provides a tree view of the model hierarchies that contribute constraints. An additional child element is added for each model element to which the constraint applies.

The displays track the mouse selection in other views. Whenever the mouse selection can be resolved to an EObject, that EObject's ResourceSet populates the left hand pane and constraints affecting the left hand pane populate the right hand pane. Tracking the mouse selection is quite expensive, and probably irritating. It can be inhibited by pinning the view to the current selection.

There is generally much too much detail if all elements and constraints are considered and so the view provides many facilities to facilitate focusing on the interesting combinations.

2.8.1. View Tool Bar

The View Tool Bar is at the top and right of the view following the Validity View title. It provides facilities common to both Model Elements and Metamodel Constraints.

2.8.1.1. Expand All

The plus icon causes the Model Elements and Metamodel Constraints to be fully expanded to display all their contents. Beware that for large models this may result in slow screen updates.

2.8.1.2. Collapse All

The minus icon causes the Model Elements and Metamodel Constraints to collapse to display only their top level elements.

2.8.1.3. Pin

The pin icon toggles the track current cursor selection. When unpinned, the default, any change in mouse selection may cause recomputation of Model Elements and Metamodel Constraints contents. When pinned the contents are stable.

2.8.1.4. Refresh

The double arrow icon causes the Model Elements and Metamodel Constraints to be recomputed. This may be necessary for a metamodel change to be used.

2.8.1.5. Run

The white triangle in green circle icon runs a validation on all enabled model element/constraint combinations updating the status indications for constraints in the left hand Model Element and model elements in right hand Constraint pane.

2.8.1.6. Filter

The Filtering menu hides unwanted contributions to the display. Each of the validation result statuses can be individually enabled.

- Show all errors
- Show all infos
- Show all failures
- Show all warnings
- Show all successes

By default none of the selections are enabled so everything is shown. As soon as a specific status is enabled all display elements with other non-enabled statuses are hidden. Thus selecting just *Show all warnings" hides error/info/failure/success results.

2.8.1.7. Save

This functionality does not appear to work in Luna SR0.

The floppy disk icon supports export of the validation results.

The available export formats are extensible through the org.eclipse.ocl.examples.emf.validation.validity.validity_exporter extension point.

The default exporters support

html

An HTML file summarising the results.

model

An XMI model conforming to validity.ecore containing all results with references to the model elements and constraints.

text

A text file summarising the results.

2.8.2. Model Elements Pane

The Model Elements Pane is the left hand pane of the Validity View.

It comprises a title and tool bar, text filter and scrollable tree of model elements and their constraints.

2.8.2.1. Model Elements Tool Bar

The Model Elements Tool Bar is at the top and right of the left hand pane following the Model Elements title. It provides facilities specific to the Model Elements.

Expand All

The plus icon causes the Model Elements to be fully expanded to display all their contents. Beware that for large models this may result in slow screen updates.

Collapse All

The minus icon causes the Model Elements to collapse to display only their top level elements.

Enable All

The tick icon causes all Model Elements to be enabled and so included in the next validation.

Disable All

The no-tick icon causes all Model Elements to be disabled and so excluded from the next validation.

Show/Hide disabled

The document icon with a query controls whether disabled Model Element selections are visible. A diagonal strikethrough shows when selections are hidden.

By default disabled selections are hidden, which allows the unwanted root elements of large models to be unchecked and so hidden before a slow attempt is made to display them.

2.8.2.2. Text Filter

The text filter takes a StringMatcher pattern that selects which elements are visible. The pattern may contain

- a * to match zero or more characters
- a ? to match exactly one character
- a \ to escape the following character

2.8.2.3. Model Elements tree

The scrollable tree shows the containment hierarchy of all elements in the ResourceSet containing the model element identified by the mouse selection.

The +/- collapse/expand icons preceding each element enable interesting elements to be shown and others folded away.

Each element is preceded by a check box that enables its usage within the next validation run. All elements may be enabled or disabled using the icons in the Model Elements Tool Bar. Enabling/disabling individual elements enables/disables the element's descendants and propagates a partial enable/disable to the element's ancestors.

The checkbox is followed by a validation status icon.

- tick for validation successful
- red cross for validation unsuccessful but incomplete
- blue cross for validation failure (incomplete)
- amber warning for a validation warning
- question mark for no validation performed

The status icon is followed by an element-specific icon identifying its type and label.

Double-clicking a leaf Constraint in the left-hand pane makes the corresponding constraint and parent model-element visible in the right-hand pane.

2.8.2.4. Model Elements Context Menu

The context menu in the model elements tree offers the following facilities in addition to those also available in the toolbar.

Validate Selection

Revalidates all constraints applicable to the selected Model Element and its children.

This seems to revalidate all Model Elements regardless in Luna SR0.

Debug Single Enabled Selection

Launches the debugger for the selected Model Element and associated Constraint.

The entry is greyed out if more than one Constraint is selected, so the invocation should normally be made from a leaf Constraint result.

Debug launching is only available for OCL constraints in Luna SR0.

Show in Editor

Opens an editor for the selected Model Element or Metamodel Constraint.

Opening is not available for all forms of constraint in Luna SR0.

2.8.3. Metamodel Constraints Pane

The Metamodel Constraints Pane is the right hand pane of the Validity View.

It comprises a title and tool bar, text filter and scrollable tree of metamodel constraints and the model elements to which they apply.

2.8.3.1. Metamodel Constraints Tool Bar

The Metamodel Constraints Tool Bar is at the top and right of the right hand pane following the Metamodel Constraints title. It provides facilities specific to the Metamodel Constraints.

Expand All

The plus icon causes the Metamodel Constraints to be fully expanded to display all their contents. Beware that for large models this may result in slow screen updates.

Collapse All

The minus icon causes the Metamodel Constraints to collapse to display only their top level elements.

Enable All

The tick icon causes all Metamodel Constraints to be enabled and so included in the next validation.

Disable All

The no-tick icon causes all Metamodel Constraints to be disabled and so excluded from the next validation.

Show/Hide disabled

The document icon with a query controls whether disabled Metamodel Constraints selections are visible. A diagonal strikethrough shows when selections are hidden.

By default disabled selections are hidden, which allows the unwanted root elements of large metamodels to be unchecked and so hidden before a slow attempt is made to display them.

2.8.3.2. Text Filter

The text filter takes a StringMatcher pattern that selects which elements are visible. The pattern may contain

- a * to match zero or more characters
- a ? to match exactly one character
- a \ to escape the following character

2.8.3.3. Metamodel Constraints tree

The scrollable tree shows the containment hierarchy of all constraints applicable to model elements in the ResourceSet containing the model element identified by the mouse selection.

The +/- collapse/expand icons preceding each element enable interesting elements to be shown and others folded away.

Each element is preceded by a check box that enables its usage within the next validation run. All elements may be enabled or disabled using the icons in the Model Elements Tool Bar. Enabling/disabling individual elements enables/disables the element's descendants and propagates a partial enable/disable to the element's ancestors.

The checkbox is followed by a validation status icon.

- tick for validation successful
- red cross for validation unsuccessful but incomplete
- blue cross for validation failure (incomplete)
- amber warning for a validation warning
- question mark for no validation performed

The status icon is followed by an element-specific icon identifying its type and label.

Double-clicking a leaf Model Element in the right-hand pane makes the corresponding Model Element and parent Metamodel Constraint visible in the left-hand pane.

2.8.3.4. Metamodel Constraints Context Menu

The context menu in the metamodel constraints tree offers the following facilities in addition to those also available in the toolbar.

Validate Selection

Revalidates all model elements applicable to the selected constraint and its children.

This seems to revalidate all Model Elements regardless in Luna SR0.

Debug Single Enabled Selection

Launches the debugger for the selected Model Element and associated Constraint.

The entry is greyed out if more than one Constraint is selected, so the invocation should normally be made from a leaf Model Element result.

Debug launching is only available for OCL constraints in Luna SR0.

Show in Editor

Opens an editor for the selected Model Element or Metamodel Constraint.

Opening is not available for all forms of constraint in Luna SR0.

2.8.4. Constraint Locators

The constraints displayed in the right hand pane are located by constraint locators that are registered with the org.eclipse.ocl.examples.emf.validation.validity.constraint_locator extension point. A constraint locator implements org.eclipse.ocl.examples.emf.validation.validity.locator.ConstraintLocator or the org.eclipse.ocl.examples.emf.validation.validity.ui.locator.ConstraintUILocator to define location, presentation, execution and debug launching of a particular kind of constraint.

Constraint locators are associated with metamodel namespaces which are determined by the nsURI of the EPackage that contains the EClass of a Model Element EObject. Constraint locators may be registered for a particular metamodel namespace or for no namespace. Those registered for no namespace are activated whenever a namespace is encountered for which no specific constraint locators are registered.

The following Constraint Locators are available by default.

2.8.4.1. org.eclipse.ocl.examples.emf.validation.validity.locator.EClassConstraintLocator

This constraint locator supports discovery of constraints realized by invariant EOperations in the Java code generated by an EMF genmodel.

2.8.4.2. org.eclipse.ocl.examples.emf.validation.validity.locator.EValidatorConstraintLocator

This constraint locator supports reflective discovery of validateXXXX methods in the Java code generated by an EMF genmodel using the EValidatorRegistry to identify the relevant Java code.

2.8.4.3. org.eclipse.ocl.examples.validity.locator.DelegateUIConstraintLocator

This constraint locator supports OCL constraints represented as EAnnotations in Ecore metamodels.

2.8.4.4. org.eclipse.ocl.examples.validity.locator.PivotUIConstraintLocator

This constraint locator supports discovery of org.eclipse.ocl.examples.pivot.Constraint classes in Pivot metamodels.

2.8.4.5. org.eclipse.ocl.examples.validity.locator.UMLUIConstraintLocator

This constraint locator supports discovery of org.eclipse.uml2.uml.Constraint classes in UML metamodels.

2.9. Debugger (new in Luna)

The OCL debugger supports debugging OCL constraints. It is a customization of the standard Eclipse debugger and so most of the facilities should be familiar to users of the Eclipse Java debugger.

The screenshot shows

- Debug Stack Trace showing the context of nested evaluation environments
- Variables View showing intermediate and local variables
- Editor showing input and context after a couple of steps
- Outline showing the Concrete Syntax Tree context

The OCL Debugger is very new, there are no doubt many opportunities for ergonomic improvements and bug fixes. Please raise a [Bugzilla](#) *.*

2.9.1. Launching

Launching the debugger for an OCL constraint requires the user to provide two pieces of information

- the expression or constraint to evaluate

• the self object upon which to operate

These may be provided in a variety of ways

2.9.1.1. Selected model object and manually entered expression

An arbitrary OCL expression may be entered in the Xtext OCL Console and evaluated on a model object selected using a mouse selection. The Debugger is invoked from the debug icon on the Console Tool Bar.

Clicking the debug icon creates a dummy Complete OCL file and then launches the debugger. The expression is encapsulated as an oclDebugExpression operation extension to the type of the selected object. The file provides the source for source level debugging. The console may be re-used while debugging.

2.9.1.2. Selected model object/constraint combination

The Validity View provides fine-grained display of the evaluation of each constraint applicable to a model element and vice-versa. One of these model element/constraint combinations may be selected and the debugger launched using **Debug Single Enabled Selection** to investigate why validation is producing unexpected results.

2.9.1.3. Selected model object and selected constraint

An OCL Expression launch configuration may be created to select a model element and a constraint for execution or debugging.

The launch configuration may be created using **Run->Run Configurations...** or **Debug->Debug Configurations...** from the Eclipse Menu Bar. This requires both Model Element and Constraint to be selected separately.

Alternatively the context menu in model editors offers an **OCL->Debug...** option that creates a Debug Configuration in which the Model Element is pre-selected from the invoking context.

2.9.2. Stepping

OCL expressions can be very compact and generally occur embedded in a larger application. The debugger is therefore optimized for this usage.

Rather than the line-based stepping typical of the Java debugger, the OCL debugger supports term by term stepping, highlighting the next term to be evaluated and showing the intermediate results as $-prefixed names in the Variables View.

The OCL debugger interpretation of the Step functionalities is adjusted to facilitate stepping to many points in a complex expression without needing to reformat the source with line breaks..

The Example Debugger View shows the imminent execution of ".size()" after stepping into "self" and ".name".

2.9.2.1. Step Into

A single OCL AST node is executed. The results can be inspected as inputs of a subsequent AST node.

2.9.2.2. Step Over

Execution proceeds until the next OCL AST node is associated with a new source line number.

2.9.2.3. Step Return

Execution proceeds until the next OCL AST node is associated with a reduced stack depth. Iterations introduce nested stack entries so step return can step out of an iteration. let expressions and nested OCL calls also introduce additional stack nesting.

2.9.2.4. Resume

Execution proceeds until the next breakpoint.

2.9.3. Variables View

The Variables View enables the local variables and intermediate results to be examined using OCL syntaxes such as single quotes for Strings.

The [Example Debugger View](#) shows the "self" variable, which is an "ecore::Package" instance, opened to show its fields, amongst which the name is 'tutorial'.

Intermediate variables are named using the property name of the subsequent AST node's input. Thus "$source" shows the OperationCallExp.source input already computed as "self.name". Multiple inputs are diasmbiguated by suffixing as in "$argument[0]".

"$pc" identifies the next instruction, which can be examined in just the same way as any other variable.

2.9.4. Breakpoints View

Line breakpoints can be set in the Complete OCL editor and examined in the Breakpoints View. Execution stops when an OCL AST node has been executed that is associated with the line of a breakpoint.

No filtering facilities are yet available.

2.9.5. Outline View

The Outline currently shows the OCL Concrete Syntax Tree which is structurally similar to the Abstract Syntax Tree that is executed. .

It would be more useful to show the AST and support Node breakpoints on it.

2.10. OCL Integration

The [OCLinEcore Editor](#) editor enables OCL to be embedded in Ecore. This section explains how that OCL is executed.

The [Complete OCL](#) editor enables OCL to be provided as a complementing document. This section explains how that complement is installed to become part of the complemented model.

The [Interactive OCL](#) console allows you to load OCL and execute OCL expression interactively.

The [Java API](#) explains how you can take control of the OCL installation and activation.

2.10.1. OCL execution in Ecore / EMF Delegates

The EMF delegate mechanisms and EAnnotations that enable EMF to delegate to OCL to support

• validation of invariants

• execution of operation bodies

• evaluation of property initial and derived values

are described in the [Delegates](#) section of the Programmers Guide.

2.10.2. Custom Validation Messages

Eclipse OCL supports the production of custom messages by defining a String-valued message expression as a parenthesized clause on an invariant.

2.10.2.1. Underlying support

An OCL invariant is an expression that returns a true or false value.

In Juno and Kepler, Eclipse OCL supported an extension whereby a null return indicated an 'error' rather than a 'warning', and an invalid return was 'fatal'.

Luna supports a rich-invariant idiom whereby an invariant can compute a tuple of results, only one of which is actually returned by tooling that does not understand the idiom. Rather than

```
invariant InvariantName:
 boolean-valued-invariant-expression;
```

You can code additional information by recoding

ocl-status-expression

as

```
invariant InvariantName:
 Tuple{
     status=boolean-valued-invariant-expression,
     message=string-valued-message-expression,
     severity=integer-valued-severity-expression, -- -ve error,0 ok,+ve warn
     ...                                -- more custom fields as desired
 }.status;
```

The idiom is a little verbose, but compatible with all OCL tooling. Eclipse OCL provides some editor enhancements to make the usage more acceptable.

2.10.2.2. Editor syntax

In the OCLinEcoreTutorial Example there is an alternative syntax for custom messages.

```
invariant SufficientCopies:
 library.loans->select((book = self))->size() <= copies;
```

may be changed to

```
invariant SufficientCopies('There are '
 + library.loans->select((book = self))->size().toString()
 + ' loans for the ' + copies.toString() + ' copies of \'' + name + '\''):
 library.loans->select((book = self))->size() <= copies;
```

to replace the default diagnostic:

```
The 'SufficientCopies' constraint is violated on 'Book b2'.
```

by

```
There are 3 loans for the 2 copies of 'b2'.
```

Unfortunately, in the Luna release, EMF does not support this customization. This must be activated explicitly using an EValidator that is aware of the ValidationDelegateExtension extended API. This is available by using the OCLinEcoreEObjectValidator.

2.10.3. CompleteOCL Validation

Integration of Complete OCL documents is harder because Complete OCL complements pre-existing models. These cannot always be aware of the existence of that complement, since the author of a model cannot know what complements may be added by its users.

The complete model formed from the primary models and the OCL complements is application-specific and so applications must gather the contributions together. Prior to the Indigo release, this restricted Complete OCL usage to Java applications that could gather the complements.

The CompleteOCLEObjectValidator may be used to install a Complete OCL document.

In many editors an **OCL->Load Document** is available in the context menu to facilitate loading a complementary Complete OCL document.

You may drag and drop one or more files from within Eclipse or outside Eclipse into the dialog, or use one of the browser buttons to locate a Complete OCL document.

2.10.3.1. Browse Registered OCL Files...

The org.eclipse.ocl.examples.xtext.completeocl.complete_ocl_registry may be used to register Complete OCL files against the nsURIs that they complement. These extension points may be defined in plugins or

projects. In either case clicking **Browse Registered OCL Files...** presents a list of registered Complete OCL documents applicable to the context from which the dialog was invoked.

2.10.3.2. Browse File System...

The **Browse File System...** button present a file system explorer so that a Complete OCL document file can found anywhere.

2.10.3.3. Browse Workspace...

The **Browse Workspace...** button present a workspace explorer so that a Complete OCL document file can found within the workspace.

2.10.4. OCLinEcore for Xtext Validation

If you want to use OCLinEcore as a validation language for Xtext you must:

Use a manually maintained Ecore model to define your parsed grammar model, otherwise your embedded OCL will be lost each time you regenerate the editor. For non-trivial models, switching from auto-generated to manual maintenance is a good idea, since you may need to control changes carefully to maintain upward compatibility for existing models.

Modify the Validator class generated by genmodel to extend OCLinEcoreEObjectValidator rather than EObjectValidator. See OCLinEcoreEObjectValidator for details.

2.10.5. Complete OCL for Xtext Validation

If you want to use Complete OCL as a validation language for Xtext, you may use the CompleteOCLEObjectValidator to register the Complete OCL for EMF Validation. This may readily be achieved by reusing the empty example JavaValidator created by Xtext to install the Complete OCL. If your Xtext language is *States*, and your Complete OCL is *model/States.ocl* in *StatesProject* you should change your StatesJavaValidator to:

```
public class StatesJavaValidator extends AbstractStatesJavaValidator
{
    @Override
    public void register(EValidatorRegistrar registrar) {
        super.register(registrar);
        StatesPackage ePackage = StatesPackage.eINSTANCE;
        URI oclURI = URI.createPlatformResourceURI(
            "/StatesProject/model/States.ocl", true);
        registrar.register(ePackage,
            new CompleteOCLEObjectValidator(ePackage, oclURI));
    }
}
```

2.11. OCL in UML (using Papyrus)

(This documentation applies to Papyrus 1.0.0.)

The behaviour of a UML model may be elaborated using OCL to define

- operation bodies
- property derivations/initializers
- class invariants to be observed by user model instances
- stereotype invariants to be observed by user model elements
- guards for state machines

2.11.1. UML Integration

Although the UML metamodel makes extensive use of OCL to specify its own well-formedness, there is no explicit ability to use OCL within UML. Usage of OCL, or any other language, is enabled by the flexibility of the ValueSpecification class and the OpaqueExpression extension.

The metamodel specifies the usage of a ValueSpecification wherever a value can sensibly be provided by a variety of technologies. Simple values can be provided by, for instance, a LiteralString or LiteralInteger.

More interesting values by an OpaqueExpression that has two interesting list features, one of language names and the other of string bodies in the corresponding language. The lists provide an ability to provide implementations in a variety of languages. In practice only one is used and if the language name is omitted, an implementation default of OCL is assumed.

Specification of a behaviour such as "name.toUpper()" can be achieved by an OpaqueExpression in which the language is Sequence('OCL') and the body is Sequence('name.toUpper()'). The OCL is therefore embedded in a textual form that has no knowledge of the classes in the OCL metamodel.

Users of the OCL Java API may avoid the need to incur OCL parsing costs by exploiting OCL's ExpressionInOCL class that extends ValueSpecification and delegates functionality to an OCLExpression.

2.11.2. Class Diagram

2.11.2.1. Class Invariant

A class invariant specifies a constraint that must be true for all well-formed instances of the class. It is specified in Papyrus, by:

- create a Constraint Node on a Class Diagram
  - select Constraint on palette
  - click on diagram where you want it
  - click on the Class you want as the Constraint context
- optionally replace the auto-generated Constraint name
  - select the Constraint
  - type a new name in the Properties View
- define the Specification of the Constraint with OCL text
  - select the Constraint
  - type F2 (or click again) to open the Essential OCL editor
  - enter the required constraint text
  - click outside the editor to close

The «Context» link provides a graphical view of the Context selection in the Properties View. It is the context that defines the type of OCL's `self` and so defines what is constrained.

You may edit the OCL text using direct edit as described above or from The Properties View. (Note that the editor has a significant start up time on the first usage, so be patient.)

Your OCL text entry is validated automatically; an error or warning marker will be shown on the Constraint if it is not satisfactory. Once you have corrected the errors you may need to invoke **Validate->Model Tree** to make the marker go away.

2.11.2.2. Operation Precondition, Postcondition and Body

Preconditions specify constraints that must be satisfied before operation execution starts.

Postconditions specify constraints that must be satisfied after operation execution finishes. Postconditions may use the reserved parameter name `result` to refer to the one result permitted by OCL. The @pre suffix may be used to refer to the state of variables prior to execution of the operation.

In OCL, a body-expression defines the functionality of a query operation as a result-type-valued expression such as `some-computation`. In contrast in UML, a body-condition defines the functionality of the operation as a Boolean-valued constraint on the result such as `result = (some-computation)`. Papyrus supports the OCL interpretation and so the `result = (...)` wrapper may be omitted.

In Papyrus, once the operation has been defined, preconditions, postconditions and a body-condition are all drawn by

- create a Constraint Node on a Class Diagram
  - select Constraint on palette
  - click on diagram where you want it
  - type Esc since context links cannot be drawn to operations
- optionally replace the auto-generated Constraint name
  - select the Constraint
  - type a new name in the Properties View
- define the Constraint Context
  - select the Operation
  - use the appropriate Add Elements (+ icon) for Precondition or Postcondition, or the Body condition **...** browser to locate the constraint
- define the Specification of the Constraint with OCL text
  - select the Constraint
  - type F2 (or click again) to open the Essential OCL editor
  - enter the required constraint text
  - click outside the editor to close

Note that the context of Operation Constraints must be specified by assigning a Constraint to one of the precondition/postcondition/bodycondition roles. Assignment of the context of the constraint directly fails to allocate the constraint to its role.

Note that in Papyrus 1.0, there is no stereotype display to indicate the precondition/postcondition/body-condition role.

Note that the OCL expressions for preconditions and postconditions should be Boolean-valued. The result-valued body-expression form should be used for a body-condition.

The owning type of the Operation is used as OCL's `self` context.

The Operation should be a query if a body-condition is provided.

In Luna, use of `result` *within postconditions incorrectly reports an unknown property. The error can be ignored.*

2.11.2.3. Property Initializers

An OpaqueExpression whose value is an OCL expression string can be used to define the default or derived value of a Property initializer.

- select the Property to make the Properties View relevant

- click the Create a new Object (+ icon) for the Default value

- Select OpaqueExpression from the menu

- click the Add elements (+ icon) for the Language

- select OCL in the left pane and click the right arrow to move to the right pane

- click OK

- enter the OCL text in the large pane

- click OK

Unfortunately, in Luna, the context does not appear to be correctly set for editor, so there is an error on self and no syntax help.

2.11.2.4. Profile Constraint

A Profile Constraint is very similar to a Class Invariant. However since the Profile is Constraint is drawn at M2, it may be evaluated at M1 to check a UML Class Diagram for consistency. In contrast a Class Invariant drawn at M1, may be evaluated by user tooling at M0 to validate user models. It is specified in Papyrus, by:

- create a Constraint Node on a Profile Diagram
  - select Constraint on palette
  - click on diagram where you want it
  - click on the Stereotype you want as the Constraint context
- optionally replace the auto-generated Constraint name
  - select the Constraint
  - type a new name in the Properties View
- define the Specification of the Constraint with OCL text
  - select the Constraint
  - type F2 (or click again) to open the Essential OCL editor
  - enter the required constraint text
  - click outside the editor to close

The OCL text can also be edited within the Properties View.

2.11.3. State Machine Diagram

The primary element of a StateMachine diagram is the StateMachine, which is a Type, but does not normally have Properties. A StateMachine should therefore be defined as a nested type of a containing type. This may be achieved within Papyrus Model Explorer by dragging the StateMachine to be a child of a Class.

2.11.3.1. Statemachine Constraint

A Constraint may be applied to a Statemachine in the same way as for a Class to specify an invariant of the Statemachine.

2.11.3.2. Statemachine Transition Guard

The guard condition of a Statemachine Transition may be specified by associating a Constraint with a Transition. The Transition should already exist and the Statemachine should be a nested type of a suitable type for OCL's `self`. The guard condition is drawn in Papyrus by

- create a Constraint Node on a StateMachine Diagram
  - select Constraint on palette
  - click on diagram where you want it
  - optionally enter the required constraint text
  - type Esc to close editor
- optionally replace the auto-generated Constraint name
  - select the Constraint, if not already selected
  - type a new name in the Properties View
- define the Constraint Context
  - select the Constraint, if not already selected
  - use the Context **...** browser in the Properties View to locate the transition
- define the Specification of the Constraint with OCL text
  - select the Constraint, if not already selected
  - type F2 (or click again) to open the Essential OCL editor
  - enter the required constraint text
  - click outside the editor to close

The required Transition is specified as the Guard of the Transition.

The owning type of the Statemachine defines OCL's `self`. In the absence of an owning type `self` will be undefined and OCL constraint validation will fail. You must therefore ensure that the StateMachine has a Class parent and that the Class has the required properties; `name` for this example. Once Class and properties are defined using a Class diagram. The

2.12. User Interface

The user interface comprises

- [Editors](#)
- [Console](#)
- [Debugger](#)
- [Validity View](#)
- [Workspace Preference Pages](#)
- [Project Property Pages](#)
- [OCL->Load Document Menu Action](#)

2.12.1. Project Property Pages

The Project Property Pages are accessible by invoking **Properties** from the right button context menu of a project.

In principle, it is possible to specify project-specific settings, however in practice is not often possible for application code to determine the prevailing project. Project-specific properties are therefore often ignored and may be removed in a future release.

The Property pages are:

- [Overall Options](#)
- [OCLinEcore editor Options](#)
- [Options applicable to the Ecore and UML bindings](#)
- [Options applicable to just the UML bindings](#)
- [The Model Registry](#)

2.12.2. Workspace Preference Pages

The Workspace Preference Pages are accessible by invoking **Preferences** from the **Window** menu on the toolbar.

The Preference pages are:

- [Overall Options](#)
- [OCLinEcore editor Options](#)
- [Options applicable to the Ecore and UML bindings](#)
- [Options applicable to just the UML bindings](#)
- [Editor Syntax Coloring](#)
- [Editor Templates](#)

2.12.3. Overall Options

The two overall options are independent of the Ecore/UML/Pivot bindings.

2.12.3.1. Default Delegation Mode

The Eclipse OCL project provides two execution engines which may be used to support EMF Delegates.

http://www.eclipse.org/emf/2002/Ecore/OCL/LPG

EMF Delegate annotations referencing the `http://www.eclipse.org/emf/2002/Ecore/OCL/LPG` URI are serviced by the classic evaluator that uses the LPG parser.

This URI was introduced in the Indigo release.

http://www.eclipse.org/emf/2002/Ecore/OCL/Pivot

EMF Delegate annotations referencing the `http://www.eclipse.org/emf/2002/Ecore/OCL/Pivot` URI are serviced by the new experimental evaluator that uses the UML-aligned Pivot model.

This URI was introduced in the Indigo release and was imposed by the Indigo OCLinEcore editor.

http://www.eclipse.org/emf/2002/Ecore/OCL

EMF Delegate annotations referencing the `http://www.eclipse.org/emf/2002/Ecore/OCL` URI are serviced by the evaluator selected on the preference page by the [Default Delegation Mode](#).

This URI was introduced in the Helios release and was imposed by the Helios OCLinEcore editor.

Use of an Indigo or Juno editor converts the URI to use the Pivot evaluator.

In Kepler, a prevailing URI in the input file is preserved, unless changed by the context menu setting. If no prevailing URI exists a default is determined by an OCLinEcore preference setting that defaults to the Pivot evaluator.

2.12.3.2. Code Generation Mode

Juno introduced an experimental ability to replace the delegated interpreted execution of OCL by direct execution of compiled Java code. This facility has been substantially improved and tested for the Kepler release.

Optimisations for Luna included inlining the bodies directly into the EMF Impl classes; the suggestion "Generate Java Code in xxxBodies classes" should therefore read "Generate Java Code in xxxImpl classes".

Further optimisations are scheduled for Mars.

This option may be selected to change the realization of OCL option.

Delegate for interpretation at run-time

Selecting the default delegation mode retains the Helios and Indigo functionality whereby **genmodel** generates Java code that encodes the OCL expressions as text strings. Each expression is lazily compiled at run-time with the result being cached to reduce overheads for repeated execution.

Generate Java code in xxxBodies classes

Selecting Java code generation causes **genmodel** to run Xtend templates that generate

- a *Package* Tables.java file

- inline OCL implementations within the *Class* Impl.java files

The tables file contains an optimised model representation allowing polymorphic operations to be dispatched in constant time.

The implementation files contain Java code corresponding to each OCL expression defining operation bodies or property initializers.

Disclaimer: the generated code is experimental has yet to be optimized and so is only about five times faster than the interpreted execution.

2.12.4. Ecore and UML Options

The options for the Ecore and UML bindings.

Ecore and UML Bindings

Configure the severities for problems diagnosed by the LPG parser.

Reference the defined property or operation in a def: expression as a constrained element of the constraint, in addition to the context classifier.	False
Interpolate <, <=, >, and >= operations when a model type defines a Java-style compareTo(...) operation.	False
Allow Integer Literals that exceed 32-bit limits.	False
Warn when the OCL 2.1 parsing of distinct xor, or, and precedences leads to a different parse to the OCL 2.0 specification of all levels equal.	False
Resolve package qualification by outward name lookup as specified by OCL 2.2, and/or by alias from an import declaration.	By Name
Process Java-like backslash escape sequences as specified by OMG Issue 14357 for OCL 2.3	True
Accept 'static' as part of a definition constraint as specified for OCL 2.2.	True
Treat operation overload resolution as a compilation error, rather than an arbitrary selection of the first best match.	False
Use of the closure() iterator specified by OCL 2.3.	Ok
Use of the toUpper() and toLower() operations on Strings.	Warning
Use of " escape sequence for single-quotes in string literals.	Warning
Use of "..." escape sequence for element names consisting of multiple OCL tokens.	Warning
Ambiguity when an unnavigable but named association end has the same name as the implicit name of an unnamed association end.	Error
Declaring (using the concrete syntax) an operation or property context in a classifier that inherits the feature (rather than declaring a redefinition of the feature as the context). This is allowed by the MDT OCL implementation but is not, strictly speaking, well-formed OCL.	Warning
Use of an operation name conceptually as in 7.4.8.	Error
any() return value when nothing is selected, "invalid" is correct Use "null" to retain the erroneous pre-Kepler resolution of the OCL 2.3.1 ambiguity.	null
Closure result includes the sources as specified by OCL 2.3 rather than the traditional Classic OCL behavior of excluding them.	False
Implement lax handling of null values in certain OclAny-defined operations.	True
Use the actual (dynamic) rather than the declared (static) source type to select the called operation.	False
Static instance for the implicit-root-class option token.	null

2.12.5. UML Options

The options for the UML binding.

UML Binding

Configure the severities for problems diagnosed by the LPG parser.

UML metaclass to consider as an OCL Association Class.	Association
Working with M1 instance models or M0 objects.	Automatically determine the effective modeling level from the context element.

2.12.6. Model Registry

The Model Registry is now deprecated.

2.12.7. Syntax Coloring

The standard Xtext syntax coloring facilities are provided for each of the OCL editors.

2.12.8. Editor Templates

The standard Xtext editor template facilities are provided for each of the OCL editors.

2.12.9. OCLinEcore Options

The options for the OCLinEcore editor.

OCL embedded in Ecore can be executed with either the Classic evaluator or the new Pivot evaluator depending on the URI used to define the embedded EAnnotations. This preference determines the URI written to Ecore files when no URI was previously in use.

Selecting `http://www.eclipse.org/emf/2002/Ecore/OCL` makes no choice and so defers to the user's run-time delegation choice.

Selecting `http://www.eclipse.org/emf/2002/Ecore/OCL/Pivot` is recommended since the OCLinEcore editor and Pivot evaluator both use the Xtext parser. This should avoid problems whereby not all facilities of the new Pivot grammar are supported by the Classic grammic or LPG evaluator.

Selecting `http://www.eclipse.org/emf/2002/Ecore/OCL/LPG` may be appropriate if evaluation using the classic LPG evaluator is important.

Chapter 3. The OCL Standard Library

This documentation on the OCL Standard Library is auto-generated from the org.eclipse.ocl.examples.library/model/OCL-2.5.oclstdlib that defines the behaviour of the Pivot evaluator and the Xtext editors. It is similar to the OCL 2.4 functionality. It is a prototype of functionality for OCL 2.5 where the use of models may eliminate ambiguities.

The library support for the Ecore and UML bindings in Luna has been upgraded so that the available operations are similar to those documented here for the Pivot binding.

3.1. Precedences

NAVIGATION > UNARY > MULTIPLICATIVE > ADDITIVE > RELATIONAL > EQUALITY > AND > OR > XOR > IMPLIES

3.2. `Bag(T)`

A bag is a collection with duplicates allowed. That is, one object can be an element of a bag many times. There is no ordering defined on the elements in a bag. Bag is itself an instance of the metatype BagType.

conformsTo `Collection(T)`

Operations

`=(object2 : OclSelf) : Boolean` precedence: EQUALITY

True if `self` and bag contain the same elements, the same number of times.

`<>(object2 : OclSelf) : Boolean` precedence: EQUALITY

`excluding(object : OclAny[?]) : Bag(T)`

The bag containing all elements of `self` apart from all occurrences of object.

`excludingAll(objects : Collection(OclAny)) : Bag(T)`

The bag containing all elements of `self` apart from all occurrences of all objects.

`flatten(T2)() : Bag(T2)`

Redefines the Collection operation. If the element type is not a collection type, this results in the same bag as `self`. If the element type is a collection type, the result is the bag containing all the elements of all the recursively flattened elements of `self`.

`including(object : T[?]) : Bag(T)`

The bag containing all elements of `self` plus object.

`includingAll(objects : Collection(T)) : Bag(T)`

The bag containing all elements of `self` and objects.

`selectByKind(TT)(type : Metaclass(TT)) : Bag(TT)`

`selectByType(TT)(type : Metaclass(TT)) : Bag(TT)`

Iterations

`closure(i : T | lambda : Lambda T() : Set(T)) : Set(T)`

The closure of applying body transitively to every distinct element of the source collection.

`collect(V)(i : T[?] | lambda : Lambda T() : V[?]) : Bag(V)`

`collectNested(V)(i : T[?] | lambda : Lambda T() : V[?]) : Bag(V)`

The Bag of elements which results from applying body to every member of the source nonordered collection.

`reject(i : T[?] | lambda : Lambda T() : Boolean) : Bag(T)`

The sub-bag of the source bag for which body is `false`.

```
self->reject(iterator | body) = self->select(iterator | not body)
```
.

`select(i : T[?] | lambda : Lambda T() : Boolean) : Bag(T)`

The sub-bag of the source bag for which body is `true`.

```
self->select(iterator | body) =
self->iterate(iterator; result : Bag(T) = Bag{} |
if body then result->including(iterator)
else result
endif)
```

```
sortedBy(i : T[?] | lambda : Lambda T() : OclAny) : Sequence(T)
```

Results in the Sequence containing all elements of the source collection. The element for which body has the lowest value comes first, and so on. The type of the body expression must have the < operation defined. The < operation must return a Boolean value and must be transitive (i.e., if a < b and b < c then a < c).

3.3. `Boolean`

The standard type Boolean represents the common true/false values. Boolean is itself an instance of the metatype PrimitiveType (from UML).

conformsTo OclAny

Operations

```
=(object2 : OclSelf) : Boolean precedence: EQUALITY
```

Returns `true` if the logical value of `self` is the same as the numeric value of object2, `false` otherwise.

```
<>(object2 : OclSelf) : Boolean precedence: EQUALITY
```

Returns `true` if the logical value of `self` is the not same as the numeric value of object2, `false` otherwise.

```
allInstances() : Set(OclSelf)
```

Returns Set{false, true}.

```
and(b : Boolean[?]) : Boolean[?] invalidating validating precedence: AND
```

`false` if either `self` or b is `false`. Otherwise `invalid` if either `self` or b is `invalid`. Otherwise `null` if either `self` or b is `null`. Otherwise `true`.

```
body: if self.oclIsInvalid() then
        if b.oclIsInvalid() then self
        else if b = false then false
        else self
        endif endif
      else if self = false then false
      else if b.oclIsInvalid() then b
      else if b = false then false
      else if self = null then null
      else if b = null then null
      else true
      endif endif endif endif endif endif
```

```
implies(b : Boolean[?]) : Boolean[?] invalidating validating precedence:
IMPLIES
```

`true` if `self` is `false`, or if b is `true`. Otherwise `invalid` if either `self` or b is `invalid`. Otherwise `null` if either `self` or b is `null`. Otherwise `false`.

```
body: if self.oclIsInvalid() then
        if b.oclIsInvalid() then self
        else if b = true then true
        else self
        endif endif
      else if self = false then true
      else if b.oclIsInvalid() then b
      else if b = true then true
      else if self = null then null
      else if b = null then b
      else false
      endif endif endif endif endif endif
```

```
not() : Boolean[?] precedence: UNARY
```

true if self is false. false if self is true. null if self is null. Otherwise invalid.

```
body: if self.oclIsInvalid() then self
        else if self = null then null
        else self = false
        endif endif
```

```
or(b : Boolean[?]) : Boolean[?] invalidating validating precedence: OR
```

true if either self or b is true. Otherwise invalid if either self or b is invalid. Otherwise null if either self or b is null. Otherwise false.

```
body: if self.oclIsInvalid() then
        if b.oclIsInvalid() then self
      else if b = true then true
        else self
        endif endif
      else if self = true then true
    else if b.oclIsInvalid() then b
    else if b = true then true
    else if self = null then null
    else if b = null then null
        else false
        endif endif endif endif endif endif
```

```
toString() : String
```

Converts self to a string value.

```
xor(b : Boolean[?]) : Boolean[?] precedence: XOR
```

true if self is true and b is false, or if self is false and b is true. false if self is true and b is true, or if self is false and b is false. Otherwise invalid if either self or b is invalid. Otherwise null.

```
body: if self = null then null
        else if b = null then null
        else self <> b
        endif endif
```

3.4. `Class`

conformsTo OclAny

3.5. `Collection(T)`

Collection is the abstract supertype of all collection types in the OCL Standard Library. Each occurrence of an object in a collection is called an element. If an object occurs twice in a collection, there are two elements.

This sub clause defines the properties on Collections that have identical semantics for all collection subtypes. Some operations may be defined within the subtype as well, which means that there is an additional postcondition or a more specialized return value. Collection is itself an instance of the metatype CollectionType.

The definition of several common operations is different for each subtype. These operations are not mentioned in this sub clause.

The semantics of the collection operations is given in the form of a postcondition that uses the IterateExp of the IteratorExp construct. The semantics of those constructs is defined in Clause 10 ("Semantics Described using UML"). In several cases the postcondition refers to other collection operations, which in turn are defined in terms of the IterateExp or IteratorExp constructs.

Well-formedness rules
A collection cannot contain invalid values.context Collection inv: self->forAll(not oclIsInvalid())

conformsTo OclAny

Attributes

```
elementType : T
```

Evaluates to the type of the collection elements.

```
lower : Integer
```

Evaluates to the lower bound on the number of collection elements.

```
upper : Integer
```

Evaluates to the upper bound on the number of collection elements.

Operations

```
=(object2 : OclSelf) : Boolean precedence: EQUALITY
```

True if c is a collection of the same kind as `self` and contains the same elements in the same quantities and in the same order, in the case of an ordered collection type.

```
<>(object2 : OclSelf) : Boolean precedence: EQUALITY
```

True if c is not equal to `self`.

```
asBag() : Bag(T)
```

The Bag that contains all the elements from `self`.

```
asOrderedSet() : OrderedSet(T)
```

An OrderedSet that contains all the elements from `self`, with duplicates removed, in an order dependent on the particular concrete collection type.

```
asSequence() : Sequence(T)
```

A Sequence that contains all the elements from `self`, in an order dependent on the particular concrete collection type.

```
asSet() : Set(T)
```

The Set containing all the elements from `self`, with duplicates removed.

```
count(object : OclAny[?]) : Integer
```

The number of times that object occurs in the collection `self`.

```
excludes(object : OclAny[?]) : Boolean
```

True if object is not an element of `self`, `false` otherwise.

```
excludesAll(T2)(c2 : Collection(T2)) : Boolean
```

Does `self` contain none of the elements of c2 ?

```
excluding(object : OclAny[?]) : Collection(T)
```

The collection containing all elements of `self` apart from object.

```
excludingAll(objects : Collection(OclAny)) : Collection(T)
```

The collection containing all elements of `self` apart from all occurrences of all objects.

```
flatten(T2)() : Collection(T2)
```

If the element type is not a collection type, this results in the same collection as `self`. If the element type is a collection type, the result is a collection containing all the elements of all the recursively flattened elements of `self`.

```
includes(object : OclAny[?]) : Boolean
```

True if object is an element of `self`, `false` otherwise.

```
includesAll(T2)(c2 : Collection(T2)) : Boolean
```

Does `self` contain all the elements of c2 ?

```
including(object : T[?]) : Collection(T)
```

The collection containing all elements of `self` plus object.

```
includingAll(objects : Collection(T)) : Collection(T)
```

The collection containing all elements of `self` and objects.

```
intersection(c : Collection(T)) : Bag(T)
```

The intersection of `self` and bag; the bag of all elements that are in both `self` and c.

```
intersection(u : UniqueCollection(T)) : Set(T)
```

The intersection of `self` and a unique collection; the set of all elements that are in both `self` and u.

```
isEmpty() : Boolean
```

Is `self` the empty collection?

Note: `null->isEmpty()` returns `true` in virtue of the implicit casting from `null` to `Bag{}`.

```
max() : T
```

The element with the maximum value of all elements in `self`. Elements must be of a type supporting the max operation. The max operation – supported by the elements – must take one parameter of type T and be both associative and commutative. UnlimitedNatural, Integer and Real fulfill this condition.

```
min() : T
```

The element with the minimum value of all elements in `self`. Elements must be of a type supporting the min operation. The min operation – supported by the elements – must take one parameter of type T and be both associative and commutative. UnlimitedNatural, Integer and Real fulfill this condition.

```
notEmpty() : Boolean
```

Is `self` not the empty collection?

`null->notEmpty()` returns `false` in virtue of the implicit casting from `null` to `Bag{}`.

```
product(T2)(c2 : Collection(T2)) : Set(Tuple(Tuple(first : T, second :
T2)::first : T, Tuple(first : T, second : T2)::second : T2))
```

The cartesian product operation of `self` and c2.

```
selectByKind(TT)(type : Metaclass(TT)) : Collection(TT)
```

```
selectByType(TT)(type : Metaclass(TT)) : Collection(TT)
```

```
size() : Integer
```

The number of elements in the collection `self`.

```
sum() : T
```

The addition of all elements in `self`. Elements must be of an `OclSummable` type to provide the zero() and sum() operations. The *sum* operation must be both associative: a.sum(b).sum© = a.sum(b.sum©), and commutative: a.sum(b) = b.sum(a). UnlimitedNatural, Integer and Real fulfill this condition.

If the *sum* operation is not both associative and commutative, the *sum* expression is not well-formed, which may result in unpredictable results during evaluation. If an implementation is able to detect a lack of associativity or commutativity, the implementation may bypass the evaluation and return an `invalid` result.

```
union(c : Collection(T)) : Bag(T)
```

The bag consisting of all elements in `self` and all elements in c.

Iterations

```
any(i : T[?] | lambda : Lambda T() : Boolean) : T[?]
```

Returns any element in the source collection for which body evaluates to `true`. If there is more than one element for which body is `true`, one of them is returned. There must be at least one element fulfilling body, otherwise the result of this IteratorExp is `null`.

```
collect(V)(i : T[?] | lambda : Lambda T() : V[?]) : Collection(V)
```

The Collection of elements that results from applying body to every member of the source set. The result is flattened. Notice that this is based on collectNested, which can be of different type depending on the type of source. collectNested is defined individually for each subclass of CollectionType.

```
collectNested(V)(i : T[?] | lambda : Lambda T() : V[?]) : Collection(V)
```

The Collection of elements which results from applying body to every member of the source collection.

```
exists(i : T[?] | lambda : Lambda T() : Boolean[?]) : Boolean[?]
```

Results in `true` if body evaluates to `true` for at least one element in the source collection.

```
exists(i : T[?], j : T[?] | lambda : Lambda T() : Boolean[?]) :
Boolean[?]
```

```
forAll(i : T[?] | lambda : Lambda T() : Boolean[?]) : Boolean[?]
```

Results in `true` if the body expression evaluates to `true` for each element in the source collection; otherwise, result is `false`.

```
forAll(i : T[?], j : T[?] | lambda : Lambda T() : Boolean[?]) :
Boolean[?]
```

```
isUnique(i : T[?] | lambda : Lambda T() : OclAny[?]) : Boolean
```

Results in `true` if body evaluates to a different value for each element in the source collection; otherwise, result is `false`.

```
iterate(Tacc)(i : T[?]acc : ; Tacc[?] | lambda : Lambda T() : Tacc[?]) :
Tacc[?]
```

```
one(i : T[?] | lambda : Lambda T() : Boolean) : Boolean
```

Results in `true` if there is exactly one element in the source collection for which body is `true`.

```
reject(i : T[?] | lambda : Lambda T() : Boolean) : Collection(T)
```

The sub-collection of the source collection for which body is `false`.

```
select(i : T[?] | lambda : Lambda T() : Boolean) : Collection(T)
```

The sub-collection of the source collection for which body is `true`.

```
sortedBy(i : T[?] | lambda : Lambda T() : OclAny) : Sequence(T)
```

Results in the Collection containing all elements of the source collection. The element for which body has the lowest value comes first, and so on. The type of the body expression must have the < operation defined. The < operation must return a Boolean value and must be transitive (i.e., if a < b and b < c then a < c).

3.6. **Enumeration**

The Enumeration type is the type of an OrderedSet of EnumerationLiteral.

conformsTo `OclAny`

Attributes

```
allLiterals : OrderedSet(EnumerationLiteral)
```

Evaluates to the literals of the enumeration.

Operations

```
allInstances() : Set(OclSelf)
```

Return a set of all enumeration values of `self`.

3.7. **EnumerationLiteral**

The standard type EnumerationLiteral represents a named constant value of an Enumeration.

conformsTo `OclAny`

Attributes

```
Enumeration : Bag(Enumeration)
```

3.8. **Integer**

The standard type Integer represents the mathematical concept of integer. Note that UnlimitedNatural is a subclass of Integer, so for each parameter of type Integer, you can use an unlimited natural as the actual parameter. Integer is itself an instance of the metatype PrimitiveType (from UML).

conformsTo `Real`

Operations

```
-() : Integer precedence: UNARY
```

The negative value of `self`.

`+(i : OclSelf) : Integer` precedence: `ADDITIVE`

The value of the addition of `self` and i.

`-(i : OclSelf) : Integer` precedence: `ADDITIVE`

The value of the subtraction of i from `self`.

`*(i : OclSelf) : Integer` precedence: `MULTIPLICATIVE`

The value of the multiplication of `self` and i.

`/(i : OclSelf) : Real` precedence: `MULTIPLICATIVE`

The value of `self` divided by i. Evaluates to `invalid` if r is equal to zero.

`abs() : Integer`

The absolute value of `self`.

`compareTo(that : OclSelf) : Integer`

The comparison of `self` with `that`. -ve if less than, 0 if equal, +ve if greater than.

`div(i : Integer) : Integer`

The number of times that i fits completely within `self`.

`mod(i : Integer) : Integer`

The result is `self` modulo i.

`max(i : OclSelf) : Integer`

The maximum of `self` an i.

`min(i : OclSelf) : Integer`

The minimum of `self` an i.

`toString() : String`

Converts `self` to a string value.

3.9. Metaclass(T)

conformsTo Class, OclType

Attributes

`instanceType : T`

Evaluates to the type of instances.

3.10. OclAny

All types in the UML model and the primitive and collection types in the OCL standard library conforms to the type OclAny. Conceptually, OclAny behaves as a supertype for all the types. Features of OclAny are available on each object in all OCL expressions. OclAny is itself an instance of the metatype AnyType.

All classes in a UML model inherit all operations defined on OclAny. To avoid name conflicts between properties in the model and the properties inherited from OclAny, all names on the properties of OclAny start with 'ocl.' Although theoretically there may still be name conflicts, they can be avoided. One can also use qualification by OclAny (name of the type) to explicitly refer to the OclAny properties.

Operations of OclAny, where the instance of OclAny is called object.

Operations

`=(object2 : OclSelf) : Boolean` precedence: `EQUALITY`

True if `self` is the same object as object2. Infix operator.

```
post: result = self = object2
```

`<>(object2 : OclSelf) : Boolean` precedence: `EQUALITY`

True if `self` is a different object from object2. Infix operator.

```
post: result = not (self = object2)
```

```
oclAsSet() : Set(OclSelf)
```

Returns a Set with `self` as the sole content, unless `self` is `null` in which case returns an empty set,

```
oclAsType(TT)(type : Metaclass(TT)) : TT[?]
```

Evaluates to `self`, where `self` is of the type identified by T. The type T may be any classifier defined in the UML model; if the actual type of `self` at evaluation time does not conform to T, then the oclAsType operation evaluates to `invalid`.

In the case of feature redefinition, casting an object to a supertype of its actual type does not access the supertype's definition of the feature; according to the semantics of redefinition, the redefined feature simply does not exist for the object. However, when casting to a supertype, any features additionally defined by the subtype are suppressed.

```
post IsSelf: result = self
```

```
post IsType: result.oclIsKindOf(type)
```

```
oclIsInState(statespec : OclState) : Boolean
```

Evaluates to `true` if the `self` is in the state indentified by statespec.

```
oclIsInvalid() : Boolean validating
```

Evaluates to `true` if the `self` is equal to OclInvalid.

```
post: result = self.oclIsTypeOf(OclInvalid)
```

```
oclIsKindOf(T)(type : Metaclass(T)) : Boolean
```

Evaluates to `true` if the type of `self` conforms to t. That is, `self` is of type t or a subtype of t.

```
oclIsNew() : Boolean
```

Can only be used in a postcondition. Evaluates to `true` if the `self` is created during performing the operation (for instance, it didn't exist at precondition time).

```
oclIsTypeOf(T)(type : Metaclass(T)) : Boolean
```

Evaluates to `true` if `self` is of the type t but not a subtype of t

```
oclIsUndefined() : Boolean validating
```

Evaluates to `true` if the `self` is equal to `invalid` or equal to `null`.

```
post: result = self.oclIsTypeOf(OclVoid) or self.oclIsTypeOf(OclInvalid)
```

```
oclLog() : OclSelf
```

Evaluates to the self, with the side effect of generating a log message comprising self.

```
oclLog(message : String) : OclSelf
```

Evaluates to the self, with the side effect of generating a log message comprising message followed by self.

```
oclType() : Metaclass(OclSelf)
```

Evaluates to the type of which `self` is an instance.

```
toString() : String
```

Returns a string representation of `self`.

3.11. **OclComparable**

The type OclComparable defines the compareTo operation used by the sortedBy iteration. Only types that provide a derived compareTo implementation may be sorted.

conformsTo OclAny

Operations

```
compareTo(that : OclSelf) : Integer
```

Return -ve, 0, +ve according to whether self is less than, equal to , or greater than that.

The compareTo operation should be commutative.

`>(that : OclSelf) : Boolean` precedence: RELATIONAL

True if `self` is greater than `that`.

`<(that : OclSelf) : Boolean` precedence: RELATIONAL

True if `self` is less than `that`.

`<=(that : OclSelf) : Boolean` precedence: RELATIONAL

True if `self` is less than or equal to `that`.

`>=(that : OclSelf) : Boolean` precedence: RELATIONAL

True if `self` is greater than or equal to `that`.

3.12. `OclElement`

The type OclElement is the implicit supertype of any user-defined type that has no explicit supertypes. Operations defined for OclElement are therefore applicable to all user-defined types.

conformsTo OclAny

Operations

`allInstances() : Set(OclSelf)`

Return a set of all instances of the type and derived types of self.

`oclContainer() : OclElement[?]`

Returns the object for which self is a composed content or null if there is no such object.

`oclContents() : Set(OclElement)`

Returns the composed contents of self.

3.13. `OclInvalid`

The type OclInvalid is a type that conforms to all other types. It has one single instance, identified as `invalid`. Any property call applied on invalid results in `invalid`, except for the operations oclIsUndefined() and oclIsInvalid(). OclInvalid is itself an instance of the metatype InvalidType.

conformsTo OclVoid

Operations

`allInstances() : Set(OclSelf)`

Returns `invalid`.

`=(object2 : OclSelf) : Boolean` precedence: EQUALITY

Returns `invalid`.

`<>(object2 : OclSelf) : Boolean` precedence: EQUALITY

Returns `invalid`.

`and(b : Boolean[?]) : Boolean[?] validating` precedence: AND

`implies(b : Boolean[?]) : Boolean[?] validating` precedence: IMPLIES

`or(b : Boolean[?]) : Boolean[?] validating` precedence: OR

`oclAsSet() : Set(OclSelf)`

`oclAsType(TT)(type : Metaclass(TT)) : TT`

`oclIsInvalid() : Boolean validating`

`oclIsKindOf(T)(type : Metaclass(T)) : Boolean`

`oclIsTypeOf(T)(type : Metaclass(T)) : Boolean`

`oclIsUndefined() : Boolean validating`

`oclType() : Metaclass(OclSelf)`

`toString() : String`

Returns 'invalid'.

3.14. `OclLambda`

The type OclLambda is the implicit supertype of all Lambda types. The operations defined for OclLambda therefore apply to all lambda expressions.

conformsTo _OclAny_

3.15. `OclMessage`

OclMessage This sub clause contains the definition of the standard type OclMessage. As defined in this sub clause, each ocl message type is actually a template type with one parameter. 'T' denotes the parameter. A concrete ocl message type is created by substituting an operation or signal for the T.

The predefined type OclMessage is an instance of MessageType. Every OclMessage is fully determined by either the operation, or signal given as parameter. Note that there is conceptually an undefined (infinite) number of these types, as each is determined by a different operation or signal. These types are unnamed. Every type has as attributes the name of the operation or signal, and either all formal parameters of the operation, or all attributes of the signal. OclMessage is itself an instance of the metatype MessageType.

OclMessage has a number of predefined operations, as shown in the OCL Standard Library.

conformsTo _OclAny_

Operations

`hasReturned() : Boolean`

True if type of template parameter is an operation call, and the called operation has returned a value. This implies the fact that the message has been sent. False in all other cases.

`result() : OclAny`

Returns the result of the called operation, if type of template parameter is an operation call, and the called operation has returned a value. Otherwise the `invalid` value is returned.

`isOperationCall() : Boolean`

Returns `true` if the OclMessage represents the sending of a UML Operation call.

`isSignalSent() : Boolean`

Returns `true` if the OclMessage represents the sending of a UML Signal.

3.16. `OclSelf`

The pseudo-type OclSelf denotes the statically determinate type of `self` in Operation and Iteration signatures. Instances of OclSelf are never created.

conformsTo _OclAny_

3.17. `OclState`

conformsTo _OclAny_

3.18. `OclSummable`

The type OclSummable defines the sum and zero operations used by the Collection::sum iteration. Only types that provide derived sum and zero implementations may be summed.

conformsTo _OclAny_

Operations

`sum(that : OclSelf) : OclSelf`

Return the sum of self and that.

The sum operation should be associative.

`zero() : OclSelf`

Return the 'zero' value of self to initialize a summation.

zero().sum(self) = self.

3.19. `OclTuple`

The type OclTuple is the implicit supertype of all Tuple types. The operations defined for OclTuple therefore apply to all tuples.

conformsTo [OclAny](#)

Operations

```
=(object2 : OclSelf) : Boolean precedence: EQUALITY
<>(object2 : OclSelf) : Boolean precedence: EQUALITY
```

3.20. `OclType`

The type OclType is the implicit supertype of any UML type. Operations defined for OclType are therefore applicable to all UML types.

conformsTo [OclElement](#)

Operations

```
conformsTo(type2 : OclType) : Boolean
```

Returns true if type2 conforms to self.

3.21. `OclVoid`

The type OclVoid is a type that conforms to all other types except OclInvalid. It has one single instance, identified as `null`, that corresponds with the UML LiteralNull value specification. Any property call applied on `null` results in `invalid`, except for the oclIsUndefined(), oclIsInvalid(), =(OclAny) and <>(OclAny) operations. However, by virtue of the implicit conversion to a collection literal, an expression evaluating to `null` can be used as source of collection operations (such as 'isEmpty'). If the source is the `null` literal, it is implicitly converted to Bag{}.

OclVoid is itself an instance of the metatype VoidType.

conformsTo [OclAny](#)

Operations

```
allInstances() : Set(OclSelf)
```

Returns Set{null}.

```
=(object2 : OclSelf) : Boolean precedence: EQUALITY
```

Redefines the OclAny operation, returning `true` if object is `null`, `invalid` if object is `invalid`, `false` otherwise.

```
<>(object2 : OclSelf) : Boolean precedence: EQUALITY
and(b : Boolean[?]) : Boolean[?] precedence: AND
implies(b : Boolean[?]) : Boolean[?] precedence: IMPLIES
or(b : Boolean[?]) : Boolean[?] precedence: OR
oclIsInvalid() : Boolean validating
oclIsUndefined() : Boolean validating
toString() : String
```

Returns `null`.

3.22. `OrderedCollection(T)`

The OrderedCollection type provides the shared functionality of the OrderedSet and Sequence collections for which the elements are ordered. The common supertype of OrderedCollection is Collection.

conformsTo `Collection(T)`

Operations

`at(index : Integer) : T[?] invalidating`

The i-th element of ordered collection.

`first() : T[?] invalidating`

The first element in `self`.

`indexOf(obj : OclAny[?]) : Integer`

The index of object obj in the ordered collection.

`last() : T[?] invalidating`

The last element in `self`.

3.23. `OrderedSet(T)`

The OrderedSet is a Set, the elements of which are ordered. It contains no duplicates. OrderedSet is itself an instance of the metatype OrderedSetType. An OrderedSet is not a subtype of Set, neither a subtype of Sequence. The common supertype of Sets and OrderedSets is Collection.

conformsTo `OrderedCollection(T)`, `UniqueCollection(T)`

Operations

`=(object2 : OclSelf) : Boolean` precedence: EQUALITY

`<>(object2 : OclSelf) : Boolean` precedence: EQUALITY

`-(s : UniqueCollection(OclAny)) : OrderedSet(T)` precedence: ADDITIVE

The elements of `self`, which are not in s.

`append(object : T[?]) : OrderedSet(T)`

The set of elements, consisting of all elements of `self`, followed by object.

`appendAll(objects : OrderedCollection(T)) : OrderedSet(T)`

The set of elements, consisting of all elements of `self`, followed by objects.

`excluding(object : OclAny[?]) : OrderedSet(T)`

The ordered set containing all elements of `self` apart from object.

The order of the remaining elements is not changed.

`excludingAll(objects : Collection(OclAny)) : OrderedSet(T)`

The ordered set containing all elements of `self` apart from all occurrences of all objects.

`flatten(T2)() : OrderedSet(T2)`

`including(object : T[?]) : OrderedSet(T)`

The ordered set containing all elements of `self` plus object added as the last element if not already present.

`insertAt(index : Integer, object : T[?]) : OrderedSet(T) invalidating`

The ordered set consisting of `self` with object present at position index.

`prepend(object : T[?]) : OrderedSet(T)`

The sequence consisting of object, followed by all elements in `self`.

`post IsAtStart: result->at(1) = object`

`post IsShiftedAlong: Sequence{1..self->size()}->forAll(index | self->at(index) = result->at`

`post IsSizePlusOne: result->size() = self->size() + 1`

`prependAll(objects : OrderedCollection(T)) : OrderedSet(T)`

The sequence consisting of objects, followed by all elements in `self`.

`reverse() : OrderedSet(T)`

The ordered set of elements with same elements but with the opposite order.

```
selectByKind(TT)(type : Metaclass(TT)) : OrderedSet(TT)
```

```
selectByType(TT)(type : Metaclass(TT)) : OrderedSet(TT)
```

```
subOrderedSet(lower : Integer, upper : Integer) : OrderedSet(T)
invalidating
```

The sub-set of `self` starting at number lower, up to and including element number upper.

Iterations

```
closure(i : T | lambda : Lambda T() : OrderedSet(T)) : OrderedSet(T)
```

The closure of applying body transitively to every distinct element of the source collection.

```
collect(V)(i : T[?] | lambda : Lambda T() : V[?]) : Sequence(V)
```

```
collectNested(V)(i : T[?] | lambda : Lambda T() : V[?]) : Sequence(V)
```

The sequence of elements that results from applying body to every member of the source ordered collection.

```
reject(i : T[?] | lambda : Lambda T() : Boolean) : OrderedSet(T)
```

The ordered set of the source ordered set for which body is `false`.

```
select(i : T[?] | lambda : Lambda T() : Boolean) : OrderedSet(T)
```

The ordered set of the source ordered set for which body is `true`

```
sortedBy(i : T[?] | lambda : Lambda T() : OclAny) : OrderedSet(T)
```

Results in the ordered set containing all elements of the source collection. The element for which body has the lowest value comes first, and so on. The type of the body expression must have the < operation defined. The < operation must return a Boolean value and must be transitive (i.e., if a < b and b < c, then a < c).

3.24. `Real`

The standard type Real represents the mathematical concept of real. Note that UnlimitedNatural is a subclass of Integer and that Integer is a subclass of Real, so for each parameter of type Real, you can use an unlimited natural or an integer as the actual parameter. Real is itself an instance of the metatype PrimitiveType (from UML).

conformsTo `OclComparable`, `OclSummable`

Operations

```
=(object2 : OclSelf) : Boolean precedence: EQUALITY
```

Returns `true` if the numeric value of `self` is the same as the numeric value of object2, `false` otherwise.

```
<>(object2 : OclSelf) : Boolean precedence: EQUALITY
```

Returns `true` if the numeric value of `self` is the not the same as the numeric value of object2, `false` otherwise.

```
+(r : OclSelf) : Real precedence: ADDITIVE
```

The value of the addition of `self` and r.

```
-(r : OclSelf) : Real precedence: ADDITIVE
```

The value of the subtraction of r from `self`.

```
*(r : OclSelf) : Real precedence: MULTIPLICATIVE
```

The value of the multiplication of `self` and r.

```
-() : Real precedence: UNARY
```

The negative value of `self`.

```
/(r : OclSelf) : Real precedence: MULTIPLICATIVE
```

The value of `self` divided by r. Evaluates to `invalid` if r is equal to zero.

```
>(r : OclSelf) : Boolean precedence: RELATIONAL
```

True if `self` is greater than r.

```
<(r : OclSelf) : Boolean precedence: RELATIONAL
```

True if `self` is less than r.

```
<=(r : OclSelf) : Boolean precedence: RELATIONAL
```

True if `self` is less than or equal to r.

```
>=(r : OclSelf) : Boolean precedence: RELATIONAL
```

True if `self` is greater than or equal to r.

```
abs() : Real
```

The absolute value of `self`.

```
compareTo(that : OclSelf) : Integer
```

The comparison of `self` with `that`. -ve if less than, 0 if equal, +ve if greater than.

```
floor() : Integer
```

The largest integer that is less than or equal to `self`.

```
max(r : OclSelf) : Real
```

The maximum of `self` and r.

```
min(r : OclSelf) : Real
```

The minimum of `self` and r.

```
round() : Integer
```

The integer that is closest to `self`. When there are two such integers, the largest one.

```
toString() : String
```

Converts `self` to a string value.

3.25. `Sequence(T)`

A sequence is a collection where the elements are ordered. An element may be part of a sequence more than once. Sequence is itself an instance of the metatype SequenceType. A Sentence is not a subtype of Bag. The common supertype of Sentence and Bags is Collection.

conformsTo `OrderedCollection(T)`

Operations

```
=(object2 : OclSelf) : Boolean precedence: EQUALITY
```

True if `self` contains the same elements as s in the same order.

```
<>(object2 : OclSelf) : Boolean precedence: EQUALITY
append(object : T[?]) : Sequence(T)
```

The sequence of elements, consisting of all elements of `self`, followed by object.

```
appendAll(objects : OrderedCollection(T)) : Sequence(T)
```

The sequence of elements, consisting of all elements of `self`, followed by objects.

```
excluding(object : OclAny[?]) : Sequence(T)
```

The sequence containing all elements of `self` apart from all occurrences of object.

The order of the remaining elements is not changed.

```
excludingAll(objects : Collection(OclAny)) : Sequence(T)
```

The sequence containing all elements of `self` apart from all occurrences of all objects.

```
flatten(T2)() : Sequence(T2)
```

Redefines the Collection operation. If the element type is not a collection type, this results in the same sequence as `self`. If the element type is a collection type, the result is the sequence containing all the elements of all the recursively flattened elements of `self`. The order of the elements is partial.

```
including(object : T[?]) : Sequence(T)
```

The sequence containing all elements of `self` plus object added as the last element.

```
insertAt(index : Integer, object : T[?]) : Sequence(T) invalidating
```
The sequence consisting of `self` with object inserted at position index.
```
prepend(object : T[?]) : Sequence(T)
```
The sequence consisting of object, followed by all elements in `self`.
```
prependAll(objects : OrderedCollection(T)) : Sequence(T)
```
The sequence consisting of objects, followed by all elements in `self`.
```
reverse() : Sequence(T)
```
The sequence containing the same elements but with the opposite order.
```
selectByKind(TT)(type : Metaclass(TT)) : Sequence(TT)
selectByType(TT)(type : Metaclass(TT)) : Sequence(TT)
subSequence(lower  :  Integer,  upper  :  Integer)  :  Sequence(T)
invalidating
```
The sub-sequence of `self` starting at number lower, up to and including element number upper.

Iterations
```
closure(i : T | lambda : Lambda T() : OrderedSet(T)) : OrderedSet(T)
```
The closure of applying body transitively to every distinct element of the source collection.
```
collect(V)(i : T[?] | lambda : Lambda T() : V[?]) : Sequence(V)
collectNested(V)(i : T[?] | lambda : Lambda T() : V[?]) : Sequence(V)
```
The sequence of elements that results from applying body to every member of the source ordered collection.
```
reject(i : T[?] | lambda : Lambda T() : Boolean) : Sequence(T)
```
The subsequence of the source sequence for which body is `false`.
```
select(i : T[?] | lambda : Lambda T() : Boolean) : Sequence(T)
```
The subsequence of the source sequence for which body is `true`.
```
sortedBy(i : T[?] | lambda : Lambda T() : OclAny) : Sequence(T)
```
Results in the Sequence containing all elements of the source collection. The element for which body has the lowest value comes first, and so on. The type of the body expression must have the < operation defined. The < operation must return a Boolean value and must be transitive (i.e., if a < b and b < c then a < c).

3.26. **Set(T)**

conformsTo [UniqueCollection(T)](#)

Operations
```
=(object2 : OclSelf) : Boolean precedence: EQUALITY
```
Evaluates to `true` if `self` and s contain the same elements.
```
<>(object2 : OclSelf) : Boolean precedence: EQUALITY
-(s : UniqueCollection(OclAny)) : Set(T) precedence: ADDITIVE
```
The elements of `self`, which are not in s.
```
excluding(object : OclAny[?]) : Set(T)
```
The set containing all elements of `self` without object.
```
excludingAll(objects : Collection(OclAny)) : Set(T)
```
The set containing all elements of `self` apart from all occurrences of all objects.
```
flatten(T2)() : Set(T2)
```
Redefines the Collection operation. If the element type is not a collection type, this results in the same set as `self`. If the element type is a collection type, the result is the set containing all the elements of all the recursively flattened elements of `self`.
```
including(object : T[?]) : Set(T)
```

The set containing all elements of `self` plus object.

```
includingAll(objects : Collection(T)) : Set(T)
```

The set containing all elements of `self` and objects.

```
selectByKind(TT)(type : Metaclass(TT)) : Set(TT)
```

```
selectByType(TT)(type : Metaclass(TT)) : Set(TT)
```

Iterations

```
closure(i : T | lambda : Lambda T() : Set(T)) : Set(T)
```

The closure of applying body transitively to every distinct element of the source collection.

```
collect(V)(i : T[?] | lambda : Lambda T() : V[?]) : Bag(V)
```

```
collectNested(V)(i : T[?] | lambda : Lambda T() : V[?]) : Bag(V)
```

The Bag of elements which results from applying body to every member of the source nonordered collection.

```
reject(i : T[?] | lambda : Lambda T() : Boolean) : Set(T)
```

The subset of the source set for which body is `false`.

```
select(i : T[?] | lambda : Lambda T() : Boolean) : Set(T)
```

The subset of set for which expr is `true`.

```
sortedBy(i : T[?] | lambda : Lambda T() : OclAny) : OrderedSet(T)
```

Results in the ordered set containing all elements of the source collection. The element for which body has the lowest value comes first, and so on. The type of the body expression must have the < operation defined. The < operation must return a Boolean value and must be transitive (i.e., if a < b and b < c, then a < c).

3.27. `State`

conformsTo `OclState`

3.28. `String`

The standard type String represents strings, which can be both ASCII or Unicode. String is itself an instance of the metatype PrimitiveType (from UML).

conformsTo `OclComparable`, `OclSummable`

Operations

```
=(object2 : OclSelf) : Boolean precedence: EQUALITY
```

```
<>(object2 : OclSelf) : Boolean precedence: EQUALITY
```

```
+(s : String) : String precedence: ADDITIVE
```

The concatenation of `self` and s.

```
at(i : Integer) : String invalidating
```

Queries the character at position i in `self`.

```
characters() : Sequence(String)
```

Obtains the characters of `self` as a sequence.

```
compareTo(that : OclSelf) : Integer
```

The comparison of `self` with `that`. -ve if less than, 0 if equal, +ve if greater than.

```
concat(s : String) : String
```

The concatenation of `self` and s.

```
endsWith(s : String) : Boolean
```

Returns true if `self` ends with the string s. Every string ends with the empty string.

```
equalsIgnoreCase(s : String) : Boolean
```

Queries whether s and `self` are equivalent under case-insensitive collation.

```
indexOf(s : String) : Integer
```

Queries the first index in `self` at which s is a substring of `self`, or zero if s is not a substring of `self`. The empty string is a substring of every string at index 1 (and also at all other indexes).

```
lastIndexOf(s : String) : Integer
```

Queries the last in `self` at which s is a substring of `self`, or zero if s is not a substring of `self`. The empty string is a substring of every string at index `self`-size()+1 (and also at all other indexes).

```
matches(regex : String) : Boolean
```

Use a regular expression match and return true if self matches regex, false otherwise.

```
replaceAll(regex : String, replacement : String) : String invalidating
```

Return a string derived from self by replacing all matches of regex by replacement.

```
replaceFirst(regex  :  String,  replacement  :  String)  :  String
invalidating
```

Return a string derived from self by replacing the first match of regex by replacement.

```
size() : Integer
```

The number of characters in `self`.

```
startsWith(s : String) : Boolean
```

Returns true if `self` starts with the string s. Every string starts with the empty string.

```
substituteAll(oldSubstring : String, newSubstring : String) : String
```

Return a string derived from self by replacing all occurrences of oldSubstring by newSubstring.

```
substituteFirst(oldSubstring : String, newSubstring : String) : String
```

Return a string derived from self by replacing the first occurrence of oldSubstring by newSubstring. Returns invalid if there is no first occurrence.

```
substring(lower : Integer, upper : Integer) : String invalidating
```

The sub-string of `self` starting at character number lower, up to and including character number upper. Character numbers run from 1 to self.size().

```
toBoolean() : Boolean invalidating
```

Converts `self` to a boolean value.

```
toInteger() : Integer invalidating
```

Converts `self` to an Integer value.

```
toLower() : String
```

This is a deprecated variant of toLowerCase() preserving compatibility with traditional Eclipse OCL behaviour.

```
toLowerCase() : String
```

Converts `self` to lower case, using the locale defined by looking up oclLocale in the current environment. Otherwise, returns the same string as `self`.

```
toReal() : Real invalidating
```

Converts `self` to a Real value.

```
toString() : String
```

Returns `self`.

```
toUpper() : String
```

This is a deprecated variant of toUpperCase() preserving compatibility with traditional Eclipse OCL behaviour.

```
toUpperCase() : String
```

Converts `self` to upper case, using the locale defined by looking up oclLocale in the current environment. Otherwise, returns the same string as `self`.

```
tokenize() : Sequence(String)
```

Partition `self` into a sequence substrings separated by any of space, line-feed, carriage-return, form-feed and horizontal-tab delimiters. The delimiters are omitted from the return.

```
tokenize(delimiters : String) : Sequence(String)
```

Partition `self` into a sequence substrings separated by characters in the delimiters. The delimiters are omitted from the return.

```
tokenize(delimiters  :  String,  returnDelimiters  :  Boolean)  :
Sequence(String)
```

Partition `self` into a sequence substrings separated by characters in the delimiters. If returnDelimeters is true the returned sequence includes the delimiters, otherwise the delimiters are omitted.

```
trim() : String
```

Return `self` with leading and trailing whitespace removed.

```
>(s : OclSelf) : Boolean precedence: RELATIONAL
```

True if `self` is greater than s, using the locale defined by looking up oclLocale in the current environment.

```
<(s : OclSelf) : Boolean precedence: RELATIONAL
```

True if `self` is less than s, using the locale defined by looking up oclLocale in the current environment.

```
<=(s : OclSelf) : Boolean precedence: RELATIONAL
```

True if `self` is less than or equal to s, using the locale defined by looking up oclLocale in the current environment.

```
>=(s : OclSelf) : Boolean precedence: RELATIONAL
```

True if `self` is greater than or equal to s, using the locale defined by looking up oclLocale in the current environment.

3.29. `Type`

conformsTo `OclType`

3.30. `UniqueCollection(T)`

The UniqueCollection type provides the shared functionality of the OrderedSet and Set collections for which the elements are unique. The common supertype of UniqueCollection is Collection.

conformsTo `Collection(T)`

Operations

```
-(s : UniqueCollection(OclAny)) : UniqueCollection(T) precedence: ADDITIVE
```

The elements of `self`, which are not in s.

```
intersection(c : Collection(T)) : Set(T)
```

The intersection of `self` and c (i.e., the set of all elements that are in both `self` and c).

```
symmetricDifference(s : UniqueCollection(OclAny)) : Set(T)
```

The set containing all the elements that are in `self` or s, but not in both.

```
union(s : UniqueCollection(T)) : Set(T)
```

The set consisting of all elements in `self` and all elements in s.

Iterations

```
sortedBy(i : T[?] | lambda : Lambda T() : OclAny) : OrderedSet(T)
```

Results in the ordered set containing all elements of the source collection. The element for which body has the lowest value comes first, and so on. The type of the body expression must have the < operation defined. The < operation must return a Boolean value and must be transitive (i.e., if a < b and b < c, then a < c).

3.31. `UnlimitedNatural`

The standard type UnlimitedNatural is used to encode the non-negative values of a multiplicity specification. This includes a special *unlimited* value (*) that encodes the upper value of a multiplicity specification. UnlimitedNatural is itself an instance of the metatype UnlimitedNaturalType.

Note that although UnlimitedNatural is a subclass of Integer, the *unlimited* value cannot be represented as an Integer. Any use of the *unlimited* value as an integer or real is replaced by the `invalid` value.

conformsTo Integer

Operations

`oclAsType(TT)(type : Metaclass(TT)) : TT`

Evaluates to `self`, where `self` is of the type identified by T. The type T may be any classifier defined in the UML model; if the actual type of `self` at evaluation time does not conform to T, then the oclAsType operation evaluates to `invalid`.

The standard behavior is redefined for UnlimitedNatural. Numeric values may be converted to Real or Integer, but the *unlimited* value may not. Conversion of *unlimited* to Real or Integer returns `invalid`.

Chapter 4. Tutorials

The OCLinEcore tutorial shows how

- to install OCL and the additional Editors and Examples
- to use the OCLinEcore editor
  - to edit Ecore meta-models
  - to enrich Ecore meta-models with OCL invariants, bodies and values
- to use embedded OCL for validation of models
- to use the OCL Console to practice evaluation of OCL
- to generate Java code for Ecore that uses the embedded OCL

The Working with Classic OCL tutorial shows how

- the OCL Parser may be invoked from Java
- the OCL evaluator may be invoked from Java

4.1. OCLinEcore tutorial

This tutorial has been updated for Eclipse Luna; Eclipse 4.4, EMF 2.10, OCL 5.0.

- Some screenshots may be slightly out of date.

4.1.1. Overview

In this example you will

- Create an Ecore model using the OCLinEcore text editor
- Create a dynamic instance of that Ecore model
- Enrich the Ecore model with OCL using the OCLinEcore text editor
- Validate the model and observe the OCL enrichments
- Use the Interactive OCL Console to execute the OCL enrichments

The above is all performed without generating any Java code; the models exploit EMF's dynamic capabilities and the OCL integration.

You may then

- Create an Ecore genmodel
- Generate Java code for the Ecore model that invokes the OCL expressions.

See the OCL Debugger tutorial for debugging See the Code Generator tutorial for Java code generation

4.1.2. References

This tutorial assumes that the reader is familiar with generating models using EMF. The reader is referred to Generating an EMF Model.

Other references:

- The Object Constraint Language: Getting Your Models Ready for MDA. Jos Warmer and Anneke Kleppe. (Addison-Wesley Object Technology)
- OCL specification.
- OCLinEcore wiki page.

4.1.3. Installing the Eclipse OCL Examples

Please see the Instructions for installing the OCL Editors.

4.1.4. Troubleshooting

The editor currently provides syntax and semantic validation. It does not yet apply all the well-formedness validation rules, so some problems may be unreported. This is work in progress. Sometimes spurious errors are displayed, which may go away with a **Save**, but may require an editor close and reopen.

4.1.5. Using the OCLinEcore text editor for Ecore

There are many different (compatible) ways to create and edit Ecore models.

- An Ecore Model may be created from an XSD schema file

- An Ecore Model may be created from a Rose model file

- An Ecore Model may be created from annotated Java file

- The Sample Ecore Editor provides tree editing

- The Ecore Tools project provides graphical editing

- Papyrus provides UML editing that may be converted to Ecore

Here we introduce the OCLinEcore editor that provides text editing, which is appropriate when a non-trivial amount of OCL enrichment is required.

All the above approaches update a *.ecore file, so the user is free to choose whichever editing approach is best suited for the planned changes.

4.1.5.1. Create a New EMF Project

We will first create a new project for this example; so invoke **File->New->Project...** (left-click the **File** menu, then left-click **New**, then left-click **Project...**).

In the **New Project** dialog left-click to expand **Eclipse Modeling Framework**, then left-click to select **Empty EMF Project**.

Left-click on **Next** and in the **New Empty EMF Project** dialog type **Tutorial** as the project name.

Left-click on **Finish**.

4.1.5.2. Create a New Ecore Model

We will now create a new model for this example.

First right-click on the **model** folder in the **Tutorial** project to define the target folder and pop-up the context-sensitive menu. Select **New->Other...** then select the **OCLinEcore Ecore File** from the **OCL** category.

The alternative **OCLinEcore Text File** creates a *.oclinecore text file which preserves whitespace and comments more faithfully but which must be converted to a *.ecore file for many modeling purposes.

Left-click **Next** and enter **Tutorial.ecore** as the file name.

Left-click **Finish** to open up an editor with some minimal example content demonstrating

- the nesting of attributes or operations or invariants within classes within packages
- use of OCL to define the body of an operation
- the syntax for mutually opposite properties
- use of OCL to define an invariant and a custom error message

Close the editor by left-clicking the cross on the editor tab.

You can see the normal Ecore view of the file by right-clicking on the **Tutorial.ecore** file to pop-up the context-sensitive menu and select **Open With->Sample Ecore Model Editor**.

Close the editor by left-clicking the cross on the editor tab.

4.1.5.3. Edit Ecore Model as OCLinEcore

We will now open the Ecore model using the OCLinEcore text editor and provide some initial content.

Right-click on the **Tutorial.ecore** file to pop-up the context-sensitive menu and select **Open With->OCLinEcore Editor**.

Now follow the following procedure to cut and paste the following text into the editor.

- select all existing content (e.g. Ctrl-A)

- delete all (e.g. Ctrl-X)

- open [Text for cut and paste]

- select and copy the text (e.g Ctrl-A and Ctrl-C) from the browser

- paste (e.g Ctrl-V) in the original editor

- save the contents (e.g. Ctrl-S)

```
import ecore : 'http://www.eclipse.org/emf/2002/Ecore#/';

package tutorial : tut = 'http://www.eclipse.org/mdt/ocl/oclinecore/tutorial'
{
  class Library
  {
    attribute name : String;
    property books#library : Book[*] { composes };
    property loans : Loan[*] { composes };
    property members#library : Member[*] { composes };
  }

  class Book
  {
    attribute name : String;
    attribute copies : Integer;
    property library#books : Library[?];
  }

  class Member
  {
    attribute name : String;
    property library#members : Library[?];
  }

  class Loan
  {
    property book : Book;
    property member : Member;
    attribute date : ecore::EDate[?];
  }
}
```

The syntax is defined in OCLinEcore. It emulates OMG specifications with 'name : type[multiplicity] { properties }'.

- `import` associates an alias with an external EPackage.

- `package` introduces an EPackage with name, nsPrefix and nsURI.

- `class` introduces an EClass with name and optional superclasses.

- `attribute` introduces a property with a datatype type (an EAttribute).

- `property` introduces a property with a class type (an EReference).

- # introduces an opposite role name.

- `_'xxx'` escapes an awkward or reserved word identifier.

The import URI is the URI of a Package, so in the example the `http://www.eclipse.org/emf/2002/Ecore` is the URI of the model, # is the fragment separator and / is the path to the Package at the root of the XMI document.

Completion assist (Ctrl Space) may be used for syntax assistance.

Format (Ctrl-Shift F) may be used to auto-format a selected range.

In order to discover a syntax for which completion assist is insufficient, you may use the Sample Ecore Editor on a test file to create the kind of Ecore element that you require, and then open the test file with the OCLinEcore editor to see the corresponding textual syntax.

4.1.5.4. The Tutorial Meta-Model

The example meta-model models a library with members and books and loans of books to members. It may be viewed graphically using the Ecore Tools (not part of this tutorial).

Note that this diagram is an Ecore Diagram rather than a UML Diagram and so the default multiplicities for attributes is Ecore's [0..1] rather than OCLinEcore's and UML's [1..1].

Note also that the OCL types `String` and `Integer` map to `EString` and `EBigInteger` in Ecore.

4.1.6. Create a Dynamic Model Instance

At this point a corresponding EMF tutorial would show how to generate Java code for the meta-model and an editor for the meta-model. Here we are concerned with modeling, so we will continue with the models alone.

In the editor view, double-click on **Library** to select it and then right-click to show the context-sensitive menu and then left-click on **Create Dynamic Instance...** to start to create a new Dynamic Model with `Library` at its root.

> Creating a Dynamic Instance requires a valid *.ecore file to exist. It does not work when editing *.oclinecore files.

In the **Create Dynamic Instance** dialog select **Tutorial/model** as the parent folder and enter **Tutorial.xmi** as the file name for the dynamic model instance and left-click **Finish**.

The model is automatically opened for editing. If it is does open with the Sample Reflective Ecore Model Editor, close the editor and open explicitly using *Open With->Sample Reflective Ecore Model Editor). This gives a tree-like presentation of the model. The properties of each node can be seen in the Properties View.

(If the Properties View is not visible, right-click within the editor and left-click on **Show Properties View**.)

Select the Library and use give it a name such as `lib`.

From the right-button menu for `Library` use **New Child->Books Book** twice, use **New Child->Loans Loan** once and **New Child->Members Member** three times to populate the model with two books, one loan and three members.

Left-click to select each of the Books and Members in turn and enter a name such as `b1` or `m2` using the Properties View. Specify that b1 has one copy and that b2 has 2 copies.

The books and members now have distinct titles in the outline. When you left-click to select the Loan and edit its Book and Member attributes, the associated pull-down has meaningful entries. Specify that the Loan is for `b2` by `m3`.

The configuration so far is simple, three members, two books and one loan. We can validate that this by right-clicking on the `Library` node, and left-clicking to **Validate** `Library` and all its children.

Since the model is so simple, it is difficult to have anything wrong; most of the illegal modeling options such as a Loan composing rather than referencing a Book are prevented by the Editor's enforcement of the meta-model.

(If you have an error at this point, a **Details** button will lead you to some diagnostics that may clarify the problem. Pasting the following XMI into **Tutorial.xmi** should also resolve an entry problem.)

```xml
<?xml version="1.0" encoding="ASCII"?>
<tut:Library xmi:version="2.0" xmlns:xmi="http://www.omg.org/XMI"
    xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
    xmlns:tut="http://www.eclipse.org/mdt/ocl/oclinecore/tutorial"
    xsi:schemaLocation="http://www.eclipse.org/mdt/ocl/oclinecore/tutorial Tutorial.ecore"
    name="lib">
  <books name="b1" copies="1"/>
  <books name="b2" copies="2"/>
  <loans book="//@books.1" member="//@members.2"/>
  <members name="m1"/>
  <members name="m2"/>
  <members name="m3"/>
</tut:Library>
```

We will now create two further identical loans of b2 by m3. This may conveniently be performed by left-clicking to select the existing loan, typing Ctrl-C to copy it, left-clicking to select the Library as the new parent, then typing Ctrl-V to paste it on the library. Repeat so that there are three identical loans.

Validating the library should still be successful, although it is clearly wrong for the two copies of b2 to participate in three loans.

4.1.7. Enrich the meta-model with OCL

The semantic constraint that a book cannot be borrowed more times than there are books is a simple example of a constraint that cannot be expressed by simple multiplicities; a more powerful capability is required that may potentially require evaluation of functions of almost arbitrary complexity. The Object Constraint Language provides this capability.

The constraint can be realized as an invariant on a book that specifies that that (the size of the (selection of loans involving the book)) is less than or equal to (the number of copies of the book).

```
    invariant SufficientCopies:
      library.loans->select(book=self)->size() <= copies;
```

In more detail:

- an invariant is defined whose name is SufficientCopies

- within the invariant on a Book, self is the instance of Book being validated.

- library.loans, which is short for self.library.loans, navigates to the library and then to all loans in the library.

- ->select(...) is a collection iteration over the loans. It selects each loan for which its argument expression is true

- book=self, which is short for aLoan : Loan | aLoan.book = self, uses the aLoan iterator over each loan to select those for which the book is the book being validated

- ->size() is a collection operation that just counts the number of selected loans

- <= copies, which is short for <= self.copies converts the count to true if it is consistent, or false if inconsistent.

Close the **Tutorial.xmi** editor before modifying its meta-model. (Beware that a wide variety of unpleasant errors can occur if the meta-model is changed after the model is loaded.)

Add the invariant shown below to the meta-model.

```
class Book
{
  invariant SufficientCopies:
    library.loans->select(book=self)->size() <= copies;
  attribute name : String;
  attribute copies : Integer;
  property library#books : Library[?];
}
```
[Text for cut and paste]

The required semantic is expressed by the `SufficientCopies` invariant constraint for a Book. For a valid model the SufficientCopies invariant must always be true.

If you reopen the **Tutorial.xmi** editor and invoke **Validate** for the `Library`, you will now get a validation error. Left click **Details** for details.

The **Details** identifies that the `SufficientCopies` invariant is not satisfied for the `b2` book.

If you now change the first loan so that `b1` is borrowed and then validate again, the problem is resolved. It is alright for `m3` to borrow the one copy of `b1` and the two copies of `b2`.

Before introducing a further constraint of no duplicate loans, we will show how OCL expressions can be exercised. OCL is a very powerful compact language; the example hides a loop over all the loans. More complex examples may easily involve three or four levels of hidden loops on a single line, but may equally easily have simple errors. It is therefore helpful to simplify expressions and use helper operations and properties to modularise them. These may then be exercised using the OCL Console or debugged using the OCL Debugger.

4.1.8. The OCL Console

The OCL Console supports interactive execution of an OCL expression in the context of a model instance.

To make the OCL Console visible, first make the **Console** view visible by **Window->Show View->Console**. Then right click on the **Open Console** and left click on **Interactive Xtext OCL**.

Alternatively, you can just invoke **OCL->Show Xtext OCL Console** from the right button menu within the **Sample Ecore Editor** or **Sample Reflective Ecore Editor**.

The **Xtext OCL** console is new Xtext-based functionality that uses the Pivot binding. It is faster, and more compliant with the OCL specification, than the **OCL** console that uses the LPG parser and Ecore binding.

The **Interactive Xtext OCL** console comprises two main text panes. The upper pane displays results. The lower pane supports entry of queries.

Left-click to select the `Library` in the **Tutorial.xmi** as the context for a query, and then type `books` followed by a new line into the lower pane of the console.

The result of evaluating this query for the Library is shown.

Substantial OCL queries spanning many lines may be entered and so the cursor up and cursor down keys move across lines. If you want to access an earlier query, you may use the **Page Up** or **Page Down** keys to save typing them again.

You can examine the execution of the earlier query by selecting each of the books in turn and executing `library.loans->select(book=self)`, to see that `b1` has one Loan and `b2` two.

4.1.9. Helper Features and Operations

We will now introduce some helper attributes and operations to make the OCL clearer and provide a richer meta-model API. Close the **Tutorial.xmi** editor and modify the meta-model to include the derived `loans` property and the helper operation `isAvailable()`. Simplify the invariant to use the derived property.

```
class Book
{
  invariant SufficientCopies:
    library.loans->select(book=self)->size() <= copies;
  attribute name : String;
  attribute copies : Integer;
  property library#books : Library[?];
  property loans : Loan[*] { derived,volatile }
  {
    derivation: library.loans->select(book=self);
  }
  operation isAvailable() : Boolean[?]
  {
    body: loans->size() < copies;
  }
}
```

[Text for cut and paste]

Note that the derived property must also be volatile to avoid problems when a model is loaded but has no content.

Reopen **Tutorial.xmi** and select **Book b2** so that the derived property is visible in the **Properties** view.

The helper operation can be evaluated in the **Console** view by selecting book `b2` and typing `isAvailable()` for execution.

We will now add further helpers and constraints to enforce an at most two loans per member policy and to require loans to be unique.

(Don't forget to close **Tutorial.xmi** while changing its meta-model.)

```
class Member
{
  invariant AtMostTwoLoans:
    loans->size() <= 2;
  invariant UniqueLoans:
    loans->isUnique(book);
  attribute name : String;
  property library#members : Library[?];
  property loans : Loan[*] { derived,volatile }
  {
    derivation: library.loans->select(member=self);
  }
  property books : Book[*] { derived,volatile,!unique }
  {
    derivation: loans->collect(book);
  }
}
```
[Text for cut and paste]

The additional `books` property may be evaluated in the OCL Console to show which books each member has on loan. The property may also be seen in the **Properties** view.

Select the library again and invoke **Validate** from the right button menu. There are now two validation failures.

4.1.10. Generating Java Code

We have shown how OCL may be used to enrich Ecore meta-models, how model instances can be created and validated and how expressions can be evaluated, all without generating any Java code.

Exactly the same facilities are available if you do generate Java code and as a result you gain some speed benefits. By default, in the Eclipse OCL 5.0.0 (Luna) release the generated Java code for OCL is interpreted and so the speed gains occur only for the EMF models. In the Code Generation Tutorial, a preliminary release of the OCL to Java code generator is described, giving an approximately five-fold speed improvement and eliminating the need for run-time compilation.

Generating Java code is exactly the same as for any other EMF project. (Prior to EMF 2.8, there was one important difference; you must explicitly set **Operation Reflection** to true. The default for this changed to true in EMF 2.8.)

Select the **Tutorial.ecore** file and invoke **New->Other...** from the right button menu and select **Eclipse Modeling Framework** and **EMF Generator Model**.

Select **Next**.

Select **Next**.

Select **Next**.

Select **Load** and **Next**.

Select **Finish**.

The **Tutorial.genmodel** editor opens.

Most of the default settings are suitable. The one that may not be is highlighted. Select the root **Tutorial** and scroll down the **Properties** view and set **Operation Reflection** to true if it is not already true. (As from EMF 2.8 the default is true.)

You may now invoke **Generate Model Code** from the right button menu of either **Tutorial** to generate Java models that invoke OCL.

4.1.10.1. Java Details

You can check that the OCL appears in your Java by looking at **tutorial.util.TutorialValidator.java** where you'll find the OCL expression as a String awaiting compilation at run-time, and the validate invocation that triggers that compilation and execution.

```
protected static final String MEMBER__AT_MOST_TWO_LOANS__EEXPRESSION = "\n" +
  "\t\t\tloans->size() <= 2";

public boolean validateMember_AtMostTwoLoans(Member member, DiagnosticChain
            diagnostics, Map<Object, Object> context) {
  return
    validate
      (TutorialPackage.Literals.MEMBER,
       member,
       diagnostics,
       context,
       "http://www.eclipse.org/emf/2002/Ecore/OCL",
       "AtMostTwoLoans",
       MEMBER__AT_MOST_TWO_LOANS__EEXPRESSION,
       Diagnostic.ERROR,
       DIAGNOSTIC_SOURCE,
       0);
}
```

Similarly in **BookImpl** you will find the declaration of a cached delegate and the dynamic invocation that provokes the first time compilation.

```
protected static final EOperation.Internal.InvocationDelegate
  IS_AVAILABLE__EINVOCATION_DELEGATE = ((EOperation.Internal)
    TutorialPackage.Literals.BOOK___IS_AVAILABLE).getInvocationDelegate();

public boolean isAvailable() {
  try {
    return (Boolean)
        IS_AVAILABLE__EINVOCATION_DELEGATE.dynamicInvoke(this, null);
  }
  catch (InvocationTargetException ite) {
    throw new WrappedException(ite);
  }
}
```

The OCL expression for the invocation delegate may be found in **TutorialPackageImpl.createOCLAnnotations()**.

```
addAnnotation
  (getBook__IsAvailable(),
   source,
   new String[] {
   "body", "loans->size() < copies"
   });
```

4.1.10.2. API Invariants

The invariants we have used so far do not contribute to the class API.

If you want to have fine grain control of which validations are performed, perhaps because in some incremental context not all are appropriate, you may use the operation form of an invariant.

```
class Book
{
  operation sufficientCopies(diagnostics : ecore::EDiagnosticChain,
    context : ecore::EMap<ecore::EJavaObject,ecore::EJavaObject>) : Boolean
  {
  body: library.loans->select(book=self)->size() <= copies;
  }
  attribute name : String;
  attribute copies : Integer;
  property library#books : Library;
}
```

Note that the operation must have a Boolean return (true for valid) and diagnostics and context arguments.

4.1.11. Summary

To illustrate how to work with the OCL and Ecore as models we have

- Created an Ecore meta-model using the OCLinEcore text editor
- Created a dynamic model instance from that meta-model
- Enriched the meta-model with embedded OCL
- Used the embedded OCL while validating the model
- Queried the model usng the Interactive OCL Console.
- Evaluated OCL embedded in the meta-model in the Console.

To use OCL and Ecore as generated Java models we have

- Generated Java that exploits the embedded OCL.

4.2. Complete OCL tutorial

This tutorial has been updated for Eclipse Luna: Eclipse 4.4, EMF 2.10, OCL 5.0.

- Some screenshots may be slightly out of date.

4.2.1. Overview

In this example you will

- Get an Overview of the Complete OCL language
- Load a Complete OCL document into a third party application
- Enhance Ecore validation for derived properties
- Validate an Ecore model using additional Complete OCL validation
- Enhance UML validation
- Validate a UML model using additional Complete OCL validation
- Enhance Xtext validation
- Validate an Xtext grammar using additional Complete OCL validation

4.2.2. Complete OCL Utility

By itself, OCL is almost useless, since without any models to operate on, the constraints cannot achieve a great deal.

The simplest way to make OCL useful is to embed OCL expressions within a model to enrich the basic structural characteristics of a model with more complex behavior. OCLinEcore provides this capability for Ecore models. Papyrus provides comparable capabilities for UML models.

This tutorial introduces the Complete OCL language which may be used to provide a self-standing document that complements a pre-existing meta-model.

4.2.3. Load Complete OCL Tutorial Example Project

All the material for this tutorial is available as part of the CompleteOCLTutorial Example project that you may load by selecting **New** then **Example...** using the right button context menu of the Project

Explorer. This should give the **New Example** dialog in which you can select the **OCL (OCL Constraint Language) Plugins** and the **Complete OCL Tutorial**.

If you do not see these example projects, follow the [Instructions for installing the OCL Editors](#).

The resulting project has a few test files.

4.2.4. Complete OCL Language Overview

The Complete OCL language is described in detail in the [Complete OCL](#) section of this documentation. In this tutorial we will provide just a brief overview of the language. If not already open, double click on **ExtraEcoreValidation.ocl** to show the following text that provides examples of many important aspects of the Complete OCL syntax.

```
import ecore : 'http://www.eclipse.org/emf/2002/Ecore#/'

package ecore

context EModelElement
/**
 * Declare a helper operation to map an ok/warning verdict to ok/error.
 */
def: asError(verdict : Boolean) : Boolean = if verdict then true else null endif

/**
 * Extra validation for EReference and EAttribute.
 */
context EStructuralFeature

/**
 * Declare a helper property to determine whether an EStructuralFeature has an OCL derivation.
 */
def: hasDerivation : Boolean =
 eAnnotations->select(source.startsWith('http://www.eclipse.org/emf/2002/Ecore/OCL'))->notEmpty()

/**
 * If a feature has an OCL derivation, it should be transient; otherwise it is not executed.
 */
inv DerivationIsTransient: hasDerivation implies transient

/**
 * If a feature has an OCL derivation, it must be volatile;
 * otherwise the cached value suppresses execution.
 */
inv DerivationIsVolatile: asError(hasDerivation implies volatile)

/**
 * If a feature has an OCL derivation, it should not also have a default value.
 */
inv DerivationIsUninitialized: hasDerivation implies defaultValue.oclIsUndefined()

/**
 * Extra validation for just EReference.
 */
context EReference

/**
 * If a feature has an OCL derivation, it should not compete with built-in containment.
 */
inv DerivationIsNotComposed: asError(hasDerivation implies not containment)

/**
 * If a feature has an OCL derivation, it should be not waste time resolving proxies.
 */
inv DerivationDoesNotResolveProxies: hasDerivation implies not resolveProxies

/**
 * If a feature has an OCL derivation and an opposite,
 * the opposite should also have an OCL derivation
 */
inv DerivationWithOppositeHasOppositeDerivation:
 hasDerivation and eOpposite <> null implies eOpposite.hasDerivation

endpackage
```

4.2.4.1. import declarations

The import statement is a serious omission from the OMG specification, since without it, any attempt to align the Complete OCL constraints with external models relies on implementation-specific magic. The import statement is therefore an Eclipse OCL extension that is likely to be part of a future OCL specification revision.

Zero or more import statements may be present to specify the URIs of external model elements and optionally alias names for those elements. In the example:

```
import ecore : 'http://www.eclipse.org/emf/2002/Ecore#/'
```

`http://www.eclipse.org/emf/2002/Ecore` specifies the URI of the Ecore metamodel and `#/` is the fragment URI navigating to the root element which is the Ecore package. The `ecore` specifies

an alias for this package, which happens to be the same as the name of the package. Within the Complete OCL document, the imported model element may be referred to by its alias.

> The Java API support for using Complete OCL documents with the Ecore and UML bindings requires implementation-specific magic; the imported models must be loaded into the package registry by the invoking code. Import statements are not used.

> Prior to the Juno release, import statements were not understood and so there was a usage conflict. Preparation of a Complete OCL document using the Xtext editor, or usage with Pivot model and Xtext parser required import statements. But re-use with the Ecore and UML LPG parser required the import statements to be removed.

> In Juno, the LPG parser ignores the import statements, so they may be left in.

4.2.4.2. package context declaration

A package context declaration may bracket declarations that complement model elements within the complemented package.

```
package ecore

...

endpackage
```

This specifies that additional Complete OCL declarations will complement the pre-existing declarations of the `ecore` package.

Multiple package context declarations may be used to complement multiple packages.

The package context declaration may be omitted if subsequent classifier context declarations have a fully qualified name identifying the package.

4.2.4.3. classifier context declaration

A classifier context declaration introduces declarations that complement subsequent model elements within the complemented classifier.

```
context EModelElement
```

The classifier context is terminated by a `context` or an `endpackage`.

4.2.4.4. feature definitions

Additional operations and properties may be defined for use within the Complete OCL document. These features may be used as if they were part of the complemented meta-model.

```
def: asError(verdict : Boolean) : Boolean =
 if verdict then true else null endif

def: hasDerivation : Boolean = eAnnotations->select(source.startsWith(
  'http://www.eclipse.org/emf/2002/Ecore/OCL'))->notEmpty()
```

A definition starts with the new feature name, then the parameters for operations and the feature type followed by an OCL expression that evaluates the operation or the property.

For properties such as `hasDerivation` there is very little difference between a property definition `hasDerivation` and a parameter-less operation definition `hasDerivation()`. The property definition and usage is two characters shorter and may seem more natural. The operation definition has the advantage that it can be overloaded in derived classes.

4.2.4.5. class invariants

Invariants may be imposed on a complemented meta-model. The invariant comprises the name of the invariant followed by an OCL expression that evaluates true when the invariant is satisfied.

```
inv DerivationIsTransient: hasDerivation implies transient
```

These invariants are executed when a model is validated in an application that has loaded the complementing Complete OCL document. The significance of this is explained in OCL->Load Document Menu Action.

The readability of constraints can be significantly enhanced by the use of let-variables or the re-use, as above, of the `hasDerivation` helper property.

4.2.4.6. custom messages

Eclipse OCL supports two extensions to invariants that allow the validation failure messages and severities to be customized.

```
inv DerivationIsVolatile(
'"volatile" must be specified for derived feature ' + self.toString()):
asError(hasDerivation implies volatile)
```

The invariant name may be followed by a parenthesized OCL expression that computes a String to be used as the validation failure message.

The severity of a validation failure may be controlled by the non-true value evaluated by the invariant expression.

- a `false` return indicates a warning severity

- a `null` return indicates an error severity

- an `invalid` return indicates a fatal severity

See Custom Validation Messages for more details.

4.2.4.7. operation and property context declarations

Complete OCL also allows an incomplete operation or property declaration in the complemented meta-model to be completed.

- initial and derived values may be specified for properties.

- preconditions, a body and postconditions may be specified for operations.

These facilities are of limited use since OCLinEcore avoids the need for incomplete meta-models.

4.2.5. OCL->Load Document Menu Action

The major disclaimer in the above is that the Complete OCL only complements the complemented meta-model in applications that have loaded the Complete OCL.

Prior to the Juno release, this meant that Complete OCL was only usable in custom Java applications since no standard modeling applications would load the complementing document.

The **OCL->Load Document** menu action enables a Complete OCL document to be loaded into a wide variety of applications.

```
platform:/resource/org.e...                    cltutorial/model/EcoreTestFile.ecore
   Bad                              Undo          Ctrl+Z
      GenModel                      Redo          Ctrl+Y
         documentat
      Ecore                         Cut
         invocationD                Copy                      f/2002/Ecore/OCL/Pivot
         settingDeleg               Paste                     002/Ecore/OCL/Pivot
         validationDe                                         /2002/Ecore/OCL/Pivot
      BadClass                      Delete
         uncachedD
            Pivot                   Validate
               deri                 Live Validation
            (:) EBoolea             Control...

                                    Debug As        ►
                                    Run As          ►
                                    Replace With    ►
                                    OCL             ►     Load Document
                                    Team            ►
                                    Compare With    ►     Show OCL Console
                                                          Show Xtext OCL Console
                                    Load Resource...

                                    Refresh
                                    Show Properties View
```

The **OCL->Load Document** menu action is added to the right button menu of applications with a ResourceSet accessible from the current selection.

> It has been observed that the extra menu action is not always immediately available, so if you do not see it, hit **Esc** to cancel the menu, select something corresponding to a model object and right click again.

In Luna, suitable applications are

- an editor generated from an Ecore meta-model
  - the Sample Ecore Editor
  - the UML Model Editor
  - the Papyrus Model Editor
  - your model editor
- an editor generated by Xtext
  - the Xtext Editor
  - the MWE2 Editor
  - the OCLinEcore Editor
  - your DSL editor

The **OCL->Load Document** menu action activates the **Load Complete OCL Document** dialog in which you can browse Registered Complete OCL Documents, the File system or the Workspace for one or more Complete OCL documents to load, or often more conveniently you can just Drag and Drop them from an Operating System Explorer or an Eclipse Explorer.

After clicking **OK** the documents load.

> Behind the scenes, it is necessary to install global wrappers around all complemented packages. These wrappers are sensitive to the ResourceSet for which complementing has been requested and so although this incurs a small performance penalty for use of the complemented packages in other applications, it should not affect the functional behavior of other applications.

4.2.6. Example Complete OCL complements for Ecore

The Sample Ecore Editor has acquired many useful validation rules, so that for many usages just invoking **Validate** is quite sufficient. But what if it isn't? Perhaps you have some style conventions that you wish to apply. Perhaps the built-in rules are not sufficient.

Prior to Juno and the **OCL->Load Document** capability, your only choice would be to check out the Ecore Editor and create a custom variant. Now you can use Complete OCL to extend the Sample Ecore Editor.

We will revisit the **ExtraEcoreValidation.ocl** document that we have just examined and use it to rectify inadequate checking of derived properties by the Sample Ecore Editor. The document provides six invariants, at least three of which detect problems that were encountered by users during the Indigo release cycle.

4.2.6.1. DerivationIsVolatile

The EMF code generation templates have a simple treatment of `volatile`. Non-volatile variables have an associated field which is returned by the `get` operation. This overrides any derivation that might be supplied.

```
inv DerivationIsVolatile: asError(hasDerivation implies volatile)
```

We therefore want to diagnose that if an EStructuralFeature has a derivation then the volatile declaration is also present to avoid the derivation being ignored.

This problem is so serious that the basic expression is wrapped in the `asError` operation to convert the default `true` / `false` okay/warning severity into the `true` / `null` okay/error severity.

4.2.6.2. DerivationIsTransient

The EMF code generation templates have a similarly simple treatment of `transient`. Non-transient variables will be serialized as part of a model save. This is not usually appropriate since the derived value is redundant and can be recomputed when the model is loaded again.

```
inv DerivationIsTransient: hasDerivation implies transient
```

We therefore want to diagnose that a derivation is not serialized because of a default non-transient declaration.

4.2.6.3. DerivationIsNotComposed

Composition is handled directly by EMF and it is not clear that it is appropriate to define an alternate meaning of composition. It is pretty certain that EMF will not permit an alternate semantics.

```
inv DerivationIsNotComposed: asError(hasDerivation implies not containment)
```

We therefore want to diagnose if a derivation is attempting to specify alternate composition semantics and report an error if this occurs.

4.2.6.4. DerivationWithOppositeHasOppositeDerivation

Opposites are also handled directly by EMF, but it is possible to replace this functionality. However if the forward functionality is replaced, it is very unlikely that EMF's default reverse functionality will be appropriate.

```
inv DerivationWithOppositeHasOppositeDerivation:
 hasDerivation and eOpposite <> null implies eOpposite.hasDerivation
```

We therefore want to diagnose that a derivation that redefines the forward semantic of opposite also redefines the corresponding reverse semantics.

4.2.6.5. DerivationIsUninitialized

An initial value for a property may be specified as a simple default value or as a derived expression.

```
inv DerivationIsUninitialized:
 hasDerivation implies defaultValue.oclIsUndefined()
```

We want to diagnose the occlusion of the derived expression by a default value.

4.2.6.6. DerivationDoesNotResolveProxies

Derived expressions are not references.

```
inv DerivationDoesNotResolveProxies:
 hasDerivation implies not resolveProxies
```

We can therefore diagnose whether the EMF proxy resolution logic is not suppressed.

4.2.7. Validating Ecore with additional Complete OCL

In the previous section we described additional Complete OCL validation constraints to detect problems with inadequate Sample Ecore diagnosis of derived properties. We will now apply those constraints to a test file.

Select **EcoreTestFile.ecore** and use the right button menu to **Open With->Sample Ecore Model Editor**. This is probably the default for double-clicking with the left button, but if you open with the OCLinEcore editor the required validation will not work (in Juno).

Now right click within the Sample Ecore Editor pane as described in OCL->Load Document Menu Action and load **ExtraEcoreValidation.ocl**. An additional Resource is shown in the editor tree.

Select a model element such as the **Bad** package and use the right button menu to invoke **Validate**.

This shows an error. Depending on the order in which the constraints are evaluated, you may also see one or two warnings. You should use the Validity View to see all failures.

If we now open **EcoreTestFile.ecore** with the OCLinEcore editor we can see that the **transient** and **volatile** keywords are indeed missing.

```
package Bad : pfx =
    'platform:/resource/org.eclipse.ocl.examples.project.completeocltutorial/model/Bad.ecore'
{
    class BadClass
    {
        attribute uncachedDerived : Boolean { derived }
        {
            derivation: true;
        }
    }
}
```

4.2.8. Editing the Complete OCL

You may edit the Complete OCL to experiment with alternate constraints or messages.

However the Complete OCL complements the meta-model and EMF does not support live modification of meta-models. It is therefore necessary to restart the Sample Ecore Editor and Reload the modified Complete OCL document in order to exploit the changes.

> A solution for this may occur in a future release.

4.2.9. Example Complete OCL complements for UML

The extension of the Sample Ecore Editor validation described in Validating Ecore with additional Complete OCL is applicable to any tree editor generated by EMF tooling.

The **ExtraUMLValidation.ocl** file provides a very simple style check that class names start with an upper case letter.

```
import uml : 'http://www.eclipse.org/uml2/4.0.0/UML#/'

context uml::Class

/**
 * The first letter of a classname should be uppercase.
 */
inv CamelCaseName: name.at(1)=name.at(1).toUpperCase()
```

The UML meta-model is imported and an invariant is specified for the Class classifier which is fully qualified to avoid the need for a surrounding package context declaration.

You may open the **PapyrusTestFile.uml** with the UML Model Editor, load the **ExtraUMLValidation.ocl**, select the **Model** and then **Validate** in the same way as for the Ecore example.

Unfortunately, this failure is not shown directly in the Luna release; you can see the warning using the Validity View.

In Juno, The Papyrus UML editor does not use the EValidator framework and so loading Complete OCL documents into Papyrus fails to enhance validation capabilities.

At the time of writing, just before Luna, the underlying Papyrus problem has been cured but a minor problem remains. It is not clear whether this will be fixed in Papyrus 1.0.0.

4.2.10. Example Complete OCL complements for Xtext

Xtext editors use EValidator and so a Complete OCL document may be loaded into an Xtext editor, including Xtext itself, to provide enhanced validation.

The **ExtraXtextValidation.ocl** file provides some demonstration style checks.

```
import 'http://www.eclipse.org/2008/Xtext#/'

package xtext

context ReferencedMetamodel
inv NoAnonymousImports: alias <> null

context Action
inv NoActions : false

context ParserRule
inv CamelCaseName : name.matches('[A-Z][A-Za-z]*')

context xtext::TerminalRule
inv UpperName : name = name.toUpperCase()

endpackage
```

The Xtext root package is imported and within the package declaration context for the **xtext** package, invariants are supplied for four classes. These are all just examples of how constraints may use the Xtext model. It is not suggested that users should use all of these constraints for real grammars.

4.2.10.1. NoAnonymousImports

```
context ReferencedMetamodel
inv NoAnonymousImports: alias <> null
```

This invariant diagnoses whether any import statements omit the `as xxxx` model name.

4.2.10.2. NoActions

```
context Action
inv NoActions : false
```

This invariant diagnoses whenever an {xxx} action statement is used.

4.2.10.3. CamelCaseName

```
context ParserRule
inv CamelCaseName : name.matches('[A-Z][A-Za-z]*')
```

This invariant verifies that the name of a parser rule starts with an upper case letter and uses only letters.

4.2.10.4. UpperName

```
context xtext::TerminalRule
inv UpperName : name = name.toUpperCase()
```

This invariant verifies that the name of a terminal rule is uppercase.

You may open the **XtextTestFile.xtext** with the Xtext Editor, load the **ExtraXtextValidation.ocl** and then **Validate** in the same way as the Ecore example.

The additional validations appear as warning markers in the editor.

Unfortunately Xtext does not have a nice toString() method for its Concrete Syntax tree so the descriptions of erroneous elements are a little inelegant.

You may edit the Xtext test file to delete the "as ecore" in the import statement and see that the additional Complete OCL constraints are contributing to the ongoing functionality of the editor.

4.2.11. Complete OCL Editor

The Complete OCL editor is invoked automatically for an existing or new *.ocl file. You can create an empty file using either **New->File** or a partial content file using **New->Other...** followed by **OCL** and **Complete OCL File**. The editor is Xtext-based and so has most of the facilities that you find in many other Eclipse editors.

4.2.12. Royal and Loyal Example

The Royal and Loyal Example was first provided by Jos Warmer and Anneke Kleppe in *The Object Constraint Language: Getting Your Models Ready for MDA* and has subsequently been used in many tutorials. The example provides substantial examples of Complete OCL and Essential OCL. The models are available by invoking **New->Example...->OCL (Object Constraint Language) Plugins**.

4.2.13. Summary

To illustrate how to work with Complete OCL we have

- Examined the Complete OCL language
- Examined constraints to rectify inadequate Ecore validation of derived features
- Loaded Complete OCL constraints to enhance validation of an Ecore model
- Loaded Complete OCL constraints to enhance validation of a UML model
- Loaded Complete OCL constraints to enhance validation of an Xtext grammar

4.3. Code Generation tutorial

This tutorial has been updated for Eclipse Luna: Eclipse 4.4, EMF 2.10, OCL 5.0.

- Some screenshots may be slightly out of date.

The direct OCL to Java Code generator was a very experimental functionality for the Juno release. It has been substantially rewritten for Kepler. Some optimisations have been activated for Luna.

In this tutorial we will continue the OCLinEcore tutorial and show how to get a direct Java representation of the Ecore model avoiding the need for run-time compilation.

4.3.1. Load OCLinEcore Tutorial Example Project

All the material for this tutorial is available as part of the OCLinEcore Example project that you may load by selecting **New** then **Example...** using the right button context menu of the Project Explorer. This should give the **New Example** dialog in which you can select the **OCL (OCL Constraint Language) Plugins** and the **OCLinEcore Tutorial**.

4.3.2. Direct code

In Generating Java Code we saw how to create a genmodel and how to generate code from it that realizes OCL as text strings in the Java implementation files. These text string are lazily compiled at run-time.

Whether to generate OCL as text strings for interpretation or to convert directly to Java is determined by the Code Generation Mode. This may be configured using the project property or workspace preference as described in Code Generation Mode. So use **Window->Preferences->OCL** to change the setting to **Generate Java code in xxxBodies classes**.

Now open **Tutorial.genmodel**, select the root resource and invoke **Generate Model Code** to (re)generate the Java code. This will take somewhat longer as additional work items show that the OCL is being compiled and that Xtend templates are generating additional Java code.

Note that you must close **Tutorial.genmodel** while changing the Code Generation Mode.

You may also need to delete the autogenerated *Impl files if you change from one mode of generation to another.

That is all there is to it. Your model code is now 100% Java; no OCL parsing is needed at run-time.

4.3.3. Using a GenAnnotation

Changing the default genmodel setting is a little dangerous since the change will affect any other genmodel activities you perform. It is therefore advisable to reset the workspace preference setting to its default and use a GenAnnotation to embed the setting in the genmodel.

The easiest way to create the GenAnnotation that ensure direct code generation regardless of workspace or project preferences, is to paste the following three lines into your genmodel just above the `foreignModel` or `genpackages` element.

```
<genAnnotations source="http://www.eclipse.org/OCL/GenModel">
  <details key="Use Delegates" value="false"/>
</genAnnotations>
```

Of course, if you want to enforce delegation you should set the `value` to `true`.

If you don't like cutting and pasting into XMI files, you can achieve the same effect with the GenModel editor by:

- Enable annotation display using **Generator->Show Annotations**
- Invoke **Annotate** from the right button context menu of the genmodel root element
- Use the **Properties View** to set the GenAnnotation source to `http://www.eclipse.org/OCL/GenModel`
- Invoke **Add Detail** from the right button context menu of the GenAnnotation
- Use the **Properties View** to set the Detail key to `Use Delegates`
- Use the **Properties View** to set the Detail value to `false`

A further "Use Null Annotations" GenAnnotation may be used to control whether @NonNull and @Nullable annotations are emitted in the generated code.

```
<genAnnotations source="http://www.eclipse.org/OCL/GenModel">
  <details key="Use Delegates" value="false"/>
  <details key="Use Null Annotations" value="true"/>
</genAnnotations>
```

4.4. Debugger tutorial

This tutorial was written for Eclipse Luna: Eclipse 4.4, EMF 2.10, OCL 5.0.

- Some screenshots may be slightly out of date.

In this tutorial we will continue the OCLinEcore tutorial and show how to use the OCL debugger to debug:

- constraints typed manually in the Console View

- embedded OCLinEcore validation failures from the Validity View

- Complete OCL validation failures from the Validity View

4.4.1. Load OCLinEcore Tutorial Example Project

The material for the first two parts of this tutorial is available as part of the OCLinEcore Example project that you may load by selecting **New** then **Example...** using the right button context menu of the Project Explorer. This should give the **New Example** dialog in which you can select the **OCL (OCL Constraint Language) Plugins** and the **OCLinEcore Tutorial**.

The material for the third parts of this tutorial is available as part of the CompleteOCL Example project that you may load in a similar way.

4.4.2. The OCL Debugger

The OCL debugger is a customization of the Eclipse debugger framework, so most of its functionality should present few surprises to those familiar with the Java debugger.

There is:

- a Stack View that shows the current line number in nested Evaluation Environments

- a Variables View in which local and intermediate variables can be re-examined

- an Editor in which the source is highlighted to show the next AST node to be evaluated

- an Outline in which the source is shown in tree form

- a Breakpoints View in which breakpoints can be controlled

We will demonstrate some of these facilities by debugging a simple example.

4.4.3. Very Simple Debug session

We will debug the execution of the OCL expression **self.name** on an EPackage.

4.4.3.1. Starting the debugger

Double click on **model/Tutorial.ecore** to open the model and expand the top entry to show the EPackage.

If the model opens with another editor, close it, and open with the Sample Ecore Editor by selecting **model/Tutorial.ecore** and then **Open With->Sample Ecore Model Editor** from the context menu.

Select the **tutorial** EPackage and invoke **OCL->Show Xtext OCL Console** from the context menu. (Wait a second or two.)

At the bottom of the Console window type **self.name**, then hit the Enter key. Then hit the Page Up key to redisplay your entry.

The Console runs an evaluation automatically after hitting Enter and shows the evaluation result: **'tutorial'**.

The Console View provides the two pieces of information necessary to run the OCL debugger:

- an EObject to be used as OCL's **self**; the Console shows the current selection just below its tool bar
- an OCL expression to execute

Start the debugger by clicking the debug icon in the Console View tool bar. (Wait a second or two.)

The debugger should appear automatically. If it doesn't, your start-debugger-automatically-on-resume preference has inhibited it. You can open the Debug perspective manually by invoking **Window->Open Perspective->Debug** from the Eclipse menu bar.

A Complete OCL document is created automatically to encapsulate the OCL expression inside as an additional operation for the type of the self object. This document is shown in the editor; it is readonly. **self** is highlighted since the next evaluation to perform is to evaluate the VariableExp AST node that performs the self access.

The stack display shows the context as line 5 of oclDebugExpression() in the synthesized Complete OCL document.

The Variables View shows two variables.

- **self** is the OCL self object
- **$pc** is a synthetic variable representing the current Program Counter

---

The Outline View currently displays the OCL Concrete Syntax tree; you may choose to close this view. In a future release it may change to support breakpoints and the Abstract Syntax Tree.

4.4.3.2. Exploring Variables

The Variables View provides an ability to drill down arbitrarily to examine the data available to your program.

The left column of the display presents the name of a variable and may be expanded to navigate to parts of the data referenced by the variable. Part name displays are currently shown 0-based, rather than 1-based as in OCL.

The right column variously displays the type of parts that can be expanded and the values of those that cannot. An OCL syntax is used so Strings appear in single quotes and Collections use names such as OrderedSet.

The bottom line shows a textual rendering of the selected variable. For many types of data a helpful rendering is available. For others the fallback is to the default Java toString() functionality.

Click on the expand/collapse icon to the left of **$pc** to expand it and allow inspection of the OCL AST. A VariableExp is next to execute and its **$pc.referredVariable** or **$pc.type** may be examined to see more program detail.

Click on the expand/collapse icon to the left of **self**, which is an **ecore::EPackage**, to expand it and shows its fields such as **name** which is **'tutorial'**.

Click on the expand/collapse icon to the left of **self.eClassifiers** to show the four classifiers.

Select **self.eClassifiers[1]** so that the bottom line display shows that the second is named Book.

The Variables View provides more insight that the Sample Ecore Properties View, so you may find it convenient to use a trivial OCL debugger session using **self** as the OCL expression to browse arbitrary model data.

4.4.3.3. Stepping Execution

Click F5 or the **Step Into** icon to advance execution by one AST node evaluation.

The editor now highlights **.name** and **$pc** shows a PropertCallyExp as the next execution. **$pc.referredVariable** shows that it is **ecore::ENamedElement:name**.

An additional synthetic variable **$source** shows the result of the **self** evaluation that forms the source term of the PropertyCallExp. As expected this is the same as **self**.

Click F5 or the **Step Into** icon again to advance execution by a further AST node evaluation.

The whole of **self.name** is highlighted and **$pc** shows that the overall ExpressionInOCL is about to be evaluated. The synthetic **$bodyExpression** for its input shows that **self.name** evaluated to **'tutorial'**.

4.4.4. Debugging a Validation failure

OCL is useful for elaborating models with additional well-formedness rules, but when these fail it can be difficult to understand why a failure occurred, particularly if the bug is in the OCL rather than the model. We will now show how the OCL debugger can be used to debug a validation failure.

Double click on **model/Tutorial.xmi** to open the model, and expand the top two entries to show some detail.

If the model opens with another editor, close it, and open with the Sample Reflective Ecore Model Editor by selecting **model/Tutorial.xmi** and then **Open With->Sample Reflective Ecore Model Editor** from the context menu.

Select the first line and invoke **Validate** from the context menu. (Wait a second.) Optionally click on Details.

These error messages provide insufficient precision to really understand the problems, so click **OK** to dismiss the popup then select **Book b2**, which has an error, and invoke **OCL->Show Validity View** to provide more insight.

Click the **Pin** icon in the Validity View tool bar to avoid thrashing whenever you change mouse selection.

Uncheck the top **ecore** line in the Metamodel Constraints since we are not interested in the successful Ecore metamodel constraints just those in the **tutorial** metamodel.

Similarly uncheck the bottom line in the Model Elements since we are not interested in the successful metamodel, just those in the tutorial model.

Click on the + tool bar icon so that the detail is shown.

We will now debug the failure of the **tutorial::Book::SufficientCopies** on the **Library lib::Book b2** model element. Select either of the leaf warnings, that is either the **tutorial::Book::SufficientCopies** child of **Book b2** in the left hand pane, or the **Library lib::Book b2** child of **SufficientCopies** in the right hand pane, and invoke **Debug Single Enabled Selection**. Wait a second or two and the debugger starts. If it doesn't, open the Debugger perspective manually.

The debugger shows **library.loans->select((book = self))->size() <= copies** with **library** highlighted as the next execution. The **library** is a shorthand for **self.library** so **$pc** in the Variables View shows a VariableExp for self as the next instruction.

Click F5 or **Step Into** and **$pc** advances but the editor highlight is unchanged since there is insufficient source detail to distinguish the original **self** from the subsequent **.library**.

Click F5 or **Step Into** a few more times and the highlight will show the iteration within the **select** body, allowing each state of each element to be examined to determine why the exhibited behavior occurs.

Continue to Click F5 or **Step Into** until **->size()** is highlighted.

Expanding **$source** in the Variables View shows the Set of three selected Loans each of which has the same book as self.

Click F5 or **Step Into** three more times until <= is highlighted.

We can now see that the **$source**, left hand side, of the comparison is 3 and the **$argument[0]**, right hand side is 2. A further step and we see the result as **$bodyExpression** demonstrating why the validation failed.

4.4.5. Debugging Complete OCL validation failure

The two preceding examples displayed their source text in a synthesized Complete OCL document.

In this example we debug a failure fir which the OCL is already available in a Complete OCL document.

Open the **model/EcoreTestFile.ecore** from the Complete OCL project using the Sample Ecore Editor.

Within the Ecore editor use **OCL->Load Document** and then drag and drop **model/ExtraEcoreValidation.ocl** and click **OK** to dismiss the pop up.

Again within the Ecore editor use **OCL->Show Validity View** to see the constraint/element pairs. *If the Validity View was already visible, close it and re-show it since in Luna addition of a Complete OCL document fails to refresh correctly.*

In the Validity View, uncheck the top two MetaModel Constraint contributions retaining just the ExtraEcoreValidation.ocl contributions. Click the plus icon in the Metamodel Constraint tool bar to expand all entries.

Select the bottom right BadClass model element below the DerivationIsVolatile constraint and invoke **Debug Single Enabled Selection**. (wait a second or two). The debugger should start, if not open the Debugger perspective manually.

Both **asError** and **hasDerivation** are OCL-defined so as you step you successively navigate into the defined property and operation.

4.4.6. Console experiments

While debugging, the original OCL expression from the Console is presented in a Complete OCL editor. This editor is readonly so you cannot edit it to correct mistakes or to experiment.

You may however safely use the OCL Console to perform further experiments. Select a suitable self object in the Variable View and cut and paste to prepare your experimental OCL expression.

In Luna, Console selections cannot be Collections so you are unfortunately restricted to single objects.

4.4.7. Longer range stepping

In the examples above we have only used F5 or **Step Into**.

In principle the tedious stepping through an iteration can be avoided by F7 or **Step Return** which should terminate on the popped evaluation environment at the end of the iteration. *This facility has not been adequately tested in Luna*.

If you arrange for some line breaks in your source text you can use F6 or **Step Next** to proceed until the line number advances. *This facility has not been adequately tested in Luna*. Line breaks can be added in the OCL Console using Shift and Enter together.

4.4.8. Break points

When debugging OCL from Complete OCL documents, the original document is a suitable source for the debugger and so line breakpoints can be set. *This facility has not been adequately tested in Luna*

4.5. Validation tutorial

This tutorial was written for Eclipse Luna: Eclipse 4.4, EMF 2.10, OCL 5.0.

- Some screenshots may be slightly out of date.

The standard EMF validation facilities are very useful for avoiding model errors and work well when the models are correct or at least nearly correct. In this tutorial we show how the Validity View can provide greater insight into what works and what doesn't.

We will show how to

- identify all constraints applicable to a particular model element
  - the constraint text
  - the validation status
- identify all model elements constrained by a particular constraint
  - the constraint text
  - the validation status
- filter the displayed model elements and constraints
  - by name
  - by status
  - by model
  - by metamodel
- launch an OCL debugger for a particular model element and constraint

4.5.1. Load Complete OCL Tutorial Example Project

The material for this tutorial is available as part of the Complete OCL Example project that you may load by selecting **New** then **Example...** using the right button context menu of the Project Explorer. This should give the **New Example** dialog in which you can select the OCL (OCL Constraint Language) Plugins and the Complete OCL Tutorial.

4.5.2. Load Test Model

Double click on **model/XMITestFile.xmi** to open the model and expand the top entry to show the EPackage.

If the model opens with another editor, close it, and open with the Sample Reflective Ecore Editor by selecting **model/Tutorial.ecore** and then **Open With->Sample Reflective Ecore Model Editor** from the context menu.

Within the editor invoke **OCL->Load Document** to load **model/ExtraEcoreValidation.ocl** and again to load **model/ExtraXMIValidation.ocl**

Your source ResourceSet now contains four resources

- the XMITestFile.xmi model

- the EcoreTestFile.ecore metamodel

- the ExtraXMIValidation.ocl additional model validation rules

- the ExtraEcoreValidation.ocl additional metamodel validation rules

4.5.3. EMF Validation

Select the **XMITestFile.xmi** and invoke **Validate** from the context menu. Click **OK** to dismiss.

Select the **EcoreTestFile.ecore** and invoke **Validate** from the context menu. Click **OK** to dismiss.

The above results clearly show problems, but not necessarily all the problems and do not show what was actually done. Sometimes validation of a model element terminates prematurely once an error has been reported. On other occasions some constraints are not run and so no corresponding errors are detected.

The above limitations are not a problem, when everything is working well, but when you have a misunderstanding as to what is being validated, a bad day can get very much worse.

4.5.3.1. Validaty View Validation

Select **OCL->Show Validity View** from the editor context menu.

The left hand pane shows the root model elements in a similar way to the Sample Reflective Ecore Editor.

The right hand pane shows the root metamodel constraint sources.

Each may be expanded using the control at the start of each line or the more general controls in the tool bars.

Important tip: click the pin icon in the Validity Model tool bar to stop the Validity View chasing your mouse selections.

You may now obtain the more detailed validation results by clicking on the green Run icon in the main Validation View tool bar.

Use the hover text to see how many validations have been rounded up into each root display.

4.5.3.2. Filtering by Root Models

There are 36 results in total, which is more than we want to look at, even for this very small model.

The **ecore in http://www.eclipse.org/emf/2002/Ecore** root constraint is contributing 30 successes without problem, so we ignore it by unchecking the enable checkbox preceding it.

The **basecs in http://www.eclipse.org/ocl/3.1.0/BaseCST** root constraint similarly contributing 2 successes without problem, so we ignore it as well by unchecking the enable checkbox preceding it.

The model is so simple that we can now expand it completely. Click on the + expand icons.

You can hover over constraints to see the details and invoke **Show In Editor** to navigate to them.

4.5.3.3. Filtering by Status

The many successes are often of limited interest, so we may concentrate on Errors by invoking **Show all Errors** from the Filtering pull down towards the right of the main Validation View tool bar.

Having found an error of interest we can see it in context. Select the error, remove the **Show all Errors** filtering, and enable the view of all constraints by clicking the tick icon in the Model Constraint pane tool bar.

This shows the error, two warnings and seven successes.

Double clicking on the erroneous child constraint makes the constraint visible in the right hand pane, showing that the constraint is only applied to this one model element.

4.5.3.4. Debugging constraints

Maybe it's time for some debugging. Select the leaf constraint below a model element, or the leaf element below a constraint and invoke **Debug Single Enabled Selection** to start the OCL debugger to step through the problematic constraint on the problematic model element. (Select the debugger perspective explicitly if it doesn't open automatically.)

Use of the OCL debugger is described in the Debugger Tutorial.

4.6. Working with Classic OCL

4.6.1. Overview

This tutorial illustrates the various services provided by the Classic Eclipse OCL implementation.

4.6.2. References

This tutorial assumes that the reader is familiar with the Eclipse extension point architecture. There is an abundance of on-line help in Eclipse for those unfamiliar with extension points.

To see the complete source code for the examples shown in this tutorial, install the OCL Interpreter Example plug-in into your workspace.

Other references:

- For an environment in which to test the OCL expressions that you will create in this tutorial, install the Library Metamodel example.

- OCL 2.0 specification.

4.6.3. Parsing OCL Expressions

The first responsibility of the OCL interpreter is to parse OCL expressions. One of the purposes of parsing an expression is to validate it: if it can be parsed, it is well-formed (the parser automatically validates the expression against the semantic well-formedness rules).

The main entrypoint into the OCL API is the OCL class. An OCL provides an autonomous OCL parsing environment. It tracks all constraints that are parsed in this environment, including the definitions of additional operations and attributes. The OCL.newInstance() factory method is used to create a new OCL with an EnvironmentFactory that provides the binding to a particular metamodel (Ecore or UML). In this tutorial, we will use the Ecore binding.

To parse a query expression, we will use the OCLHelper object, which provides convenient operations for parsing queries and constraints (intended for processing constraints embedded in models).

```
boolean valid;
OCLExpression<EClassifier> query = null;

try {
    // create an OCL instance for Ecore
    OCL<?, EClassifier, ?, ?, ?, ?, ?, ?, ?, Constraint, EClass, EObject> ocl;
    ocl = OCL.newInstance(EcoreEnvironmentFactory.INSTANCE);

    // create an OCL helper object
    OCLHelper<EClassifier, ?, ?, Constraint> helper = ocl.createOCLHelper();

    // set the OCL context classifier
    helper.setContext(EXTLibraryPackage.Literals.WRITER);

    query = helper.createQuery("self.books->collect(b : Book | b.category)->asSet()");

    // record success
    valid = true;
} catch (ParserException e) {
    // record failure to parse
    valid = false;
    System.err.println(e.getLocalizedMessage());
}
```

The example above parses an expression that computes the distinct categories of Book s associated with a Writer. The possible reasons why it would fail to parse (in which case a ParserException is thrown) include:

- syntactical problems: misplaced or missing constructs such as closing

parentheses, variable declarations, type expressions, etc.

- semantic problems: unknown attributes or operations of the context

type or referenced types, unknown packages, classes, etc.

4.6.4. Parsing OCL Constraints

OCL is primarily intended for the specification of *constraint* s. Unlike queries, there are a variety of different kinds of constraints used in different places in a model. These include classifier invariants, operation constraints, and attribute derivation constraints. The OCLHelper can parse these for us.

Let's imagine the confusion that arises from a library that has more than one book of the same title (we are not intending to model copies). We will create an invariant constraint for @Book@s stipulating that this is not permitted:

```
Constraint invariant = null;

try {
    // set the OCL context classifier
    helper.setContext(EXTLibraryPackage.Literals.LIBRARY);

    invariant = helper.createInvariant(
        "Library.allInstances()->forAll(b1, b2 | b1 <> b2 implies b1.title <> b2.title)");
} catch (ParserException e) {
    // record failure to parse
    System.err.println(e.getLocalizedMessage());
}
```

Parsing constraints differs from parsing query expressions because they have additional well-formedness rules that the parser checks. For example, an invariant constraint must be boolean-valued, an attribute derivation constraint must conform to the type of the attribute, and such constructs as @pre and `oclIsNew()` may only be used in operation post-condition constraints.

4.6.5. Evaluating OCL Expressions and Constraints

More interesting than parsing an OCL expression or constraint is evaluating it on some object. The [Query](#) interface provides two methods for evaluating expressions. Queries are constructed by factory methods on the `OCL` class.

- [Object evaluate(Object)](#)

evaluates the expression on the specified object, returning the result. The caller is expected to know the result type, which could be a primitive, `EObject`, or a collection. There are variants of this method for evaluation of the query on multiple objects and on no object at all (for queries that require no "self" context).

- [boolean evaluate(Object)](#)

This method evaluates a special kind of OCL expression called a *constraint*. Constraints are distinguished from other OCL queries by having a boolean value; thus, they can be used to implement invariant or pre/post-condition constraints. There are variants for checking multiple objects and for selecting/rejecting elements of a list that satisfy the constraint.

In order to support the `allInstances()` operation on OCL types, the `OCL` API provides the

[setExtentMap(Map<CLS, ? extends Set<? extends E>> extentMap)](#) method. This assigns a mapping of classes (in the Ecore binding, `EClass` es) to the sets of their instances. By default, the `OCL` provides a dynamic map that computes the extents on demand from the contents of a `Resource`. An alternative extent map can be found in [org.eclipse.ocl.ecore.opposites.ExtentMap](#). We will use a custom extent map in evaluating a query expression that finds books that have the same title as a designated book:

```
// create an extent map
Map<EClass, Set<? extends EObject>> extents = new HashMap<EClass, Set<? extends EObject>>(
Set<Book> books = new HashSet<Book>();
extents.put(EXTLibraryPackage.Literals.BOOK, books);

// tell the OCL environment what our classifier extents are
ocl.setExtentMap(extents);

Library library = EXTLibraryFactory.eINSTANCE.createLibrary();

Book myBook = EXTLibraryFactory.eINSTANCE.createBook();
myBook.setTitle("David Copperfield");
books.add(myBook);

// this book is in our library
library.add(myBook);

Writer dickens = EXTLibraryFactory.eINSTANCE.createWriter();
dickens.setName("Charles Dickens");

Book aBook = EXTLibraryFactory.eINSTANCE.createBook();
aBook.setTitle("The Pickwick Papers");
aBook.setCategory(BookCategory.MYSTERY_LITERAL);
books.add(aBook);
aBook = EXTLibraryFactory.eINSTANCE.createBook();
aBook.setTitle("David Copperfield");
aBook.setCategory(BookCategory.BIOGRAPHY_LITERAL);  // not actually, of course!
books.add(aBook);
aBook = EXTLibraryFactory.eINSTANCE.createBook();
aBook.setTitle("Nicholas Nickleby");
aBook.setCategory(BookCategory.BIOGRAPHY_LITERAL);  // not really
books.add(aBook);

dickens.addAll(books);  // Dickens wrote these books
library.addAll(books);  // and they are all in our library

// use the query expression parsed before to create a Query
Query<EClassifier, EClass, EObject> eval = ocl.createQuery(query);

Collection<?> result = (Collection<?>) eval.evaluate(dickens);
System.out.println(result);
```

The same `Query` API is used to check constraints. Using the `library` and `extents` map from above and the constraint parsed previously:

```
eval = ocl.createQuery(constraint);

boolean ok = eval.check(library);

System.out.println(ok);
```

4.6.6. Implementing Content Assist

The `OCLHelper` interface provides an operation that computes content-assist proposals in an abstract form, as `Choice` s. An application's UI can then convert these to JFace's `ICompletionProposal` type.

Obtaining completion choices consists of supplying a partial OCL expression (up to the cursor location in the UI editor) to the `OCLHelper::getSyntaxHelp(ConstraintKind,  String) `, java.lang.String) method. This method requires a `ConstraintKind` enumeration indicating the type of constraint that is to be parsed (some OCL constructs are restricted in the kinds of constraints in which they may be used).

```
helper.setContext(EXTLibraryPackage.Literals.BOOK);

List<Choice> choices = helper.getSyntaxHelp(
    ConstraintKind.INVARIANT,
    "Book.allInstances()->excluding(self).");

for (Choice next : choices) {
    switch (next.getKind()) {
    case OPERATION:
    case SIGNAL:
        // the description is already complete
        System.out.println(next.getDescription());
    case PROPERTY:
    case ENUMERATION_LITERAL:
    case VARIABLE:
        System.out.println(next.getName() + " : " + next.getDescription());
        break;
    default:
        System.out.println(next.getName());
        break;
    }
}
```

A sample of the output looks like:

```
author : Writer
title : String
oclIsKindOf(typespec : OclType)
oclAsType(typespec : OclType) : T
...
```

The choices also provide the model element that they represent, from which a more sophisticated application can construct appropriate JFace completions, including context information, documentation, etc.

4.6.7. Working with the AST

The OCL Interpreter models the OCL language using EMF's Ecore with support for Java-style generic types. The bindings of this generic Abstract Syntax Model for Ecore and for UML substitutes these metamodels' constructs for the generic type parameters, plugging in the definitions of the "classifier", "operation", "constraint", etc. constructs of the OCL vocabulary. These bindings, then, support persistence in or as an adjunct to Ecore and UML models.

For processing the abstract syntax tree (AST) parsed from OCL text, the API supplies a _Visitor_ interface. By implementing this interface (or extending the _AbstractVisitor_ class, which is recommended), we can walk the AST of an OCL expression to transform it in some way. This is exactly what the interpreter, itself, does to evaluate an expression: it just walks the expression using an evaluation visitor. For example, we can count the number times that a specific attribute is referenced in an expression:

```
helper.setContext(EXTLibraryPackage.Literals.BOOK);

OCLExpression<EClassifier> query = helper.parseQuery(
    "Book.allInstances()->select(b : Book | b <> self and b.title = self.title)");

AttributeCounter visitor = new AttributeCounter(
    EXTLibraryPackage.Literals.BOOK__TITLE);

System.out.println(
    "Number of accesses to the 'Book::title' attribute: " + query.accept(visitor));
```

where the visitor is defined thus:

```
class AttributeCounter extends AbstractVisitor<Integer,
  EClassifier, EOperation, EStructuralFeature, EEnumLiteral,
  EParameter, EObject, EObject, EObject, Constraint> {
    private final EAttribute attribute;

    AttributeCounter(EAttribute attribute) {
        super(0);  // initialize the result of the AST visitiation to zero
        this.attribute = attribute;
    }

    protected Integer handlePropertyCallExp(PropertyCallExp<EClassifier, EStructuralFeature
      Integer sourceResult, List<Integer> sourceResults) {
        if (callExp.getReferredProperty() == attribute) {
            // count one
            result++;
        }

        return result;
    }
}
```

4.6.8. Serialization

Because the OCL expression AST is a graph of EMF objects, we can serialize it to an XMI file and deserialize it again later. To save our example expression, we start over by initializing our OCL instance with a resource in which it will persist the environment and in which we will persist the parsed expression. The key is in the persistence of the environment: OCL defines a variety of classes on the fly by template instantiation. These include collection types, tuple types, and message types. Other elements needing to be persisted are additional operations and attributes that may be defined in the local environment.

```
// create a resource in which to store our parsed OCL expressions and constraints
Resource res = resourceSet.createResource(
    URI.createPlatformResourceURI("/MyProject/myOcl.xmi", true);

// initialize a new OCL environment, persisted in this resource
ocl = OCL.newInstance(EcoreEnvironmentFactory.INSTANCE, res);

// for the new OCL environment, create a new helper
helper = OCL.createOCLHelper();

helper.setContext(EXTLibraryPackage.Literals.BOOK);

// try a very simple expression
OCLExpression<EClassifier> query = helper.createQuery("self.title");

// store our query in this resource.  All of its necessary environment has
// already been stored, so we insert the query as the first resource root
res.getContents().add(0, query);

res.save(Collections.emptyMap());
res.unload();
```

To load a saved OCL expression is just as easy:

```
Resource res = resourceSet.getResource(
    URI.createPlatformResourceURI("/MyProject/myOcl.xmi", true),
    true;

@SuppressWarnings("unchecked")
OCLExpression<EClassifier> query = (OCLExpression<EClassifier>) res.getContents().get(0);

System.out.println(ocl.evaluate(myBook, query));
```

In the snippet above, we used the OCL's convenience method for a one-shot evaluation of a query. Looking at the contents of the XMI document that we saved, we see that the self variable declaration is not

---

owned by the query expression, but is, rather, free-standing. The `ExpressionInOCL` metaclass solves this problem by providing properties that contain context variable declarations, including `self` and (in the context of operations) operation parameters.

```
<?xml version="1.0" encoding="ASCII"?>
<xmi:XMI xmi:version="2.0" xmlns:xmi="http://www.omg.org/XMI" xmlns:xsi="http://www.w3.org
  <ocl.ecore:PropertyCallExp xmi:id="_897fVPfmEduCQ48h829a5g">
    <eType xsi:type="ocl.ecore:PrimitiveType" href="http://www.eclipse.org/ocl/1.1.0/oclsto
    <source xsi:type="ocl.ecore:VariableExp" xmi:id="_897fVvfmEduCQ48h829a5g" name="self"
      <eType xsi:type="ecore:EClass" href="http:///org/eclipse/emf/examples/library/extlib
    </source>
    <referredProperty xsi:type="ecore:EAttribute" href="http:///org/eclipse/emf/examples/l
  </ocl.ecore:PropertyCallExp>
  <ocl.ecore:Variable xmi:id="_897fUvfmEduCQ48h829a5g" name="self">
    <eType xsi:type="ecore:EClass" href="http:///org/eclipse/emf/examples/library/extlibra
  </ocl.ecore:Variable>
</xmi:XMI>
```

4.6.9. Summary

To illustrate how to work with the OCL API, we

- Parsed and validated OCL expressions and constraints.

- Evaluated OCL query expressions and constraints.

- Obtained content-assist suggestions for the completion of OCL expressions.

- Transformed an OCL expression AST using the *Visitor* pattern.

- Saved and loaded OCL expressions to/from XMI resources.

4.7. Installing the Eclipse OCL Examples and Editors

These instructions have been updated for Eclipse Luna; Eclipse 4.4, EMF 2.10, OCL 5.0.

- Some screenshots may be slightly out of date.

The OCL User Interface (console, editors, debugger and validity view) is not part of the core OCL functionality included in the Eclipse Modeling Tools Package, so although you may have OCL installed and be able to read this tutorial via the **Help->Help Contents->OCL Documentation**, you may not have the OCL examples installed.

An easy way to test whether you have the OCL Examples installed is to right click on a *.ecore file and see whether **OCLinEcore Editor** appears in the **Open With** submenu.

If OCL is not installed at all, or if just the examples are not installed, the following installation step will automatically install the OCL Examples and all required projects such as **EMF**, **UML2**, **MWE2**, **Xpand** and **Xtext**.

Left-click on **Help** in the Eclipse menu-bar then left-click on **Install New Software...** and select the **Luna – http://download.eclipse.org/releases/luna** update site from the pull-down menu to **Work with** and be patient while the available updates are identified. Then type **OCL** in the filter text, click on the expand item preceding the **Modeling** category and then check **OCL Examples and Editors SDK**.

Select **Next**.

Select **Next** again and read the license agreement. Set to accept it.

Select **Finish** and be patient while the software is downloaded and installed. Select **Restart Now** when prompted to do so.

4.7.1. Troubleshooting

Eclipse Modeling Projects have a large number of classes and so require a large amount of PermGen space on a Sun JVM. If you are using default Eclipse startup settings you are liable to encounter OutOfMemoryExceptions. Therefore follow the advice in How do I start Eclipse and set XX:PermSize to at least 64M, either on your Eclipse command line, or your Eclipse shortcut or in the **eclipse.ini** adjacent to **eclipse.exe**. If you are using a 64 bit machine or plan to use graphical modeling tools such as Papyrus or Sirius, 128M is almost certainly necessary.

Chapter 5. Examples

5.1. Royal and Loyal Example Project

The RoyalAndLoyal example project provides a substantial example of a Complete OCL document complementing an independent Ecore meta-model.

This is the standard example used in many OCL texts and courses. It was first produced as part of the *The Object Constraint Language Second Edition* by *Jos Warmer* and *Anneke Kleppe*.

This example may be used to explore a wide variety of OCL syntaxes and their presentation in the Complete OCL editor.

You may install the example by selecting **Example...** from the **New** menu, then selecting **Royal and Loyal Example** under the **OCL (Object Constraint Language) plugins**.

Open **RoyalAndLoyal.ecore** with the OCLinEcore editor to explore the Ecore metamodel. Note how the Outline can be alphabeticized and so provide a useful overview. The outline very similar to the conventional Sample Ecore Editor tree view.

Open **RoyalAndLoyal.ocl** with the CompleteOCL editor to explore the OCL. Note how the full AST can be explored in the Outline.

5.2. Empty Example Project

The Empty example project creates an empty project with a Java class path set up to assist in the use of OCL.

This assistance is not really necessary now that the editors are based on Xtext and now that an XMI representation is not automatically saved in a **bin** directory.

The OCL editors can bed used wherever Ecore editors can be used.

It is not necessary for a project to have a Java nature.

It is not necessary for a project to have an Xtext nature. If you add an Xtext nature, your OCL files will be built automatically when other files in the project or its dependencies change. This can significantly clutter the Problems View if you have problems with your OCL, and may significantly increase build times.

5.3. OCLinEcore Tutorial Example Project

The OCLinEcore Tutorial project provides the conclusion of the OCLinEcore Tutorial and the material for the Getting Started quick introduction.

The project provides an example of OCL embedded in Ecore that is also used by the Code Generation Tutorial and Debugger tutorial.

5.4. Complete OCL Tutorial Example Project

The Complete OCL Tutorial project provides examples for the the Complete OCL Tutorial.

The project provides examples Complete OCL documents that complement Ecore, UML, Xtext and XMI.

5.5. OCL Interpreter Example

5.5.1. Introduction

This example illustrates the usage of the generic OCL Parser API to parse and evaluate OCL query expressions and constraints within the SDK. It demonstrates how to author OCL expressions and evaluate them against elements of library model instances, or against Ecore and UML elements. For Ecore and UML models, a further option of parsing (not evaluating) model-level (M1 in the OMG modeling stack) constraints is available.

5.5.2. References

Please refer to the document Object Constraint Language Examples Overview for reviewing the library meta-model used as the basis for demonstrating the capabilities in this example.

5.5.3. Description

This example plug-in is named `org.eclipse.emf.ocl.examples.interpreter`. This plug-in contributes the `OCL Interpreter` menu to the library editor's main menu and context menu. The menu has one item:

- `Show Console`: Opens the interactive OCL console.

Please refer to the tutorial OCL Interpreter Tutorial for reviewing the code samples within this example.

The bottom field in the console accepts OCL expressions (comments supported). You can press **Enter** to evaluate on the currently selected element. You can press **Ctrl**+**Enter** or **Shift**+**Enter** to insert a newline. The top field shows the output and errors. The console can be cleared by the **Eraser** button and closed by the **X** button.

Because the `EXTLibrary` model is based on the Ecore metamodel, ensure that the `Ecore` metamodel is selected in the console's tool bar. Also ensure that the `M2` modeling level is selected, as `EXTLibrary` is not a metamodel, so instances of it are not models. Thus, the OCL expressions that we create will target the Ecore meta-model, as the model of the EXTLibrary model.

Content-assist is automatically activated on typing any of " .", " ->", " ::", and " ^". Also, `Ctrl`+`Space` can be used to invoke content-assist at any time.

5.5.4. Support for Ecore and UML Models

The OCL Console contributes an **OCL->Show OCL Console** menu action to the Ecore and UML editors (for `*.ecore` and `*.uml` models). These actions automatically select the appropriate metamodel in the console.

For both Ecore and UML, parsing constraints at the `M1` (model) level is supported. This implements a scratch pad for developing OCL constraints in the context of:

• classifiers, for invariant constraints

• operations, for pre/post condition constraints and body expressions

• attributes, for initial-value and derivation constraints

The console infers the kind of constraint from the selected element; in the case of an operation, it assumes a post-condition constraint as these constraints support a superset of the syntax for pre-conditions and body expressions.

The figure above shows the parsing of a derivation constraint on an Ecore property (an `EStructuralFeature`).

The figure above shows the parsing of an invariant constraint on a UML classifier (a `Class`). Note that UML can model the `Job` as an association class; a roughly equivalent Ecore model is more verbose.

5.5.5. Example Code

Refer to the code in this example if you need to:

- parse, validate and evaluate OCL queries and constraints on EMF model elements
- implement content-assist for OCL constraints in your model editor

Copyright © 2000, 2007 IBM Corporation and others. All Rights Reserved.

Chapter 6. Classic Ecore/UML Programmers Guide

The Ecore/UML Programmers Guide describes the ways in which the Ecore or UML bindings of Eclipse OCL can be used from Java programs.

The Ecore binding has been available since Eclipse OCL 1.0.0 (Callisto). The UML binding was added in 1.1.0 (Europa). Both will remain for as long as necessary. Examples quality prototypes of the new UML-aligned Pivot binding were first available in 3.1.0 (Indigo). The Pivot binding will become the preferred binding in 6.0.0 (Mars). The Pivot binding is described in a separate Pivot Programmers Guide.

The OCL Parser/Interpreter provides an implementation of the Object Constraint Language 2.4 specification for EMF-based metamodels and models. It offers OCL constraint and query parsing and evaluation, model-based validation, and provides an infrastructure for content assist in textual editors.

The following features are supported in the current version:

- Classifier invariant constraints
- Operation precondition and postcondition constraints and body conditions
- Property constraints (initial-value and derivation)
- Attribute and operation definitions (def: expressions)
- Package context declaration
- Basic values and types
- Collection types
- Navigation of attributes and association ends
- Operation invocation
- Iteration expressions (all standard iterators)
- Let expressions
- If expressions
- Tuples
- Message expressions, including unspecified values
- Operations predefined by OCL: allInstances(), oclIsKindOf(), oclIsTypeOf(), oclAsType(), oclIsNew()
- Escape syntax for illegal names: type, operation, attribute, etc. names that correspond to OCL reserved words can be escaped in the standard fashion using a leading underscore ('_'). In addition, names that contain spaces or tabs can be escaped by enclosing them in double-quotes ('"'; this is non-standard). e.g., `self.ownedRule->forAll(c : Constraint | c._context = self)`

The above constructs are supported by the parser for parsing and for evaluation, with the exception of the oclIsNew() operation and message expressions. All of the above are supported for both Ecore and UML models. The following are supported by default for UML (both in parsing and evaluation):

- Navigation of non-navigable association ends (including those that are owned by the association)
- Qualified association end navigation
- Navigation to association classes, including source qualifiers
- Operations predefined by OCL: oclIsInState()

The following features are provided in addition to the OCL specification:

- String case conversion operations: toUpper(), toLower()
- Support for comparison (<, <=, etc.) and sorting of any java `Comparable` s of conformant types
- Transitive closure of associations: closure(expr : OCLExpression) iterator
- Navigation of "hidden" opposites of references specified in Ecore models using a `Property.oppositeRoleName` annotation with source `http://schema.omg.org/spec/`

`MOF/2.0/emof.xml` on the forward reference, producing an `OppositePropertyCallExp` expression

The OCL implementation is defined in plug-ins for convenient deployment in Eclipse, but as is the case for EMF, it can also be used stand-alone. The plug-ins are partitioned thus:

- `org.eclipse.ocl`: the core parsing, evaluation, and content assist services. Definition of the OCL Abstract Syntax Model and Environment API. These APIs are generic, independent of any particular metamodel (though using Ecore/EMF as the meta-meta-model).

- `org.eclipse.ocl.ecore`: implementation of the Ecore metamodel environment, binding the generic Environment and AST APIs to the Ecore language. Provides support for working with OCL constraints and queries targeting Ecore models.

- `org.eclipse.ocl.uml`: implementation of the UML metamodel environment, binding the generic Environment and AST APIs to the UML language. Provides support for working with OCL targeting UML models.

Please refer to the [OCL Interpreter Tutorial](#) for review of the code samples.

6.1. Parsing Constraints and Queries

The OCL parser provides two APIs for parsing constraint and query expressions. The [`OCLHelper`](#) interface is designed primarily for parsing constraints and query expressions embedded in models, such as Ecore or UML models. The [`OCL`](#) class serves as the main entrypoint into the parsing API but also implements the parsing of [OCL documents](#), for example from text files. In both cases, the concept of `Environment` is crucial.

6.1.1. The OCL Environment

The following diagram shows the core of the `Environment` API, that clients of the OCL parser interact with:

The OCL class is a generic type; its type parameters represent the various metaclasses of the metamodels that OCL works with in the UML/MOF family of OMG specifications. For example, <C> represents the Classifier concept, <O> the Operation concept, etc. See the discussion of metamodels supported by OCL for details of the mappings. The same type parameter names are used consistently throughout the OCL APIs to represent the same metaclasses.

The OCL class defines instances of autonomous OCL parsing and evaluation environments. It has a single root Environment created by an EnvironmentFactory implementation for a particular EMF-based metamodel. The OCL environment consists, conceptually, of the model that is to be constrained together with all of the constraints and additional operations and attributes defined (via OCL) for the purpose of formulating constraints.

Environment s nest. Usually the root environment has no correlation to an element in the model, or it may correspond to some Package providing a default namespace (called a package context).

Alternatively, it may contain one or more nested environments defining package namespaces. A package context contains one or more classifier contexts, which in turn can contain operation and/or attribute contexts. Whereas the purpose of a package context is primarily to assist in the look-up of named model elements, the classifier, operation, and attribute contexts have deeper meaning.

A classifier context defines the type of the `self` variable in OCL constraints and queries. By itself, it is the context for invariant constraints for the context classifier. Additionally, as the parent context for operation and attribute constraints, it indicates the classifier in which context an operation or attribute constraint applies; this may be the classifier that defines these features, or it may inherit them from some more general classifier.

An `Environment` may contain named `Variable`s to which OCL expressions can refer. The most common of these is `self`. Others include the parameters defined by an operation (and its `result`), in the case of an operation context. The OCL API even allows clients to add variables, in code, to define "global" names.

6.1.2. Creating an OCL Environment

The static factory methods on the `OCL` class are used to create instances. It is a good practice to re-use the same OCL instance for all parsing and evaluation of constraints and queries on a model while that model is loaded (usually in some `ResourceSet` in an editor). Using the shared environment factory for the Ecore metamodel, we can create an OCL environment suitable for parsing OCL constraints on any Ecore model and evaluating them on instances of the model:

```
// create an OCL instance for Ecore
OCL ocl = OCL.newInstance(EcoreEnvironmentFactory.INSTANCE);
```

[Text for cut and paste]

Several of the type parameters in the `OCL` generic type signature are useful mostly within the OCL API. We leave them, here, as wildcards.

6.1.3. The OCL Helper

From an OCL instance, we can create a helper object with which to parse constraints and additional operation/attribute definitions. This `OCLHelper` stores all of the instantiations of OCL template metaclasses (such as `CollectionType(T)` and `TupleType` and additional operation/attribute definitions in the root environment of the `OCL` that created it. This ensures that all of these constructs are available for reuse in subsequent parsing.

The `OCLHelper` is primarily designed for parsing constraints and query expressions embedded in models, providing the following API for that purpose:

- `createQuery()`: parses a query expression

- `createConstraint()`: parses a constraint of a given `ConstraintKind`

- `createInvariant()`: convenience for invariant constraints

- `createPrecondition()`: convenience for pre-condition constraints

- `createPostcondition()`: convenience for post-condition constraints

- `createBodyCondition()`: convenience for body conditions

- `createInitialValueExpression()`: convenience for attribute initial values

- `createDerivedValueExpression()`: convenience for attribute derived values

- `defineOperation()`: convenience for additional operation definitions

- `defineAttribute()`: convenience for additional attribute definitions

Different kinds of constraints require different context environments. The `setContext()`, `setOperationContext()`, and `setAttributeContext()` methods create the appropriate nested `Environment@s` in the host `@OCL` instance's root environment.

The result of parsing a query expression is an OCLExpression , an instance of the Abstract Syntax Model . The result of parsing a constraint is an instance of the `Constraint` metaclass defined by the OCL's target metamodel .

```
// create an OCL helper object
OCLHelper<EClassifier, EOperation, EStructuralFeature, Constraint> helper =
        ocl.createOCLHelper();

// set the OCL context classifier
helper.setContext(EXTLibraryPackage.Literals.LIBRARY);

Constraint invariant = helper.createInvariant(
    "books->forAll(b1, b2 | b1 <> b2 implies b1.title <> b2.title)");

OCLExpression<EClassifier> query = helper.createQuery(
    "books->collect(b : Book | b.category)->asSet()");
```
[Text for cut and paste]

Ecore does not define a `Constraint` metaclass, so the OCL binding for Ecore supplies one.

6.1.4. Operation and Attribute Contexts

In the case of constraints on operations or attributes, the context consists of two elements: the constrained operation/attribute and a classifier in the context of which the constraint is to apply. This accounts for the possibility that a classifier defines constraints on inherited features. As an example, consider the `EModelElement::getEAnnotation(EString)` operation and `EReference::eReferenceType` property in the Ecore metamodel. These can be constrained as follows:

```
EOperation oper = null;
for (EOperation next : EcorePackage.Literals.EMODEL_ELEMENT.getEOperations()) {
    if ("getEAnnotation".equals(next.getName())) {
        oper = next;
        break;
    }
}

// define a post-condition specifying the value of EModelElement::getEAnnotation(EString)
// This operation environment includes variables representing the operation
// parameters (in this case, only "source : String") and the operation result
helper.setOperationContext(EcorePackage.Literals.ECLASS, oper);
Constraint body = helper.createPostcondition(
    "result = self.eAnnotations->any(ann | ann.source = source)");

// define a derivation constraint for the EReference::eReferenceType property
helper.setAttributeContext(
    EcorePackage.Literals.EREFERENCE,
    EcorePackage.Literals.EREFERENCE__EREFERENCE_TYPE);
Constraint derive = helper.createDerivedValueExpression(
    "self.eType->any(true).oclAsType(EClass)");
```
[Text for cut and paste]

6.2. Evaluating Constraints and Queries

In Parsing Constraints, we saw how to use the `OCLHelper` API for parsing OCL constraints and query expressions. Parsing constraints is very interesting in itself, but we can also make OCL come alive in our applications by evaluating these constraints. For this, OCL provides a `Query` API.

6.2.1. The OCL Query

Like the `OCLHelper` for parsing constraints, the OCL facade object provides `Query` objects for evaluating constraints and query expressions.

The `Query` encapsulates an _EvaluationEnvironment_ providing the run-time values of context variables to the OCL interpreter. These context variables are set and retrieved using the following methods:

- `add(String, Object)`: adds a name-value binding for a variable

- `replace(String, Object)`: replaces an existing variable binding

- `remove()`: removes a variable binding

- `getValueOf(String)`: obtains a variable value

The context variables of primary interest are `self` and, in operation constraints, the variables corresponding to its parameters. The `EvaluationEnvironment` API is also used to supply values for "global" variables added to the parsing `Environment` by the client.

Another important consideration in the evaluation environment is the `allInstances()` operation, which obtains the entire extent of a classifier. For data types, this is a simple problem: the extent of an `Enumeration` is well defined and the extents of other kinds of `DataType` s are undefined. For `Class` extents, the `EvaluationEnvironment` provides support for an extent map, mapping classes to the sets of their instances, as determined by the client. A client sets the extent map using the _OCL.setExtentMap()_ method. The default extent map, if none is provided by the client, lazily computes the extent of a class from the EMF `Resource` containing the context element of the evaluation. An alternative extent map can be found in _org.eclipse.ocl.ecore.opposites.ExtentMap_ .

So, after optionally setting values of context variables (other than `self`; the `Query` takes care of this) and an extent map, simply construct a query and use it to evaluate the expression or check the constraint:

```
OCL ocl = OCL.newInstance(EcoreEnvironmentFactory.INSTANCE);
OCLHelper<EClassifier, ?, ?, Constraint> helper = ocl.createOCLHelper();

helper.setContext(EXTLibraryPackage.Literals.LIBRARY);
Constraint invariant = helper.createInvariant(
    "books->forAll(b1, b2 | b1 <> b2 implies b1.title <> b2.title)");
OCLExpression<EClassifier> query = helper.createQuery(
    "books->collect(b : Book | b.category)->asSet()");

// create a Query to evaluate our query expression
Query queryEval = ocl.createQuery(query);

// create another to check our constraint
Query constraintEval = ocl.createQuery(invariant);

List<Library> libraries = getLibraries();  // hypothetical source of libraries

// only print the set of book categories for valid libraries
for (Library next : libraries) {
    if (constraintEval.check(next)) {
        // the OCL result type of our query expression is Set(BookCategory)
        @SuppressWarnings("unchecked")
        Set<BookCategory> categories = (Set<BookCategory>) queryEval.evaluate(next);

        System.out.printf("%s: %s%n", next.getName(), categories);
    }
}
```
[Text for cut and paste]

One of the advantages of the `Query` API is that a query's evaluation environment can be reused for multiple evaluations, as above. The extent of any classifier is only computed once. For convenience, however, in situations where only a single evaluation is required, the `OCL` class provides shortcuts:

```
// check a single library
Library lib = getLibrary();  // hypothetical source of a library

// check whether it satisfies the constraint
System.out.printf("%s valid: %b", lib.getName(), ocl.check(lib, invariant));
```
[Text for cut and paste]

The `Query` API also provides methods that work on multiple elements. The first example, above, could be written more succinctly as:

```
// only print the set of book categories for valid libraries
for (Library next : constraintEval.select(libraries)) {
    @SuppressWarnings("unchecked")
    Set<BookCategory> categories = (Set<BookCategory>) queryEval.evaluate(next);

    System.out.printf("%s: %s%n", next.getName(), categories);
}
```
[Text for cut and paste]

6.3. Parsing OCL Documents

As we saw in the Parsing Constraints and Queries topic, the OCL parser provides an `OCLHelper` API for parsing constraints embedded in models. OCL also permits constraints to be specified in a text document, as an adjunct to the model. In this case, the concrete syntax for context declarations indicates the context of constraints, equivalent to their placement in models.

As an example, consider the following Complete OCL document: "

```
import 'platform:/resource/org.eclipse.emf.examples.library/model/extlibrary.ecore'

package extlibrary

context Library
-- get all books with a title in a library and its branches (recursively)
def: getBooks(title : String) : Set(Book) =
    books->select(b | b.title = title)->asSet()->union(
        branches.getBooks(title)->asSet())

context Book
-- the library containing a book
def: library : Library = Library.allInstances()->any(books->includes(self))

-- book titles are unique within their library branch (and its sub-branches)
inv unique_title: not library.oclIsUndefined() implies
    library.getBooks(title) = Set{self}

endpackage
```

[Text for cut and paste]

The *import* on the first line is an extension supported by the Complete OCL editor for use with the Pivot meta-model. The *import* is ignored by the parsers for the Ecore or UML bindings, which assume that the relevant metamodels have been registered in either the global EPackage.Registry or the local EPackage.Registry passed to the EnvironmentFactory..

6.3.1. The OCL Input

The OCLInput class encapsulates an OCL document. An input can be created from a string or an input stream.

Given an OCLInput, simply ask an OCL to parse it: "

```
EPackage.Registry registry = new EPackageRegistryImpl();
registry.put(EXTLibraryPackage.eNS_URI, EXTLibraryPackage.eINSTANCE);
EcoreEnvironmentFactory environmentFactory = new EcoreEnvironmentFactory(registry);
OCL ocl = OCL.newInstance(environmentFactory);

// get an OCL text file via some hypothetical API
InputStream in = getInputStream("/model/parsingDocumentsExample.ocl");

Map<String, Constraint> constraintMap = new HashMap<String, Constraint>();

// parse the contents as an OCL document
try {
    OCLInput document = new OCLInput(in);

    List<Constraint> constraints = ocl.parse(document);
    for (Constraint next : constraints) {
        constraintMap.put(next.getName(), next);

        OCLExpression<EClassifier> body = next.getSpecification().getBodyExpression();
        System.out.printf("%s: %s%n", next.getName(), body);
    }
} finally {
    in.close();
}
```

[Text for cut and paste]

6.3.2. Accessing the Constraints

The OCL returns the list of constraints if they were successfully parsed. They are retained by the OCL (available via the getConstraints() method at any time), and in particular, any definitions of additional operations or attributes are available for subsequent constraint parsing. Any number of OCL documents may be parsed by the same OCL instance, combined also with constraints parsed by OCLHelpers. All of these constraints are retained by the OCL environment.

```
Library library = getLibrary();  // get library from a hypothetical source

OCLHelper<EClassifier, ?, ?, Constraint> helper = ocl.createOCLHelper();

// use the constraints defined in the OCL document

// use the getBooks() additional operation to find a book
helper.setContext(EXTLibraryPackage.Literals.LIBRARY);
OCLExpression<EClassifier> query = helper.createQuery(
    "getBooks('Bleak House')->asSequence()->first()");

Book book = (Book) ocl.evaluate(library, query);
System.out.printf("Got book: %s%n", book);

// use the unique_title constraint to validate the book
System.out.printf("Validate book: %b%n",
    ocl.check(book, constraintMap.get("unique_title")));
```

[Text for cut and paste]

The source for these examples may be found in the org.eclipse.ocl.ecore.tests plugin in model/parsingDocumentsExample.ocl and in src/org/eclipse/ocl/ecore/tests/DocumentationExamples.java.

6.4. OCL Relationship to Metamodels

The OCL implementation provides support for models defined using either the Ecore or the UML metamodel (as implemented by the Eclipse EMF and UML2 projects), and an extensibility API that allows additional EMF-based metamodels to be plugged in.

> The direct and indirect coupling of the Ecore and UML2 meta-models to Ecore makes exact compliance with the OMG specification very difficult, particularly in the area of reflection. Eclipse OCL is therefore migrating to a new potentially 100% OMG compliant Pivot metamodel that hides the differencess between OMG's UML and

EMOF and Eclipse's UML and Ecore. The Pivot binding is described in the Pivot Programmers Guide.

The OCL API implements support for different target metamodels via the EnvironmentFactory interface. An implementation of this interface binds the metamodel's metaclasses to the generic type parameters of the OCL class. The metamodel-specific Environment implementation constructed by this factory implements the reflection capability required by OCL to discover the elements of the model being constrained and the relationships between them.

6.4.1. The Ecore Metamodel Binding

An OCL binding for the Ecore metamodel is provided by the org.eclipse.ocl.ecore plug-in. It is best suited to parsing and evaluating OCL constraints on Ecore models. Evaluation of constraints is supported on instances of the EMF-generated Java API (Ecore as the source for the genmodel) and on dynamic EObjects.

As is illustrated by most of the examples in this documentation, the Ecore binding is provided by the EcoreEnvironmentFactory class. By default, the Ecore environment uses the static EPackage registry to look up package names. It can also be supplied with an alternative package registry (for example, one local to a ResourceSet) but it will always use the static registry as a backup. Aside from the package registry, the Ecore environment factory maintains no state. So, when the shared registry is to be used, the static EcoreEnvironmentFactory.INSTANCE is most practical.

The Ecore binding for OCL provides the following capabilities, reflecting the subset of Ecore's modeling constructs with respect to UML:

Capability	Parse	Evaluate
Classifier invariant constraints	Y	Y
Operation precondition and postcondition constraints and body conditions	Y	N
Property constraints (initial-value and derivation)	Y	Y*
Attribute and operation definitions (def: expressions)	Y	Y
Package context declaration	Y	n/a
Basic values and types, mapped from the standard EDataTypes to OCL's primitive types	Y	Y
Collection types	Y	Y
Navigation of attributes and references	Y	Y
Operation invocation	Y	Y
Iteration expressions (all standard iterators)	Y	Y
Let expressions	Y	Y
If expressions	Y	Y
Tuples	Y	Y
Message expressions, including unspecified values	Y	N
Operations predefined by OCL: allInstances()	Y	Y
Operations predefined by OCL: oclIsKindOf(), oclIsTypeOf(), oclAsType()	Y	Y

Operations predefined by OCL: oclIsNew()	Y	N
@pre expressions	Y	N
* derivation only		

Ecore metamodel capability matrix

Because Ecore does not define analogues of some of the UML metaclasses required by the OCL Abstract Syntax Model, the Ecore binding defines these on its behalf, in the `platform:/plugin/ org.eclipse.ocl.ecore/model/OCLEcore.ecore` metamodel. These include:

- `Constraint`: the model of an OCL constraint (when the `language` is OCL)

- `CallOperationAction`: used in the model of message expressions

- `SendSignalAction`: used in the model of message expressions

- `ExpressionInOCL`: it is this metaclass's general class `OpaqueExpression` that Ecore does not define. It is elided in the Ecore binding

- `State`: Ecore provides no behavior modeling capabilities. The Ecore binding simply substitutes `EObject`

For applications that work exclusively with the Ecore binding for OCL, the `org.eclipse.ocl.ecore` package defines a subclass of the `OCL` class that supplies all of the generic type parameter bindings to simplify typing (in the absence of type aliasing in Java). It also provides Ecore-specific convenience factory methods for the `OCL`, itself, and narrows the return type of the factory methods for the `OCLHelper` and `Query` interfaces. These specialized interfaces likewise supply the generic type parameter bindings for Ecore.

6.4.2. The UML Metamodel Binding

An OCL binding for the UML metamodel is provided by the `org.eclipse.ocl.uml` plug-in. It is best suited to parsing and evaluating OCL constraints on UML models. Evaluation of constraints is supported on instances of the UML2-generated Java API (UML as the source for the genmodel), on dynamic EObjects (using an Ecore model created by the UML-to-Ecore converter), and on `InstanceSpecification` elements in the UML model.

The UML binding is provided by the <u>UMLEnvironmentFactory</u> class. By default, the UML environment factory and all of the environment contexts that it creates use a private `ResourceSet` to look up the corresponding UML model(s) against which OCL constraints are parsed.

- It is the client's responsibility to ensure that the UML model is loaded in the resource set used by the UML environment factory instance.

The UML environment factory can alternatively be initialized with a resource set of the client's choosing. Ordinarily, the UML environment uses its resource set's local `EPackage` registry to look up EMF-generated `EPackage` names corresponding to UML models. A custom package registry may be provided by the client if necessary.

The UML binding for OCL provides the following capabilities:

Capability	Parse	Evaluate
Classifier invariant constraints	Y	Y
Operation precondition and postcondition constraints and body conditions	Y	N
Property constraints (initial-value and derivation)	Y	Y*
Attribute and operation definitions (def: expressions)	Y	Y
Package context declaration	Y	n/a
Basic values and types	Y	Y+

Collection types	Y	Y
Operation invocation	Y	Y-
Navigation of attributes and references	Y	Y
Navigation of non-navigable association ends (including those that are owned by the association)	Y	Y
Qualified association end navigation	Y	Y=
Navigation to association classes, including source qualifiers	Y	Y=
Iteration expressions (all standard iterators)	Y	Y
Let expressions	Y	Y
If expressions	Y	Y
Tuples	Y	Y
Message expressions, including unspecified values	Y	N
Operations predefined by OCL: allInstances()	Y	Y
Operations predefined by OCL: oclIsKindOf(), oclIsTypeOf(), oclAsType()	Y	Y
Operations predefined by OCL: oclIsInState()	Y	N
Operations predefined by OCL: oclIsNew()	Y	N
@pre expressions	Y	N

* derivation only

\+ OCL defines the Real primitive type that is missing from UML, but not a LiteralReal

\- with InstanceSpecifications, only where body constraints are defined

\= only with InstanceSpecifications

UML metamodel capability matrix

A special case of the UML environment's support for dynamic EObjects, mentioned above, is stereotype applications. The Eclipse UML2 component uses dynamic EMF in the implementation of stereotype applications, by converting UML `Profile` s to `EPackage` s. Constraints parsed in the context of a UML `Stereotype` can be evaluated on applications (instances) of that stereotype or on model elements to which the stereotype is applied. This applies only to UML models, themselves, as instances of the UML metamodel (stereotyping is only available in the UML metamodel).

For applications that work exclusively with the UML binding for OCL, the `org.eclipse.ocl.uml` package defines a subclass of the `OCL` class that supplies all of the generic type parameter bindings to simplify typing (in the absence of type aliasing in Java). It also provides UML-specific convenience factory methods for the `OCL`, itself, and narrows the return type of the factory methods for the `OCLHelper` and `Query` interfaces. These specialized interfaces likewise supply the generic type parameter bindings for UML. h2. Content Assist Support

The Content Assist facilities described here are used by the Interactive OCL Console. They are not used by the new Xtext-based Editors or the Interactive Xtext OCL Console.

The `OCLHelper` API provides support for content-assist in rich editors, by parsing partial OCL expressions and supplying completion suggestions. The `List<Choice> getSyntaxHelp(ConstraintKind, String)` operation returns a list of suggestions for the next token to follow the end of the expression fragment.

The `Choice` objects returned by the helper include some convenient text strings (name and description) to formulate basic JFace content-assist proposals. Each choice also carries a reference to the element that it represents, the kind of element indicated by the `ChoiceKind` enumeration, for a more sophisticated content assist that might inlude context information, documentation, etc. as in Eclipse JDT. The list of choices depends in part on the kind of constraint expression that is to be completed, as for example, the `oclIsNew()` operation is only permitted in operation post-conditions.

```
helper.setContext(EXTLibraryPackage.Literals.BOOK);

List<Choice> choices = helper.getSyntaxHelp(ConstraintKind.INVARIANT,
    "Book.allInstances()->collect(author)->");

for (Choice next : choices) {
    switch (next.getKind()) {
    case OPERATION:
    case SIGNAL:
        // the description is already complete
        System.out.println(next.getDescription());
    case PROPERTY:
    case ENUMERATION_LITERAL:
    case VARIABLE:
        System.out.println(next.getName() + " : " + next.getDescription());
        break;
    default:
        System.out.println(next.getName());
        break;
    }
}
```

6.4.3. Syntax Completion Choices

The computation of `Choice` s is supported for the following tokens, which may be used by a client as auto-assist triggers:

Token	Completion choices
`.`	Features applicable to the type of the expression to the left of the dot, or its element type if it is a collection. association classes (in the UML environment only)
`->`	Collection operations and iterators
`::`	Packages, types, enumeration literals, and states (in the UML environment only)
`^`	Operations and signals (in the UML environment only)
`^^`	In other situations, the choices the current context variables and implicit references to features of the `self` variable. For example, if the input is something like `""` or `"self.isOrdered and "`

Content-assist triggers

The completion of partially specified identifiers is also supported, by backtracking to look for one of these triggering tokens. This supports interactively narrowing the choices while the content-assist window is active.

```
choices = helper.getSyntaxHelp(ConstraintKind.POSTCONDITION,
    "self.author.oclIs");
```

6.5. OCL Abstract Syntax Model

The OCL Abstract Syntax Model is defined by the OCL Language 2.4 specification . We will not attempt to describe this model, here. However, the Eclipse implementation of OCL defines some extensions to this model that provide additional services. The most important of these is support for the *Visitor* design pattern.

6.5.1. The Visitable and Visitor Interfaces

All of the metaclasses in the Abstract Syntax Model (nodes in the AST) that can be visited implement the [Visitable](#) interface. It define a single operation `accept(Visitor)`. This method delegates to the appropriate `visitXyz(Xyz)` method of the [Visitor](#) . The direct implementors of the `Visitable` interface are the `OCLExpression` and those metaclasses of the `Expressions` package that do not conform to `OCLExpression`:

- `Variable`
- `CollectionLiteralPart`
- `TupleLiteralPart`
- `ExpressionInOCL`

This last is not defined in the `Expressions` package because it pertains to the placement of OCL in `Constraint` elements in models.

The OCL parser, internally, defines a few implementations of visitors, including a `ValidationVisitor` for validating OCL expressions and an [EvaluationVisitor](#) for evaluating OCL expressions.

6.5.2. Implementing a Visitor

The best way to implement a visitor is to extend the [AbstractVisitor](#) class. It provides a `result` variable of the generic type parameter type `T` to store the result computed by the visitor (optional) and a convenient pattern of selective method overrides to process only those nodes of interest for the task at hand.

The `AbstractVisitor` provides implementations of all of the `visitXyz()` interface methods that simply return the current `result` value. Furthermore, for any internal nodes of the syntax tree (such as `OperationCallExp` and `IfExp`), the `visitXyz()` methods recursively visit the child nodes, feeding the results of those descents into a `handleXyz()` method that the subclass can override to compute some result from the child results.

Thus, a subclass needs only to selectively override the default implementations of `visitXyz()` methods for leaf tree nodes and `handleXyz()` methods for non-leaves. For example, to find all variables that are declared but never used:

```
OCLExpression<Classifier> expr = getExpression();  // hypothetical source of an expression

Set<Variable<Classifier, Parameter>> variables = expr.accept(
    new AbstractVisitor<Set<Variable<Classifier, Parameter>>,
              Classifier, Operation, Property, EnumerationLiteral,
              Parameter, State, CallOperationAction, SendSignalAction, Constraint>(
        new HashSet<Variable<Classifier, Parameter>>()) {  // initialize the result

        @Override
        protected Set<Variable<Classifier, Parameter>> handleVariable(
                Variable<Classifier, Parameter> variable,
                Set<Variable<Classifier, Parameter>> initResult) {

            result.add(variable);

            return result;
        }

        @Override
        public Set<Variable<Classifier, Parameter>> visitVariableExp(
                VariableExp<Classifier, Parameter> v) {

            result.remove(v.getReferredVariable());

            return result;
        }
    }});

Set<String> varNames = new HashSet<String>();
for (Variable<?, ?> next : variables) {
    varNames.add(next.getName());
}

System.out.println("Unused variables: + " varNames);
```

6.5.3. The OppositePropertyCallExp Extension

In Ecore models, a reference may have defined an opposite reference, usually owned by the class that is the type of the forward reference. An opposite reference has several, often undesirable or even prohibitive, implications on the class owning it:

• A getter and, for settable features with upper multiplicity 1, a setter will be added, requiring the class to know the class owning the forward reference. This would create cyclic component references if the two classes lived in different components and would therefore not be possible.

• The default serialization format and usually the storage format for non-default model stores changes to include the opposite reference.

Yet, particularly for expressing constraints over the instance models it is often instrumental to be able to navigate such forward references also in reverse. The OppositePropertyCallExp class which inherits from NavigationCallExp and is sibling of PropertyCallExp allows for this reverse navigation in OCL. It points to the forward reference, and its semantics are to navigate this reference in reverse.

To allow for convenient creation of such expressions in the OCL concrete syntax, the standard property call syntax, such as self.x can be used, where x is not the name of a forward reference on self's class but rather an annotated name on a reference using self's class or any of its base classes as its type. To enable this feature, use the special environment factory class EcoreEnvironmentFactoryWithHiddenOpposites when initializing the OCL environment, e.g., by passing such an object to the OCL.newInstance(...) method.

The name for the reverse navigation can be specified by an <u>EAnnotation</u> with source http://schema.omg.org/spec/MOF/2.0/emof.xml and with details key Property.oppositeRoleName. The details value contains the name by which the "hidden" opposite can be referred to in OCL expressions.

If OCL delegates are to be used, the standard EPackage annotations with `invocationDelegate`, `settingDelegate` and `validationDelegate` details for the `http://www.eclipse.org/emf/2002/Ecore` source must be augmented as shown by a further `hiddenOpposites` detail for the `http://www.eclipse.org/emf/2002/Ecore/OCL` source.

This additional annotation causes the `EnvironmentFactory` functionality for the EPackage to be provided by an instance of the `EcoreEnvironmentFactoryWithHiddenOpposites` class which uses the `DefaultOppositeEndFinder` class will be used for finding and navigating the hidden opposites. More substantial customisation is possible by specifying an `environmentFactoryClass` detail with the fully qualified name of a derived `EcoreEnvironmentFactory` that provides a constructor taking an `EPackage.Registry` argument. Note, that the class specified must be visible by your Ecore model's bundle.

6.6. Customizing the Environment

An application that integrates OCL may find it advantageous to provide its users with an enhanced OCL environment, to simplify their task of formulating OCL constraints and queries. For example, an application might define additional "primitive" operations on the OCL standard data types that are pertinent to its domain, or "global" variables that inject useful objects into the user's context. It is also possible to customize the way "hidden" opposites are looked up and navigated, specifically to allow reverse navigation across Ecore references that have no opposite defined.

6.6.1. Defining Global Variables

Consider an application that allows end-users to specify conditions, using OCL, to filter the objects that are shown in the user interface. Given a sufficiently rich model (expressed in Ecore or UML) of the objects that the UI presents, many conditions can be expressed entirely in terms of this model. However, some queries might depend on state of the application, itself, not the data: which perspective is active, whether some view is showing, or even the time of day. These are not characteristics of the objects that the user wishes to filter.

Such an application might, then, choose to define application-specific variables that a filter condition can query: `app$perspective`, `app$views`, `app$time`. Or, perhaps a single variable `app$`, that has properties that a condition can access:

```
-- filter out OCL files in the Web Development perspective
self.extension = 'ocl' and app$.perspective = 'Web Development'
```

To do this, we define a small Ecore model of our application context, e.g.:

Then, in the code that parses a user's filter condition:

```
OCL<?, EClassifier, ?, ?, ?, ?, ?, ?, ?, Constraint, EClass, EObject> ocl;
ocl = OCL.newInstance(EcoreEnvironmentFactory.INSTANCE);

OCLHelper<EClassifier, ?, ?, Constraint> helper = ocl.createOCLHelper();
helper.setContext(MyPackage.Literals.FILE);

// create a variable declaring our global application context object
Variable<EClassifier, EParameter> appContextVar =
        ExpressionsFactory.eINSTANCE.createVariable();
appContextVar.setName("app$");
appContextVar.setType(AppPackage.Literals.APP_CONTEXT);

// add it to the global OCL environment
ocl.getEnvironment().addElement(appContextVar.getName(), appContextVar, true);

List<Constraint> conditions = new ArrayList<Constraint>();

// parse the user's filter conditions
for (String cond : getFilterConditions()) {
    conditions.add(helper.createInvariant(cond));
}

// apply the filters
applyFilters(conditions);
```

The body of our hypothetical `applyFilters()` method must bind this context variable to a value. In this case, the value can be computed when we apply the filters:

```
AppContext appContext = AppFactory.eINSTANCE.createAppContext();

// hypothetical workbench utilities
appContext.setPerspective(WorkbenchUtil.getCurrentPerspective());
appContext.getViews().addAll(WorkbenchUtil.getOpenViewIDs());
appContext.setTime(new Date());

List<Query<EClassifier, EClass, EObject>> queries =
    new ArrayListlt;Query<EClassifier, EClass, EObject>>(constraints.size());

for (Constraint next : constraints) {
    Query<EClassifier, EClass, EObject> query = ocl.createQuery(next);

    // bind the variable value
    query.getEvaluationEnvironment().add("app$", appContext());

    queries.add(query);
}

filter(queries);  // applies these filters to the current objects
                  // by evaluating the OCLS on them.
```

6.6.2. Defining Helper Operations in Java

OCL allows the definition of additional operations and attributes using `def:` expressions. This is very convenient for the formulation of constraints, but what if the operation that we need is something like a regex pattern match?

```
class Person
inv valid_ssn: self.ssn.regexMatch('\d{3}-\d{3}-\d{3}') <> null
```

We might try to define this using OCL, as an additional operation on the OCL Standard Library's `String` primitive type:

```
class String
def: regexMatch(pattern : String) : String =
    -- ???
```

The operations available in the OCL Standard Library simply are not sufficient to express the value of this operation, which should return the substring matching a regex pattern or `null` if the pattern does not match. We need to implement this operation in Java. We can do that by creating a custom `Environment` that knows how to look up this operation, and an `EvaluationEnvironment` that knows how it is implemented.

First, let's start by defining a specialization of the `EcoreEnvironment`. The constructor that is used to initialize the root environment of an `OCL` instance will add our `regexMatch` additional operation to the `String` primitive type. The constructor that is used to create nested environments copies the operation from its parent.

```java
class MyEnvironment extends EcoreEnvironment {
    EOperation regexMatch;

    // this constructor is used to initialize the root environment
    MyEnvironment(EPackage.Registry registry) {
        super(registry);

        defineCustomOperations();
    }

    // this constructor is used to initialize child environments
    MyEnvironment(MyEnvironment parent) {
        super(parent);

        // get the parent's custom operations
        regexMatch = parent.regexMatch;
    }

 // override this to provide visibility of the inherited protected method
    @Override
    protected void setFactory(
      EnvironmentFactory<EPackage, EClassifier, EOperation,
      EStructuralFeature, EEnumLiteral, EParameter, EObject,
      CallOperationAction, SendSignalAction, Constraint, EClass, EObject>
      factory) {
        super.setFactory(factory);
    }

    // use the AbstractEnvironment's mechanism for defining
    // "additional operations" to add our custom operation to
    // OCL's String primitive type
    private void defineCustomOperations() {
        // pattern-matching operation
        regexMatch = EcoreFactory.eINSTANCE.createEOperation();
        regexMatch.setName("regexMatch");
        regexMatch.setEType(getOCLStandardLibrary().getString());
        EParameter parm = EcoreFactory.eINSTANCE.createEParameter();
        parm.setName("pattern");
        parm.setEType(getOCLStandardLibrary().getString());
        regexMatch.getEParameters().add(parm);

        // annotate it so that we will recognize it
        // in the evaluation environment
        EAnnotation annotation = EcoreFactory.eINSTANCE.createEAnnotation();
        annotation.setSource("MyEnvironment");
        regexMatch.getEAnnotations().add(annotation);

        // define it as an additional operation on OCL String
        addOperation(getOCLStandardLibrary().getString(), regexMatch);
    }
}
```

Next, we will define the corresponding specialization of the `EcoreEvaluationEnvironment` that will know how to evaluate calls to this custom operation:

```
class MyEvaluationEnvironment extends EcoreEvaluationEnvironment {
    MyEvaluationEnvironment() {
        super();
    }

    MyEvaluationEnvironment(
            EvaluationEnvironment<EClassifier, EOperation, EStructuralFeature,
            EClass, EObject> parent) {
        super(parent);
    }

    public Object callOperation(EOperation operation, int opcode,
            Object source, Object[] args) {
        if (operation.getEAnnotation("MyEnvironment") == null) {
            // not our custom regex operation
            return super.callOperation(operation, opcode, source, args);
        }

        if ("regexMatch".equals(operation.getName())) {
            Pattern pattern = Pattern.compile((String) args[0]);
            Matcher matcher = pattern.matcher((String) source);

            return matcher.matches()? matcher.group() : null;
        }

        throw new UnsupportedOperationException();  // unknown operation
    }
}
```

Finally, we define a specialization of the EcoreEnvironmentFactory that creates our custom environments:

```
class MyEnvironmentFactory extends EcoreEnvironmentFactory {
    public Environment<EPackage, EClassifier, EOperation, EStructuralFeature,
      EEnumLiteral, EParameter, EObject, CallOperationAction,
      SendSignalAction, Constraint, EClass, EObject> createEnvironment() {
        MyEnvironment result = new MyEnvironment(getEPackageRegistry());
        result.setFactory(this);
        return result;
    }

    public Environment<EPackage, EClassifier, EOperation, EStructuralFeature,
      EEnumLiteral, EParameter, EObject, CallOperationAction,
      SendSignalAction, Constraint, EClass, EObject>
      createEnvironment(Environment<EPackage, EClassifier, EOperation,
      EStructuralFeature, EEnumLiteral, EParameter, EObject,
      CallOperationAction, SendSignalAction, Constraint, EClass,
      EObject> parent) {
        if (!(parent instanceof MyEnvironment)) {
            throw new IllegalArgumentException(
                "Parent environment must be my environment: " + parent);
        }

        MyEnvironment result = new MyEnvironment((MyEnvironment) parent);
        result.setFactory(this);
        return result;
    }

    public EvaluationEnvironment<EClassifier, EOperation, EStructuralFeature,
      EClass, EObject> createEvaluationEnvironment() {
        return new MyEvaluationEnvironment();
    }

    public EvaluationEnvironment<EClassifier, EOperation, EStructuralFeature,
      EClass, EObject> createEvaluationEnvironment(
      EvaluationEnvironment<EClassifier, EOperation, EStructuralFeature,
      EClass, EObject> parent) {
        return new MyEvaluationEnvironment(parent);
    }
}
```

Now, we can use our environment to parse the kind of expression that we were looking for:

```
OCL<?, EClassifier, ?, ?, ?, ?, ?, ?, ?, Constraint, EClass, EObject> ocl;
ocl = OCL.newInstance(new MyEnvironmentFactory());

OCLHelper<EClassifier, ?, ?, Constraint> helper = ocl.createOCLHelper();
helper.setContext(MyPackage.Literals.PERSON);

// double the '\' to escape it in a Java string literal
Constraint validSSN = helper.createInvariant(
        "self.ssn.regexMatch('\\d{3}-\\d{3}-\\d{3}') <> null");

Person person = getPersonToValidate();

System.out.printf("%s valid SSN: %b%n", person, ocl.check(person, validSSN));
```

6.6.3. Selecting a Package Lookup Strategy

When package names are provided in OCL expressions, e.g., when representing types in an `oclIsKindOf` call, these names are looked up using a specific strategy. By default, the lookup proceeds starting at the parsing context, traversing up the package hierarchy. If the package name cannot be resolved this way, for the Ecore binding a lookup is performed in the `EPackage.Registry`. By default, the package name provided is compared to the names of the packages that are contained as values in the registry.

In rare cases there may be ambiguous package names. For example, if an OCL expression is to be parsed using a classifier from the OCL AST metamodel as its context, the context package is `ocl::ecore`. If such an expression is trying to reference a type from the EMF Ecore package with package name `ecore`, the EMF Ecore package is hidden by the lookup happening relative to the context package. Instead of the EMF Ecore package, the `ocl::ecore` package will be found.

Such an ambiguity can be resolved by using a dedicated `EPackage.Registry` which registers the otherwise ambiguous packages with a special "URI" that represents a simple alias name for the package. In order to force the OCL parser to look up packages by those alias names, an option needs to be set on the OCL environment, as follows:

```
Registry r = new EPackageRegistryImpl();
r.putAll(EPackage.Registry.INSTANCE);
r.put("EMFEcore", EcorePackage.eINSTANCE);
r.put("OCLEcore", org.eclipse.ocl.ecore.EcorePackage.eINSTANCE);
OCL ocl = OCL.newInstance(new EcoreEnvironmentFactory(r));
((EcoreEnvironment) ocl.getEnvironment()).setOption(
    ParsingOptions.PACKAGE_LOOKUP_STRATEGY,
    ParsingOptions.PACKAGE_LOOKUP_STRATEGIES.
        LOOKUP_PACKAGE_BY_ALIAS_THEN_NAME);
Helper helper = ocl.createOCLHelper();
helper.setContext(
    org.eclipse.ocl.ecore.EcorePackage.eINSTANCE.getOCLExpression());
org.eclipse.ocl.ecore.OCLExpression expr = helper.createQuery(
    "self.oclIsKindOf(EMFEcore::EClassifier) and not
     self.oclIsKindOf(OCLEcore::OCLExpression)");
```

In the example above, two packages with ambiguous simple names (EMF Ecore package and OCL Ecore package, both with simple name `ecore`) are added with alias names `EMFEcore` and `OCLEcore`, respectively. The package lookup strategy is then set to `LOOKUP_PACKAGE_BY_ALIAS_THEN_NAME` which allows OCL expressions to reference the packages by their aliases, as in `self.oclIsKindOf(EMFEcore::EClassifier) and not self.oclIsKindOf(OCLEcore::OCLExpression)`.

Note, that the use of a delegating registry (constructor `EPackageRegistryImpl(EPackage.Registry)`) does not work because a registry initialized this way does not forward the call to `values()` which would be required by the OCL package lookup implementation. Instead, if the packages registered with the default registry are required, they need to be copied to a new registry using `putAll` as shown above.

6.6.4. Customizing Hidden Opposite Lookup and Navigation

The default <u>EcoreEnvironmentFactory</u> produces environments which can find references that have an annotation with source `http://schema.omg.org/spec/MOF/2.0/emof.xml` that have a detail with key `Property.oppositeRoleName`. In the class that is the type of the reference, and all its subclasses, for OCL this annotation defines an otherwise "hidden" opposite property which can be used in OCL expressions. This can be convenient when it is not possible or desirable to define an explicit opposite reference, e.g., because the class that would have to own the opposite reference can't easily be modified or the serialization of that class must not be changed.

The logic used to find these "hidden" opposites and to navigate them is provided by implementations of the <u>OppositeEndFinder</u> interface. By default, the `EcoreEnvironmentFactory` uses the <u>DefaultOppositeEndFinder</u> implementation. It performs the lookup of annotated references by maintaining a cache based on the Ecore package registry. Successful navigation of those "hidden" opposites requires an <u>ECrossReferenceAdapter</u> to be registered for the containment hierarchy or the resource or resource set that should be used as the scope of the navigation.

Obviously, <u>ECrossReferenceAdapter</u> has a significant downside: it responds to "hidden" opposite navigation requests only based on what has so far been loaded by EMF. If the set of resources held by an underlying EMF storage system contains more resources than have so far been loaded into the resource set, non-loaded content from that storage system won't be considered by the `ECrossReferenceAdapter`. Given a store with reasonable search capabilities it is desirable to take advantage of these capabilities also to perform reverse navigation of those "hidden" opposites. To achieve this, a specific implementation of the <u>OppositeEndFinder</u> interface can be provided. It may be

a specialization of DefaultOppositeEndFinder , e.g., when the reference lookup based on the Ecore package registry is sufficient and only the navigation behavior shall be redefined:

```
class MyOppositeEndFinder extends DefaultOppositeEndFinder {
    MyOppositeEndFinder(EPackage.Registry registry) {
        super(registry);
    }

    @Override
    public Object navigateOppositeProperty(EStructuralFeature property, Object target) {
        Collection<Object> result = null;
        EObject eTarget = (EObject) target;
        // do something clever, e.g., using your underlying store's query facility or
        // the new EMF Query2 component (incubation)
        // ...
        return result;
    }
}
```

With this, OCL can be instantiated using the custom opposite end finder as follows:

```
  OCL ocl = OCL.newInstance(new EcoreEnvironmentFactoryWithHiddenOpposites(
                    EPackage.Registry.INSTANCE, new MyOppositeEndFinder()));
  ...
```

With this, when the use of a property in an OCL expression cannot be resolved to an attribute or reference, the opposite end finder is asked to look for a correspondingly-named "hidden" opposite. Navigation across this "hidden" opposite will then call the `navigateOppositeProperty` method on `MyOppositeEndFinder`.

6.7. OCL Persistence

The Eclipse OCL component implements the OCL Abstract Syntax model as an EMF-based metamodel. Thus, parsed OCL expressions and constraints can be serialized, for example in XMI documents. The OCL 2.4 specification is unclear about how the serialization of expressions should look (this will be solved in the next OCL 2.5 specification), especially where references to demand-created types are concerned. This topic discusses the approach taken by the Eclipse OCL component to provide a practical solution to this problem.

6.7.1. The Type Resolver

OCL defines a number of template metaclasses, including the `CollectionType` metaclass and its specializations, `MessageType`, and `TupleType`. In all of these cases, OCL specifies that these templates are instantiated as needed in the OCL environment, and that only one instance of a template exists for any given combination of template arguments. For example, only one `OrderedSet(String)` exists and it is created on the occasion when it is first needed. Likewise, the `OclMessage` type for invocations of the `EModelElement::getEAnnotation(EString)` operation and the `Tuple{a : String, b : EClass}` type.

The problem is, that the OCL Specification does not indicate how expressions that reference such demand-created types can be persisted, because it does not define what should own these types. A similar problem exists for additional operations and attributes defined in OCL via `def:` expressions. The TypeResolver API is responsible for the demand-creation of these types and for their persistence.

Every _Environment_ has a `TypeResolver` that persists demand-created types and additional features. For a client that doesn't require persistence, the `TypeResolver` will create a `Resource` with the dummy `ocl://` scheme (no resource factory is provided for this scheme).

A client that does require persistence of OCL expressions and these demand-created elements should provide a specific resource in which to store them, either via the _OCL_ class's `newInstance(EnvironmentFactory,  Resource)` factory method or via the _EnvironmentFactory_ interface's `load(Resource)` method.

```
Resource modelResource = getResourceSet().getResource(
        URI.createPlatformResourceURI("/models/My.ecore", true), true);

// persist demand-created types etc. in my model resource
OCL<?, EClassifier, ?, ?, ?, ?, ?, ?, ?, Constraint, EClass, EObject> ocl;
ocl = OCL.newInstance(EcoreEnvironmentFactory.INSTANCE, myResource);

// use the OCL to parse constraints, store them in the Ecore model,
//   and save everything together in one resource for a consistent,
//   self-contained OCL environment

...
```

The _AbstractTypeResolver_ class creates packages in which to store the different elements that it creates: collection types, message types, tuple types, and additional operations and attributes. These last are owned by classes that "shadow" the classifiers in which context they are defined, in the manner by which the OCL specification's adaptation for EMOF indicates that operations are to be "owned" by EMOF `DataType` s.

An environment implementation can customize the way these demand-created elements are stored, by choosing different packages or using some other strategy altogether. Or, using the default `TypeResolver` implementation, a client of the OCL parser can find the demand-created objects in the resolver's resource and relocate them as needed.

6.8. Creating Metamodel Bindings

The Eclipse OCL component provides a generic specification of the OCL Abstract Syntax Model plus bindings for two popular Eclipse metamodels: Ecore and UML. Users of the OCL API can likewise create bindings for their metamodels, to integrate OCL with their modeling languages.

The `Environment` interface has a generic type signature with several parameters, representing the metamodeling constructs required by OCL, that it borrows from UML, EMOF, and the other metamodels that it targets. The Javadoc for that interface defines the mappings, and the same type parameter names are used consistently throughout the OCL API.

To provide a metamodel binding, a client must provide implementations of the following interfaces:

- `Environment` and `EnvironmentFactory`, supplying suitable substitutions for the generic type parameters. Note that not all of these are actually required; for example, Ecore does not have the concept of `State`, so it just substitutes `EObject`

- `EvaluationEnvironment` for accessing properties of run-time instances of models

- `UMLReflection` for introspecting models (instances of thetarget metamodel)

- `OCLStandardLibrary`, providing the instances of the metamodel's `Classifier` metaclass that implement the OCL Standard Library types

- `OCLFactory`, providing a factory for all of the metaclasses of the Abstract Syntax Model

This last item, above, necessitates furthermore that the metamodel binding provide a concrete specialization of the Abstract Syntax Model (in its entirety) that mixes in the target metamodel's correspondents of the UML `Classifier` and `TypedElement` metaclasses. The former is required to provide compatibility of the metaclasses in the OCL `Types` with the target metamodel's type system. The latter is required for compatibility of the metaclasses in the OCL `Expressions` package with the target metamodel's typed elements.

6.8.1. The OCL Abstract Syntax Model

The following diagram summarizes the metaclasses of the OCL `Types` package:

The following diagram summarizes the call expression metaclasses of the OCL `Expressions` package:

The following diagram summarizes the literal expression metaclasses of the OCL `Expressions` package:

The following diagram summarizes the remaining metaclasses of the OCL `Expressions` package:

6.9. Incrementally Re-Evaluating OCL Expressions Using the Impact Analyzer

When Ecore metamodels use many OCL invariants and the models constrained by these invariants grow large, re-evaluating the invariants becomes a performance challenge. As OCL expressions can navigate freely across resource boundaries, changes to a model element in one resource can easily affect invariants for model elements in other resources. To reliably catch all invalidated constraints after a change it would be necessary to re-evaluate all invariants on all their context objects regardless their resource. This does not scale sufficiently well.

The `ImpactAnalyzerFactory` interface allows tool builders to efficiently determine a much smaller set of model elements on which re-evaluation of expressions is necessary after a change.

Given an OCL expression, the factory can be used to create an impact analyzer for a single expression as follows:

```
final OCLExpression e = ...;
final ImpactAnalyzer impactAnalyzer =
  ImpactAnalyzerFactory.INSTANCE.createImpactAnalyzer(
      e,      // the expression to re-evaluate incrementally
      false,  // whether to re-evaluate when new context objects appear
      OCLFactory.INSTANCE);
```

The impact analyzer obtained this way can create a change notification filter which can then be used to register for notifications that indicate a change which may affect the value of the expression. Consider the following example:

```
ResourceSet myResourceSet = ...;
EventFilter filter = impactAnalyzer.createFilterForExpression();
EventManager eventManager =
 EventManagerFactory.eINSTANCE.getEventManagerFor(myResourceSet);
eventManager.subscribe(filter, new AdapterImpl() {
    public void notifyChanged(Notification notification) {
        Collection<EObject> valueMayHaveChangedOn =
            impactAnalyzer.getContextObjects(notification);
        for (EObject eo : valueMayHaveChangedOn) {
         // ... perform some re-evaluation action of e for context eo here
        }
    }
});
```

The event manager can be used to register the event filters of several OCL expressions with their respective adapters. The adapters for different expressions do not have to be distinct but may optionally be shared. The following figure shows how the classes relate, as a UML class diagram:

For each OCL expression a new impact analyzer is used. The event filters produced by them can be registered with the same event manager. The following figure shows a typical instance collaboration diagram in UML notation.

The event manager factory and the event managers it produces lay the scalable foundation for the re-evaluation process. Even if it has to manage many subscriptions, its performance does not degrade as it would if the change notification filters were evaluated one after the other. With this it becomes possible to register many OCL expressions for change impact analysis as shown above. The figure below shows a typical default configuration of an event manager, as a UML instance collaboration diagram.

The event manager in the figure is configured to listen to the change events coming from anything inside the resource set. In this example it is shown with three different event filters, each coming with its own adapter handling those change notifications matches by the respective filter.

As described in more detail in the Javadoc, event managers may be re-used, temporarily deactivated and new ones may be created specifically upon request. This way it is possible to have several event managers, e.g., listening for changes during different phases of a model's life cycle without having to create and initialize the event managers again and again. Also, an event manager is not restricted to listen to the changes of exactly one resource set. The following figure shows a not so typical configuration, again as a UML instance collaboration diagram.

6.9.1. Using the Impact Analyzer in EMF Editors

The `org.eclipse.ocl.examples.impactanalyzer.ui` package provides experimental support for embedding the impact analyzer in EMF editors. Adding the lines

```
@SuppressWarnings("unused")    // not read; just used to avoid GC
private Revalidator revalidator;  //  from collecting re-validator
```

to the field declarations of an editor class, and adding the lines

```
revalidator = new Revalidator(editingDomain, OCLFactory.INSTANCE,
                         DefaultOppositeEndFinder.getInstance(),
                         MyMetamodelEcorePackage.eINSTANCE);
```

When you use the [OCLinEcore](#) editor, the required EAnnotations to support delegation are provided automatically. This section provides sufficient detail to allow them to be maintained manually using the Sample Ecore Editor or Java code.

These EAnnotations ensure that delegates can be used for both genmodeled and reflective models. The use of genmodel to generate Java classes for your metamodel has significant performance benefits for modeling, but currently makes little difference for OCL execution. The use of genmodel has the disadvantage that you must install the Java classes and so the user of the Java classes must run in a different Eclipse or standalone session to the developer. Conversely, using reflective models allows both developer and user to share the same Eclipse session.

6.10.1. GenModel Settings

There is one GenModel setting that needs to be correctly set to ensure that OCL within generated Java classes can successfully be invoked by itself. Make sure that support for reflective operation invocation is generated by setting the `Operation Reflection` option to `true`.

6.10.2. OCL Delegate URIs

Each application implementing delegation has an associated Delegate URI, which is

- `http://www.eclipse.org/emf/2002/Ecore/OCL` for the classic evaluator
- `http://www.eclipse.org/emf/2002/Ecore/OCL/Pivot` for the Pivot evaluator

Only the `http://www.eclipse.org/emf/2002/Ecore/OCL` was available in the Helios release and so the Helios release of the OCLinEcore editor used that URI.

The OCLinEcore editor uses the Pivot metamodel which is more accurate and OMG compliant and so in the Indigo release, the OCLinEcore editor uses the `http://www.eclipse.org/emf/2002/Ecore/OCL/Pivot` URI and converts all incoming usage of `http://www.eclipse.org/emf/2002/Ecore/OCL` URI to `http://www.eclipse.org/emf/2002/Ecore/OCL/Pivot`.

As described in [The two Eclipse OCLs](#) the Pivot evaluator uses an intermediate Pivot model to hide Ecore and UML2 and so allow full OMG-compliance. The Pivot evaluator is only available when the OCL Examples and Editors feature has been installed as described in [Installation](#).

The OCL Delegate URIs are registered using the

- org.eclipse.emf.ecore.invocation_delegate
- org.eclipse.emf.ecore.setting_delegate
- org.eclipse.emf.ecore.query_delegate
- org.eclipse.emf.ecore.validation_delegate

extension points.

6.10.3. Standalone Initialization

The initialization code for standalone usage of EMF delegates is given in the [Standalone](#) section.

6.10.4. Invocation Delegates

An invocation delegate is invoked to execute the body of an EOperation. An invocation delegate must be registered for the EPackage of the EClassifier of the EOperation.

The EPackage registration is provided by an EAnnotation on the EPackage

- source = `http://www.eclipse.org/emf/2002/Ecore`
  - key = `invocationDelegates`
  - value = *OCL-Delegate-URI*

The invocation delegate is provided by an EAnnotation on the EOperation

- source = *OCL-Delegate-URI*
  - key = `body`
  - value = *OCL-expression*

The `OCL-expression` is evaluated to provide the EOperation value with the containing EClassifier as the `self` context object and the EParameters accessible as parameters from OCL. The return type of the `OCL-expression` must conform to the return type of the EOperation.

6.10.5. Setting Delegates

A setting delegate is invoked to provide the initial or derived value of an EStructuralFeature. A setting delegate must be been registered for the EPackage of the EClassifier of the EStructuralFeature.

The EPackage registration is provided by an EAnnotation on the EPackage

- source = `http://www.eclipse.org/emf/2002/Ecore`
  - key = `settingDelegates`
  - value = `OCL-Delegate-URI`

The setting delegate is provided by an EAnnotation on the EStructuralFeature

- source = `OCL-Delegate-URI`
  - key = `derivation`
  - value = `OCL-expression`

The `OCL-expression` is evaluated to provide the EStructuralFeature value with the containing EClassifier as the `self` context object. The result type of the `OCL-expression` must conform to the type of the EStructuralFeature.

An `initial` rather than `derivation` value may be specified. The `initial` is ignored if a `derivation` is also specified.

6.10.6. Validation Delegates

A validation delegate is invoked to provide additional validation of an EClassifier. A validation delegate must be registered for the EPackage of the EClassifier for which the EClassifier provides any Ecore invariants or Ecore constraints. Both Ecore constraints and invariants constrain an EClassifier, the difference is that an Ecore invariant is realised by an EOperation and so an Ecore invariant may be re-used by modeling environments that may wish to selectively check or re-check constraints.

The EPackage registration is provided by an EAnnotation on the EPackage

- source = `http://www.eclipse.org/emf/2002/Ecore`
  - key = `validationDelegates`
  - value = `OCL-Delegate-URI`

All Ecore constraints must be listed in an EAnnotation on the EClassifier

- source = `http://www.eclipse.org/emf/2002/Ecore`
  - key = `constraints`
  - value = `constraintName1 constraintName2 constraintName3`

The validation delegate for each Ecore constraint is provided by a further EAnnotation on the EClassifier

- source = `OCL-Delegate-URI`
  - key = `constraintName`
  - value = `OCL-expression`

The validation delegate for each Ecore invariant is provided by an EAnnotation on the EOperation

- source = `OCL-Delegate-URI`
  - key = `body`
  - value = `OCL-expression`

The `OCL-expression` is evaluated to validate the EClassifier with the EClassifier as the `self` context object. The result type of the `OCL-expression` must be Boolean.

6.10.7. Validation Messages

When a validation fails EMF generates a default diagnostic of the form `The 'constraintName' is violated on 'constrainedObject'`.

If the [OCLinEcoreEObjectValidator](#) or [CompleteOCLEObjectValidator](#) are used a custom message may be supplied using an additional EAnnotation on the EClassifier.

- source = *OCL-Delegate-URI*
  - key = *constraintName* $message
  - value = *OCL-expression*

The *OCL-expression* is evaluated to produce the custom message with the EClassifier as the `self` context object. The result type of the *OCL-expression* must be String.

The severity of the diagnostic can also be customized by exploiting the four values of the Boolean value of the constraint evaluation.

- `true` indicates successful validation
- `false` indicates unsuccessful validation with warning severity
- `null` indicates unsuccessful validation with error severity
- `invalid` indicates a failure to perform validation (error severity)

6.10.8. Query Delegates

A query delegate is invoked to evaluate a parameterized query on a EObject for which there is no corresponding EOperation. A query delegate is registered to install this query and allow its compiled form to be cached. The delegate may then be invoked as many times as required for compatible context objects and parameters.

This facility enables an EMF application to execute OCL without declaring or instantiating any OCL classes.

The query delegate registration is analogous to direct use of `OCL.newInstance().createHelper().createQuery()`

The query delegate execution is analogous to `OCL.evaluate()`

6.11. Ecore/UML Standalone Configuration

If you use Eclipse OCL within Eclipse you should find that the appropriate registrations are provided for you automatically by the plugin registration mechanisms.

However if you use Eclipse OCL outside Eclipse, for instance in JUnit tests, you must provide the corresponding registrations in your code.

6.11.1. Ecore

For the Ecore metamodel, the required registrations should be provided by invoking `org.eclipse.ocl.ecore.OCL.initialize(ResourceSet)`.

This may be invoked with a null argument to install the registrations in the global EPackage.Registry. This is not normally recommended, but since this is for your application, the integrity of the global registry is your responsibility.

It is normally recommended to install the registrations solely for use in your own ResourceSet and to pass that to the initialize routine.

This initialization ensures that *.ecore is understood.

If you want to use EMF delegates to dispatch OCL, the required registrations may be provided by `org.eclipse.ocl.ecore.delegate.OCLDelegateDomain.initialize(ResourceSet)`.

This may be invoked with a null argument to install the registrations in the global EPackage.Registry rather than a specified local registry.

6.11.2. UML

For the UML metamodel, the required registrations should be provided in a similar way by invoking `org.eclipse.ocl.uml.OCL.initialize(ResourceSet)`.

This initialization ensures that *.uml is understood that http://www.eclipse.org/ocl/1.1.0/ oclstdlib.uml is known and that standard pathmap: locations are resolvable. It also invokes

```
org.eclipse.uml2.uml.resources.util.UMLResourcesUtil.init(ResourceSet)
```
to ensure that all Eclipse and OMG UML namespaces and extensions are registered..

6.11.3. Xtext Editors

The Xtext Editors use the Pivot binding and so their initialiation is described in "Pivot Standalone Configuration"#PivotStandalone.

The Xtext editors may be used with the Ecore or UML bindings in so far as the Complete OCL editor provides a *.ocl document that may be parsed by the LPG parser, and the OCLinEcore editor provides embedded OCL that may be executed by either evaluator.

Chapter 7. Unified or Pivot Programmers Guide

The Unified or Pivot Programmers Guide describes the ways in which the Pivot binding Eclipse OCL can be used from Java programs.

The Pivot binding was first available as an examples quality prototype in 3.1.0 (Indigo). The Pivot binding will become the preferred binding in 6.0.0 (Mars). The older Ecore and UML bindings are described in a separate Ecore/UML Programmers Guide.

The OCL Parser/Interpreter provides an implementation of the Object Constraint Language 2.4 specification for EMF-based metamodels and models. It offers OCL constraint and query parsing and evaluation, model-based validation, and provides an infrastructure for content assist in textual editors.

The following features are supported in the current version:

- Classifier invariant constraints
- Operation precondition and postcondition constraints and body conditions
- Property constraints (initial-value and derivation)
- Attribute and operation definitions (def: expressions)
- Package context declaration
- Basic values and types
- Collection types
- Navigation of attributes and association ends
- Operation invocation
- Iteration expressions (all standard iterators)
- Let expressions
- If expressions
- Tuples
- Message expressions, including unspecified values
- Operations predefined by OCL: allInstances(), oclIsKindOf(), oclIsTypeOf(), oclAsType(), oclIsNew()
- Escape syntax for illegal names: type, operation, attribute, etc. names that correspond to OCL reserved words can be escaped in the standard fashion using a leading underscore ('_'). In addition, names that contain spaces or tabs can be escaped by enclosing them in double-quotes ('"'; this is non-standard). e.g., `self.ownedRule->forAll(c : Constraint | c._context = self)`

The above constructs are supported by the parser for parsing and for evaluation, with the exception of the oclIsNew() operation and message expressions. All of the above are supported for both Ecore and UML models. The following are supported by default for UML (both in parsing and evaluation):

- Navigation of non-navigable association ends (including those that are owned by the association)
- Qualified association end navigation
- Navigation to association classes, including source qualifiers
- Operations predefined by OCL: oclIsInState()

The following features are provided in addition to the OCL specification:

- String case conversion operations: toUpper(), toLower()
- Support for comparison (<, <=, etc.) and sorting of any java `Comparable` s of conformant types
- Transitive closure of associations: closure(expr : OCLExpression) iterator
- Navigation of "hidden" opposites of references specified in Ecore models using a `Property.oppositeRoleName` annotation with source `http://schema.omg.org/spec/MOF/2.0/emof.xml` on the forward reference, producing an `OppositePropertyCallExp` expression

The OCL implementation is defined in plug-ins for convenient deployment in Eclipse, but as is the case for EMF, it can also be used stand-alone. The plug-ins are partitioned thus:

- `org.eclipse.ocl.examples.domain`: the neutral Pivot model interfaces.
- `org.eclipse.ocl.examples.pivot`: the neutral Pivot model and evaluator.
- `org.eclipse.ocl.examples.library`: the extensible OCL Stndard Library.
- `org.eclipse.ocl.examples.codegen`: the OCL to Java code generator.
- `org.eclipse.ocl.examples.debug...`: the extensible debugger.
- `org.eclipse.ocl.examples.validity`: the Validation View.
- `org.eclipse.ocl.examples.xtext...`: Xtext editors.

7.1. Validators

When using the Pivot metamodel, there are two specialized validators available to support integration of OCL in to a larger Ecore environment.

7.1.1. OCLinEcoreEObjectValidator

Unfortunately, in the Indigo release, EMF does not support this customization and so must be activated by explicitly using an EValidator that is aware of the ValidationDelegateExtension extended API. This is available by using the OCLinEcoreEObjectValidator, which you may install globally by:

```
EValidator.Registry.INSTANCE.put(null, new OCLinEcoreEObjectValidator());
```

or more selectively by adjusting the inheritance of the Validator class generated by EMF from (for a model of a Company):

```
import org.eclipse.emf.ecore.util.EObjectValidator;


/**
 * <!-- begin-user-doc -->
 * The <b>Validator</b> for the model.
 * <!-- end-user-doc -->
 * @see company.CompanyPackage
 */
public class CompanyValidator extends EObjectValidator {
```

to

```
import org.eclipse.ocl.examples.xtext.oclinecore.validation.OCLinEcoreEObjectValidator;


/**
 * <!-- begin-user-doc -->
 * The <b>Validator</b> for the model.
 * <!-- end-user-doc -->
 * @see company.CompanyPackage
 * @generated not
 */
public class CompanyValidator extends OCLinEcoreEObjectValidator {
```

Note the **@generated not** that indicates that the class interface is manually defined. Do not use **@generated NOT** since that indicates that the whole class is manually defined.

7.1.2. CompleteOCLEObjectValidator

The CompleteOCLEObjectValidator is used to enable Complete OCL documents to participate in the validation processing of an Xtext editor.

The APIs for merging Complete OCL and Ecore as intermediate Pivots and then migrating the Pivot back to Ecore are experimental.

7.2. The Pivot Evaluator

The Pivot evaluator is a complete reimplementation of the classic evaluator to exploit experience and the Pivot metamodel

- numeric growth beyond 32/64 bits is accommodated
- equal numbers are equal regardless of type
- templated types are supported
- library operations are modeled and extensible
- oclType() returns a Metaclass(OclSelf) offering full reflection without loss of static typing
- optimised virtual function dispatch tables
- code generation to Java

The APIs of the two evaluators are very similar since Ecore compatibility is very important. For basic OCL evaluation, users should not notice any functional difference between the two evaluators. The Pivot evaluator is generally between 2 and 5 times faster as well as being more accurate. The code generated evaluation may be a further 20 times faster.

7.2.1. The Evolving Pivot Value System

The classic evaluator uses Ecore and Java library representations such as EObject, Integer, String and Set directly for evaluation. This avoids conversion costs but incurs OCL accuracy challenges for numeric equality and growth.

The Juno release of the Pivot evaluator use polymorphic `Value` representations such as EObjectValue, IntegerValue, StringValue and SetValue. This avoids the OCL accuracy difficulties but requires wrapper objects and incurs conversion costs wherever a compatible Ecore API is in use.

The IntegerValue and RealValue classes avoid the equivalence and accuracy problems of Integer and Double by implementing Object.equals(Object) with OCL semantics.

The costs of the polymorphic Boolean, String and EObject wrappers became apparent when testing the code generator and so the Kepler and Luna releases use a hybrid representation. Unboxed values (the natural Ecore and Java representation) are used wherever OCL and Java have compatible semantics, that is for Boolean, String, null, invalid/exception and EObjects that are not Types. Boxed polymorphic value representations are used wherever OCL and Java semantics differ, that is for IntegerValue, RealValue, CollectionValue, TupleValue and TypeValue. This avoids unnecessary conversion costs, but requires many instanceof tests to compensate for the lack of Value polymorphism. When generating code, static analysis can often eliminate many of the instanceof cases and so the hybrid representation is faster.

7.2.2. The Pivot Value System

Every value has a unique type identity supervised by the `IdManager` class. This unique identity can be shared by multiple OCL applications that may have distinct type systems as a result of Complete OCL complements.

Every value has a type that is determined from its type identity by a type-system-specific `IdResolver` instance, which also supports conversion between boxed and unboxed value representations.

7.2.2.1. Value Conversions

The values are managed by a `ValueFactory` which provides many utility methods such as `ValueFactory.valueOf(Object)` for creating a `Value` from a naked Java object. The reverse conversion from a value to a naked Java object may be be performed by `Value.asObject()` with methods in derived value classes providing stronger type returns.

7.2.2.2. Polymorphic Integers

The `IntegerValue` interface has a family of IntIntegerValueImpl, LongIntegerValueImpl and BigIntegerValueImpl realizations that use Java types internally but support numeric growth where necessary without imposing the overheads of BigInteger on the vast majority of mundane usages. The wrapping of `int` in `IntegerIntValueImpl` is very comparable to the wrapping of `int` in `java.lang.Integer` so there is little performance or representation cost.

This enables the Pivot evaluator to handle unlimited integers as specified by the OMG OCL specification.

> Prior to the Juno release the handling of greater than 32 bit integers in the classic evaluator was suspect. The Juno release enhances support to allow for 64 bit integers but makes no provision for greater than 64 bit evaluations.

7.2.2.3. Polymorphic Collections

The `CollectionValue` interface has multiple implementations for Bag, OrderedSet, Sequence and Set with implementations that observe OMG OCL semantics.

> The classic implementation uses Java collections directly, which unfortunately means that the Java semantics for equality is used. Consequently the classic evaluator incorrectly evaluates `Set{1,1.0}->size()` as 2.

Using a distinct hierarchy of collection classes opens up opportunities for smart operation, such as in-place update for collections that are rendered redundant by a calculation.

> The classic implementation creates a new collection at every opportunity.

7.2.2.4. Polymorphic Objects

The `ObjectValue` interface has an implementation for EObject and further implementations for more specialized objects such as types.

The Pivot evaluator can be used on alternate data models by providing an alternate `ObjectValue` to wrap an alternative form of data object.

> The classic implementation uses EObject directly, which makes use of non-EObject data models rather hard.

7.2.3. The Pivot Evaluator Type System

The Pivot Evaluator uses a very lightweight type system so that alternate implementations can be used.

For compiled evaluation, a dispatch-table based implementation is used.

For OCL compilation, a UML-aligned representation of the combined UML, OCL, library and user type systems is used.

> The classic implementation uses either UML or Ecore meta-models directly, with Ecore as the meta-meta-model. Consequently there was no support for oclType(). Reflection was available in the non-OMF Ecore domain, so the meta-meta-class is "EClass" rather than "Class".

7.2.4. The Pivot Evaluator Implementation System

The Pivot evaluator may be used in an interpreted form similar to the classic evaluator. In this form the evaluator performs a tree-walk over the Abstract Syntax Tree of the OCL expression. Languages that extend OCL may extend this tree-walk by implementing the relevant visitor evaluations for additional AST nodes.

A partially optimized code generator is available for the Pivot evaluator for which the code generator walks the AST at compile-time. The code generator may be extended to support code generation for languages that extend OCL. See the QVTi code generator in the QVTd project as an example.

7.2.5. Polymorphic Implementations

The OCL Standard Library comprises packages of classes with one class per library feature, each class implementing the polymorphic implementation interface.

Provision of additional library function therefore requires

- provision of the Java class for the library feature

- declaration of the library feature

Library features (properties, operations and iterations) are declared in a Standard Library model that identifies the invocation signature and binds it to a Java implementation.

```
type Collection(T) : CollectionType conformsTo OclAny {

    operation asSet() : Set(T) =>
        'org.eclipse.ocl.examples.library.collection.CollectionAsSetOperation';

    iteration exists(i : T | body : Lambda T() : Boolean) : Boolean
        => 'org.eclipse.ocl.examples.library.iterator.ExistsIteration';
    iteration exists(i : T, j : T | body : Lambda T() : Boolean) : Boolean
        => 'org.eclipse.ocl.examples.library.iterator.ExistsIteration';
```

The extract from `/org.eclipse.ocl.examples.library/model/OCL-2.5.oclstdlib` shows the declaration of the `Collection` type as a templated type with a `T` parameter. The `Collection` type conformsTo (extends/inherits/generalizes) the `OclAny` type and is an instance of the `CollectionType` meta-type.

The `asSet` operation takes no arguments and returns a `Set(T)`, a set of the collection template type. The declaration is bound to `org.eclipse.ocl.examples.library.collection.CollectionAsSetOperation` which is the Java class name of the implementation.

The `exists` iteration has two overloads, taking one or two iterators of the collection template type. The iteration body is a lambda expression operating on a collection template element with no additional arguments to return a Boolean value. The iteration also returns a Boolean value. The same Java implementation class is used for both one and two argument forms.

> The corresponding implementations in the classic evaluator were mostly inlined within the `EvaluationVisitorImpl.visitOperationCallExp` method and so were difficult to extend.

> The corresponding declarations in the classic evaluator were partially modeled in **oclstdlib.ecore** or **oclstdlib.uml**, although in practice an equivalent manually code model initialization is used. The type declarations used by the parser and analyzer are independently coded and do not support iterations as modeled concepts.

7.3. Pivot Standalone Configuration

If you use Eclipse OCL within Eclipse you should find that the appropriate registrations are provided for you automatically by the plugin registration mechanisms.

However if you use Eclipse OCL outside Eclipse, for instance in JUnit tests, you must provide the corresponding registrations in your code.

```
org.eclipse.ocl.examples.pivot.OCL.initialize(resourceSet);
org.eclipse.ocl.examples.pivot.uml.UML2Pivot.initialize(resourceSet)
org.eclipse.ocl.examples.pivot.model.OCLstdlib.install();
org.eclipse.ocl.examples.pivot.delegate.OCLDelegateDomain.initialize(resourceSet)
org.eclipse.ocl.examples.completeocl.CompleteOCLStandaloneSetup.doSetup()
org.eclipse.ocl.examples.oclinecore.OCLinEcoreStandaloneSetup.doSetup()
org.eclipse.ocl.examples.oclstdlib.OCLstdlibStandaloneSetup.doSetup()
org.eclipse.ocl.examples.domain.utilities.StandaloneProjectMap.getAdapter(resourceSet);
```

These are elaborated on below.

7.3.1. Models

For the Pivot metamodel, the required registrations should be provided by invoking `org.eclipse.ocl.examples.pivot.OCL.initialize(ResourceSet)`. This initialization ensures that *.ecore is understood.

If *.uml support is also required, invoke `org.eclipse.ocl.examples.pivot.uml.UML2Pivot.initialize(ResourceSet)` as well. This initialization ensures that *.uml is understood and that standard pathmap: locations are resolvable. It also invokes `org.eclipse.uml2.uml.resources.util.UMLResourcesUtil.init(ResourceSet)` to ensure that all Eclipse and OMG UML namespaces and extensions are registered.

7.3.2. OCL Standard Library

If you want to use the default OCL Standard Library you should invoke `org.eclipse.ocl.examples.pivot.model.OCLstdlib.install()` which installs a compiled shareable form of `/org.eclipse.ocl.examples.library/model/OCL-2.5.oclstdlib`.

If you want to use an alternate library examine the code for the standard installation above, and if you want to compile your library examine the `/org.eclipse.ocl.examples.build/src/org/eclipse/ocl/examples/build/GenerateOCLstdlibModel.mwe2` launcher for the `/org.eclipse.ocl.examples.build/src/org/eclipse/ocl/examples/build/acceleo/generateOCLstdlib.mtl` Acceleo template.

Note that the library is extensible and importable so you may import your own library that in turn imports the standard library.

If you neglect to install an OCL Standard Library, you get the error "No OCL Standard Library content available". If you provide a custom library that fails to meet the miinimal requirements of defining the basic library types (e.g. Boolean, Set, Tuple) and methods (e.g. OclAny::"=") you get an error such as "No 'Boolean' type in the OCL Standard Library".

7.3.3. Pivot Delegates

If you have textual OCL embedded within Ecore models you need to register the EMF delegates so that EMF gets, calls or validates dispatch the embedded OCL to the OCL delegates. The required registrations may be provided by `OCLDelegateDomain.initialize(ResourceSet)` from the `org.eclipse.ocl.examples.pivot.delegate` package.

This may be invoked with a null argument to install the registrations in the global EPackage.Registry rather than a specified local registry.

If you neglect to register delegates, you may get an error of the form "An exception occurred while delegating evaluation of the ..."

7.3.4. Xtext Parsers

If you want to be able to convert any textual form of OCL to its internal pivot form you need to initialize the relevant parser.

*.ocl Complete OCL documents are initialized by `CompleteOCLStandaloneSetup.doSetup()`.

*.oclinecore metamodels are initialized by `OCLinEcoreStandaloneSetup.doSetup()`

*.oclstdlib OCL Standard Library definitions are initialized by `OCLstdlibStandaloneSetup.doSetup()`.

*.ecore, *.essentialocl, *.uml files or general use of the query API is initialized by `EssentialOCLStandaloneSetup.doSetup()`.

Each of the above ensures that everything that it requires is installed. The various set ups can be found in one of the following packages:

```
org.eclipse.ocl.examples.xtext.completeocl.
org.eclipse.ocl.examples.xtext.essentialocl.
org.eclipse.ocl.examples.xtext.oclinecore.
org.eclipse.ocl.examples.xtext.oclstdlib.
```

7.3.5. platform:/plugin and platform:/resource URIs

If you want to be able to use `platform:/plugin/...` or `platform:/resource/...` URIs in a standalone configuration you need to configure the EMF package and URI map registries appropriately. This is a costly activity that involves scanning the classpath and exploiting the content of any plugin.xml and MANIFEST.MF files that are found.

```
org.eclipse.ocl.examples.domain.utilities.StandaloneProjectMap.getAdapter(resourceSet);
```

creates a `StandaloneProjectMap` to cache all the scan results, initializes the ResourceSet and installs itself as an adapter on the ResourceSet so that it can be retrieved again if needed. Users are

strongly recommended to ensure that a single `StandaloneProjectMap` is shared by all clients and so avoid incurring the classpath scan cost more than once.

(The `StandaloneProjectMap` has no OCL-specific functionality; it just cures a major problem in the standalone usage of EMF.)

7.3.6. Classpath

If your standalone environment supports OSGI bundles, as will be the case when you use Eclipse to launch a JUnit test or a transformation, the required plugin dependencies are easily configured in the MANIFEST.MF using JDT quick fixes, or the Manifest editor.

For a totally standalone Java launch, you must identify the exact spelling of each JAR that you require and identify it on your Java classpath. The Eclipse JARs may be found in the plugins folder adjacent to your eclipse.exe. So you may need `org.eclipse.ocl.common_1.0.0.v20120516-1543.jar` amongst many others. The required JARs can be recursively determined by looking at the Class Not Found Exceptions from the Java launch and locating the plugin with a similar name prefix. This is very tedious and has to be repeated each time you upgrade, so don't do it. Use OSGI. However if you must, the following dependency trees may provide some clues.

The dependency tree for the basic parsing and evaluation is:

```
org.eclipse.ocl.common
  org.eclipse.ocl.examples.common
    org.eclipse.ocl.examples.domain
      org.eclipse.ocl.examples.library
        org.eclipse.ocl.examples.pivot
          org.eclipse.ocl.examples.xtext.base
            org.eclipse.ocl.examples.xtext.essentialocl
              org.eclipse.ocl.examples.xtext.completeocl
              org.eclipse.ocl.examples.xtext.oclinecore
              org.eclipse.ocl.examples.xtext.oclstdlib
```

Additionally the UI requires

```
org.eclipse.ocl.common.ui
  org.eclipse.ocl.examples.markup
    org.eclipse.ocl.examples.markup.ui
      org.eclipse.ocl.examples.xtext.essentialocl.ui
        org.eclipse.ocl.examples.xtext.completeocl.ui
        org.eclipse.ocl.examples.xtext.oclinecore.ui
        org.eclipse.ocl.examples.xtext.oclstdlib.ui
        org.eclipse.ocl.examples.xtext.console
```

You may also need the Xtext, EMF, MWE, Orbit plugins and their dependencies

```
com.google.guava
com.google.inject
org.apache.log4j
org.eclipse.emf.common
  org.eclipse.emf.ecore
    org.eclipse.emf.codegen
    org.eclipse.emf.ecore.xmi
org.eclipse.xtext
  org.eclipse.xtext.common.types
    org.eclipse.xtext.common.types.ui
  org.eclipse.xtext.ui
    org.eclipse.xtext.ui.shared
  org.eclipse.xtext.util
```

7.4. Pivot Thread Safety

OCL is declarative and side effect free and so particularly suitable for execution on multiple threads, provided all shared context is maintained in ways that avoid inter-thread conflicts.

The classic Ecore-based OCL evaluation makes no attempt to guarantee thread safety and some of the more recent functionality involving EMF delegate caches is very suspect for multiple thread usage. So if you want thread safety use the Pivot-based evaluation.

The thread safety of interpreted Pivot evaluation is similarly suspect, however the much faster code generated evaluation is designed for thread safety.

7.4.1. Code Generated Evaluation

The code-generated evaluator is intended to be thread-safe; all shared objects update their caches within relatively fine-grained synchronized regions. However there are a number of class static variables that are not synchronized and might therefore experience at best a redundant multiple initialization and at worst an assumed uniqueness violation. Thread safe code must therefore invoke:

```
org.eclipse.ocl.examples.domain.values.util.ValuesUtil.initAllStatics()
```

to ensure eager initialization of unsynchronized class variables. This routine is itself synchronized and so may be safely invoked on all threads, if it is not practical to invoke it solely from just a startup thread.

It is not permissible to modify any part of any OCL object, array or collection.

Application code should not assume that the getter for a protected final field is invoked internally and so should not attempt to modify behavior by overriding it.

7.4.1.1. Design Notes

Loose miscellaneous static fields are initialized by ValuesUtil.initAllStatics().

Most non-static fields are @NonNull and final eliminating thread hazards. However lazy caches cannot be avoided and these require manual review. Caches shared across OCl invocations use Weak references to avoid leakage.

ElementIds are unique and shared across OCL evaluations and so IdManager maintains a hierarchy of synchronized caches for distinct forms of ElementId. Some ElementIds such as TemplateParameterId are subject to two-phase construction (constructor followed by install). It is assumed that a half-constructed ElementId will not be made visible to other threads.

Values are optionally shared and so valuesUtil has a few loose statics for simple values such as FALSE, and a synchronized cache for integers in the range -256 to 1024.

EvaluatorIterationManagers do not currently permit forking of iterations to multiple threads and may malfunction if application code does so.

7.4.2. Interpreted Evaluation

This is not considered thread-safe. Superficial consideration suggests that the EMF delegate dispatching in particular needs careful attention.

7.4.3. OCL Analysis

The Xtext-based functionality is only thread-safe in so far as Xtext imposes strict main/worker thread disciplines. It is very unlikely that activating additional worker threads will give satisfactory results.

7.5. Parsing Constraints and Queries

This section may be contrasted with the corresponding Parsing Constraints and Queries for the Ecore binding to see examples of the small changes needed to migrate from the Ecore binding to the Pivot binding.

The OCL parser provides two APIs for parsing constraint and query expressions. The `OCLHelper` interface is designed primarily for parsing constraints and query expressions embedded in models, such as Ecore or UML models. The `OCL` class serves as the main entrypoint into the parsing API but also implements the parsing of OCL documents, for example from text files. In both cases, the concept of `Environment` is crucial.

7.5.1. The OCL Environment

The `OCL` API provides a Facade for the various objects that support different aspects of OCL parsing and evaluation activities in a that spans activities for which the meta-models remain unchanged. A new OCL Facade is required if the meta-models change.

The OCL class is a simple type.

> There is no need for the Ecore/UML template parameters that parameterize the equivalent Ecore/UML class.

Behind the scenes, the unified Pivot variants of the primary UML, OCL and user and meta-models, complementing Complete OCL documents and Standard Libraries are maintained by a MetaModelManager , which also maintains all the collection and tuple specialization singletons so that they can be shared by subsequent processing. A distinct MetaModelManager is required for each combination of primary meta-models and complementing Complete OCL documents and so for safety a new MetaModelManager is created for each OCL session. Increased metya-model sharing can be achieved by re-using MetaModelManager s when constructing a PivotEnvironmentFactory.

An OCL parsing activity maintains the root and nested parsing context in Environment instances which are created by an EnvironmentFactory .

Environment s nest. Usually the root environment has no correlation to an element in the model, or it may correspond to some Package providing a default namespace (called a package context). Alternatively, it may contain one or more nested environments defining package namespaces. A package context contains one or more classifier contexts, which in turn can contain operation and/or attribute contexts. Whereas the purpose of a package context is primarily to assist in the look-up of named model elements, the classifier, operation, and attribute contexts have deeper meaning.

A classifier context defines the type of the self variable in OCL constraints and queries. By itself, it is the context for invariant constraints for the context classifier. Additionally, as the parent context for operation and attribute constraints, it indicates the classifier in which context an operation or attribute constraint applies; this may be the classifier that defines these features, or it may inherit them from some more general classifier.

An Environment may contain named Variable s to which OCL expressions can refer. The most common of these is self. Others include the parameters defined by an operation (and its result), in the case of an operation context. The OCL API even allows clients to add variables, in code, to define "global" names.

7.5.2. Creating an OCL Environment

The static factory methods on the OCL class are used to create instances. It is a good practice to re-use the same OCL instance for all parsing and evaluation of constraints and queries on a model while that model is loaded (usually in some ResourceSet in an editor). It is also good practice to invoke dispose() to release all OCL-related Resource references.

Using the shared Pivot environment factory , we can create an OCL environment suitable for parsing OCL constraints on any Ecore model and evaluating them on instances of the model:

```
// create an OCL instance for Ecore
OCL ocl = OCL.newInstance(new PivotEnvironmentFactory());
```
[Text for cut and paste]

7.5.3. The OCL Helper

From an OCL instance, we can create a helper object with which to parse constraints and additional operation/attribute definitions.

The `OCLHelper` is primarily designed for parsing constraints and query expressions embedded in models, providing the following API for that purpose:

- `createQuery()`: parses a query expression
- `createConstraint()`: parses a constraint of a given `ConstraintKind`
- `createInvariant()`: convenience for invariant constraints
- `createPrecondition()`: convenience for pre-condition constraints
- `createPostcondition()`: convenience for post-condition constraints
- `createBodyCondition()`: convenience for body conditions
- `createDerivedValueExpression()`: convenience for attribute derived values

Different kinds of constraints require different context environments. The `setContext()`, `setOperationContext()`, and `setAttributeContext()` methods create the appropriate nested `Environment` s in the host `OCL` instance's root environment.

The result of parsing a query expression or a constraint is an `ExpressionInOCL`, an instance of the Abstract Syntax Model.

> The Ecore/UML binding variously produces a Constraint or OCLEXpression result. A Constraint has too much context and an OCLExpression too little. An ExpressionInOCL is just right.

```
// create an OCL helper object
OCLHelper helper = ocl.createOCLHelper(EXTLibraryPackage.Literals.LIBRARY);

ExpressionInOCL invariant = helper.createInvariant(
    "books->forAll(b1, b2 | b1 <> b2 implies b1.title <> b2.title)");

ExpressionInOCL query = helper.createQuery(
    "books->collect(b : Book | b.category)->asSet()");
```
[Text for cut and paste]

7.5.4. Operation and Attribute Contexts

In the case of constraints on operations or attributes, the context consists of two elements: the constrained operation/attribute and a classifier in the context of which the constraint is to apply. This accounts for the possibility that a classifier defines constraints on inherited features. As an example, consider the `EModelElement::getEAnnotation(EString)` operation and `EReference::eReferenceType` property in the Ecore metamodel. These can be constrained as follows:

```
EOperation oper = null;
for (EOperation next : EcorePackage.Literals.EMODEL_ELEMENT.getEOperations()) {
    if ("getEAnnotation".equals(next.getName())) {
        oper = next;
        break;
    }
}

// define a post-condition specifying the value of EModelElement::getEAnnotation(EString).
// This operation environment includes variables representing the operation
// parameters (in this case, only "source : String") and the operation result
helper.setOperationContext(EcorePackage.Literals.ECLASS, oper);
ExpressionInOCL body = helper.createPostcondition(
    "result = self.eAnnotations->any(ann | ann.source = source)");

// define a derivation constraint for the EReference::eReferenceType property
helper.setPropertyContext(
    EcorePackage.Literals.EREFERENCE,
    EcorePackage.Literals.EREFERENCE__EREFERENCE_TYPE);
ExpressionInOCL derive = helper.createDerivedValueExpression(
    "self.eType->any(true).oclAsType(EClass)");
```

[Text for cut and paste]

7.6. Evaluating Constraints and Queries

In Parsing Constraints, we saw how to use the `OCLHelper` API for parsing OCL constraints and query expressions. Parsing constraints is very interesting in itself, but we can also make OCL come alive in our applications by evaluating these constraints. For this, OCL provides a `Query` API.

7.6.1. The OCL Query

Like the `OCLHelper` for parsing constraints, the OCL facade object provides `Query` objects for evaluating constraints and query expressions.

The `Query` encapsulates an `EvaluationEnvironment` providing the run-time values of context variables to the OCL interpreter. These context variables are set and retrieved using the following methods:

- `add(String, Object)`: adds a name-value binding for a variable
- `replace(String, Object)`: replaces an existing variable binding
- `remove()`: removes a variable binding
- `getValueOf(String)`: obtains a variable value

The context variables of primary interest are `self` and, in operation constraints, the variables corresponding to its parameters. The `EvaluationEnvironment` API is also used to supply values for "global" variables added to the parsing `Environment` by the client.

Another important consideration in the evaluation environment is the `allInstance()` operation, which obtains the entire extent of a classifier. For data types, this is a simple problem: the extent of an `Enumeration` is well defined and the extents of other kinds of `DataType` s are undefined. For `Class` extents, the `EvaluationEnvironment` provides support for an extent map, mapping classes to the sets of their instances, as determined by the client. A client sets the extent map using the `OCL.setExtentMap()` method. The default extent map, if none is provided by the client, lazily computes the extent of a class from the EMF `ResourceSet` containing the context element of the evaluation.

So, after optionally setting values of context variables (other than `self`; the `Query` takes care of this) and an extent map, simply construct a query and use it to evaluate the expression or check the constraint:

```
OCL ocl = OCL.newInstance();
OCLHelper helper = ocl.createOCLHelper(EXTLibraryPackage.Literals.LIBRARY);
ExpressionInOCL invariant = helper.createInvariant(
    "books->forAll(b1, b2 | b1 <> b2 implies b1.title <> b2.title)");
ExpressionInOCL query = helper.createQuery(
    "books->collect(b : Book | b.category)->asSet()");

// create a Query to evaluate our query expression
Query queryEval = ocl.createQuery(query);

// create another to check our constraint
Query constraintEval = ocl.createQuery(invariant);

List<Library> libraries = getLibraries();  // hypothetical source of libraries

// only print the set of book categories for valid libraries
for (Library next : libraries) {
    if (constraintEval.check(next)) {
        // the OCL result type of our query expression is Set(BookCategory)
        @SuppressWarnings("unchecked")
        Set<BookCategory> categories = (Set<BookCategory>) queryEval.evaluate(next);

        debugPrintf("%s: %s%n\n", next.getName(), categories);
    }
}
```
[Text for cut and paste]

One of the advantages of the `Query` API is that a query's evaluation environment can be reused for multiple evaluations, as above. The extent of any classifier is only computed once. For convenience, however, in situations where only a single evaluation is required, the `OCL` class provides shortcuts:

```
// check a single library
Library lib = getLibrary();  // hypothetical source of a library

// check whether it satisfies the constraint
System.out.printf("%s valid: %b", lib.getName(), ocl.check(lib, invariant));
```
[Text for cut and paste]

The `Query` API also provides methods that work on multiple elements. The first example, above, could be written more succinctly as:

```
// only print the set of book categories for valid libraries
for (Library next : constraintEval.select(libraries)) {
    @SuppressWarnings("unchecked")
    Set<BookCategory> categories = (Set<BookCategory>) queryEval.evaluate(next);

    System.out.printf("%s: %s%n", next.getName(), categories);
}
```
[Text for cut and paste]

7.7. Parsing OCL Documents

As we saw in the Parsing Constraints and Queries topic, the OCL parser provides an `OCLHelper` API for parsing constraints embedded in models. OCL also permits constraints to be specified in a text document, as an adjunct to the model. In this case, the concrete syntax for context declarations indicates the context of constraints, equivalent to their placement in models.

As an example, consider the following Complete OCL document:

```
import 'platform:/plugin/org.eclipse.emf.examples.library/model/extlibrary.ecore'

package extlibrary

context Library
-- get all books with a title in a library and its branches (recursively)
def: getBooks(title : String) : Set(Book) =
    books->select(b | b.title = title)->asSet()->union(
        branches.getBooks(title)->asSet())

context Book
-- the library containing a book
def: library : Library = Library.allInstances()->any(books->includes(self))

-- book titles are unique within their library branch (and its sub-branches)
inv unique_title: not library.oclIsUndefined() implies
    library.getBooks(title) = Set{self}

endpackage
```

[Text for cut and paste]

7.7.1. The OCL Input

The Ecore binding provided an `OCLInput` class to supervise the OCL source text, and the result of parsing the document was a `List<Constraint>`. The Pivot binding uses an Xtext parser with a UML-aligned output. The input text is therefore specified by a URI and loaded by the Xtext parser to create a Concrete Syntax Resource. This may then be converted to the Pivot Abstract Syntax Resource. The Abstract Syntax Resource has a conventional Model, Package, Class, Operation hierarchy in order to provide a coherent composition context for the Constraints.

The Concrete Syntax Resource created by the Xtext parser

* comprises a CompleteOCLDocumentCS
* containing a PackageDeclarationCS for `extlibrary`
* containing a ClassifierContextDeclCS for `Library`
  * containing a DefCS
    * containing a DefOperationCS for `getBooks`
    * and a SpecificationCS
* and a ClassifierContextDeclCS for `Book`
  * containing an InvCS for `unique_title`
  * containing a SpecificationCS

each SpecificationCS contains the parsed OCL Expression tree.

The complementing Abstract Syntax Resource

* comprises a Model with a `pivot:/..../extlibrary.ocl` URI
* containing a Package named `extlibrary`
* containing a Class named `Library`
  * containing an Operation named `getBooks`
  * containing a body Constraint
* and a Class named `Book`
  * containing an invariant Constraint for `unique_title`

The complementing Abstract Syntax Resource has the same structure as the complemented Resource

The complemented Abstract Syntax Resource

* comprises a Model with a `pivot:/..../extlibrary.ecore` URI
* containing a Package named `extlibrary`

- containing a Class named `Library`

- and a Class named `Book`

There are therefore two Class objects named `Library`, one for each Resource. The objects are distinct in so far as they belong to different resources, which can be separately serialized, and in so far as they may appear distinct to OCL expressions that use reflective access. However they are logically merged and the `MetaModelManager` provides utility methods that allow the multiple objects to be accessed as a merged object.

Given the `URI` of an OCL document, simply ask an `OCL` to parse it:

```
EPackage.Registry registry = new EPackageRegistryImpl();
registry.put(EXTLibraryPackage.eNS_URI, EXTLibraryPackage.eINSTANCE);
OCL ocl = OCL.newInstance(registry);

// get an OCL text file via some hypothetical API
URI uri = getInputURI("/model/parsingDocumentsExample.ocl");

Map<String, ExpressionInOCL> constraintMap = new HashMap<String, ExpressionInOCL>();

// parse the contents as an OCL document
Resource asResource = ocl.parse(uri);
for (TreeIterator<EObject> tit = asResource.getAllContents(); tit.hasNext(); ) {
    EObject next = tit.next();
    if (next instanceof Constraint) {
        Constraint constraint = (Constraint)next;
        ExpressionInOCL expressionInOCL = ocl.getSpecification(constraint);
        if (expressionInOCL != null) {
            String name = constraint.getName();
            if (name != null) {
                constraintMap.put(name, expressionInOCL);
                debugPrintf("%s: %s%n\n", name,
                    expressionInOCL.getBodyExpression());
            }
        }
    }
}
```
[Text for cut and paste]

7.7.2. Accessing the Constraints

The `OCL` returns the list of constraints if they were successfully parsed. They are retained by the OCL (available via the `getConstraints()` method at any time), and in particular, any definitions of additional operations or attributes are available for subsequent constraint parsing. Any number of OCL documents may be parsed by the same `OCL` instance, combined also with constraints parsed by `OCLHelpers`. All of these constraints are retained by the `OCL` environment.

```
Library library = getLibrary();  // get library from a hypothetical source

OCLHelper helper = ocl.createOCLHelper(EXTLibraryPackage.Literals.LIBRARY);

// use the constraints defined in the OCL document

// use the getBooks() additional operation to find a book
ExpressionInOCL query = helper.createQuery(
    "getBooks('Bleak House')->asSequence()->first()");

Value bookValue = ocl.evaluate(library, query);
Book book = (Book) bookValue.asObject();
System.out.printf("Got book: %s%n", book);

// use the unique_title constraint to validate the book
boolean isValid = ocl.check(book, constraintMap.get("unique_title"));
System.out.printf("Validate book: %b%n", isValid);
```
[Text for cut and paste]

The source for these examples may be found in the org.eclipse.ocl.examples.xtext.tests plugin in model/parsingDocumentsExample.ocl and in src/org/eclipse/ocl/examples/test/xtext/ PivotDocumentationExamples.java.

7.8. OCL Relationship to Metamodels

The Pivot-based OCL implementation provides indirect support for models defined using either the Ecore or the UML metamodel (as implemented by the Eclipse EMF and UML2 projects), and an [extensibility API](#) that allows additional EMF-based metamodels to be plugged in. The indirection through the UML-aligned Pivot metamodel makes OMG compliance much easier and decouples the implementationm from particular bindings. Support for an alternate concrete metamodel representation is therefore comparatively simple.

The OCL API implements support for different target metamodels via the `EnvironmentFactory` interface. An implementation of this interface binds the metamodel's metaclasses to the generic type parameters of the `OCL` class. The metamodel-specific `Environment` implementation constructed by this factory implements the reflection capability required by OCL to discover the elements of the model being constrained and the relationships between them.

7.8.1. The Pivot Metamodel Binding

A preliminary OCL binding for the Pivot metamodel is provided in the Indigo release by the `org.eclipse.ocl.examples.pivot` plug-in. It is planned to promote this to `org.eclipse.ocl.pivot` in the Mars release.

The Pivot metamodel prototypes resolutions of the following problems in the OCL 2.4 specification

- UML-alignment
- OCL Standard Library model
- XMI interchange
- Complete OCL implementability

The support for an OCL Standard Library model enables large parts of the OCL specification to be captured by models. This makes the behavior mutable and extensible through definition of alternate or extended library models. (The corresponding Ecore and UML bindings have an Ecore representation of the library but much of its functionality is directly implemented and so immutable.)

The Pivot metamodel is auto-generated by a package merge of

- selected parts of the UML metamodel
- additional OCL packages
- implementation-specific packages

The implementation-specific packages provide

- Visitors throughout the entire metamodel (OCL **and** MOF)
- Ecore extensions

It is anticipated that the performance advantages of a uniform compliant metamodel, without the complexities of the templates from the `org.eclipse.ocl` plugin, will outweigh the initial overhead of converting an Ecore or UML metamodel to Pivot form. Once this has been demonstrated, the direct Ecore and UML metamodels will be deprecated.

The Pivot binding is provided by the `PivotEnvironmentFactory` class. For compatibility, as a default, the Pivot environment uses the static `EPackage` registry to look up package names. This default is deprecated since the domain of `allInstances()` may be very large when many models are registered. It should therefore be supplied with an alternative package registry (for example, one local to a `ResourceSet`) for relevant metamodels. The static registry is then used as a backup for package lookups, but not for `allInstances()`. The Pivot environment factory maintains the Pivot models associated with

- Ecore metamodels in use
- UML metamodels in use
- Library models in use

- Concrete Syntax source models
  - OCLinEcore (rather than Ecore)
  - Complete OCL
  - OCL Standard Library

The Pivot binding for OCL will provide the full capabilities of the UML binding, but at present only the Ecore facilities have been tested. The Pivot binding has the additional ability to support extensions to the library.

For applications that work exclusively with the Pivot binding for OCL, the `org.eclipse.ocl.examples.pivot` package defines an `OCL` class that provides similar facilities to the corresponding Ecore and UML binding equivalents.

The Pivot metamodel is used by Eclipse OCL for:

- all Xtext editors; editing, parsing, analysis and validation
- the Xtext OCL console; editor and evaluation
- EMF delegates using the http://www.eclipse.org/emf/2002/Ecore/OCL/Pivot URI
- explicit use of the Pivot metamodel from Java

The Pivot metamodel is not used by Eclipse OCL for:

- OCL console editing and evaluation
- EMF delegates using the http://www.eclipse.org/emf/2002/Ecore/OCL/LPG URI
- Impact Analyzer.
- explicit use of the Ecore or UML bindings from Java

EMF delegates using the http://www.eclipse.org/emf/2002/Ecore/OCL virtual URI are redirected to either http://www.eclipse.org/emf/2002/Ecore/OCL/Pivot or http://www.eclipse.org/emf/2002/Ecore/OCL/LPG by the setting of the "Executor targeted by the default OCL delegate" preference setting, which defaults to http://www.eclipse.org/emf/2002/Ecore/OCL/LPG for compatibility.

Note that the Indigo and Juno OCLinEcore editor uses the http://www.eclipse.org/emf/2002/Ecore/OCL/Pivot URI and so uses the Pivot Evaluator, whereas the Helios OCLinEcore editor used the http://www.eclipse.org/emf/2002/Ecore/OCL URI and so the Ecore evaluator. A file using the http://www.eclipse.org/emf/2002/Ecore/OCL URI will automatically be upgraded to the http://www.eclipse.org/emf/2002/Ecore/OCL/Pivot URI when edited using the Indigo or Juno OCLinEcore editors.

In Kepler and Luna, the OCLinEcore editor preserves any existing delegate URI selection. The new "Preferred executor requested for OCL constraints" preference determines the URI when no previous setting is available. This defaults to http://www.eclipse.org/emf/2002/Ecore/OCL/Pivot for backwards compatibility. h2(#Pivot-Ids). Ids

The ElementId hierarchy provides the simplest base level of metamodel representation. The ElementIds feature

- identity
- uniqueness
- thread-safety
- predictability
- hashcodes

Every primary hierachical metamodel object such as a Package, Type, Operation or Property has a globally unique identity established by the package-class-feature path.

Auxiliary metamodel object such as a TemplateParameter, TuplePart or List-of-Parameter have a locally unique identity supporting fast matching of tuples or single lookup for operation parameters.

7.8.2. Id Equality

ElementIds are unique, whereas metamodel elements are not; there may be many meta-models in many applications all with their own Boolean PrimitiveTypeImpl instances. The equivalence of these

elements may be established rapidly since each returns the same TypeId.BOOLEAN singleton from PrimitiveTypeImpl.getTypeId().

7.8.3. IdManager

Uniqueness of ElementIds is enforced by the various getXxxId methods of the single IdManager.INSTANCE. These methods are synchronized to ensure thread safety. Child hierarchical objects are similarly mediated by their parent.

7.8.4. CollectionTypeId

CollectionTypeIds are a degenerate form of specialization/generalization with a single template parameter. The template parameter is declared explicitly in generalizations.

7.8.5. TupleTypeId

TupleTypes are self-contained, that is all external template parameter references with the part types are bindings of a specialized tuple type whose generalization replaces those external references by the template parameters of the generalization.

For instance given a declaration

Set(A)::op(B)() : Tuple(a:A, b:Bag(B), c:B)

Tuple(a:A, b:Bag(B), c:B) is the (A,B) specialization of the Tuple(T1,T2)(a:T1,b:Bag(T2),c:T2) generalization.

7.8.6. LambdaTypeId

LambdaTypes are self-contained in the same way as tuples with specializations of generalizations.

7.8.7. ParameterIds

A ParameterIds identifies an ordered list of typeid suitable for identifying an operation's parameter list by a single object and hashcode.

A ParameterIds has no knowledge of its parent Operation and so ParameterIds are reused whenever the typeid list arises. Note that collection typeids are always collectionTypeIds, so there is no need for multiplicities. The residual optional existence is not subject to overloading and is ignored in ParameterIds.

LambdaTypes reuse ParameterIds to capture the extended type list comprising the typeids of context-type, result-type then parameter-types.

7.8.8. TuplePartId

A TuplePartId identifies a part of a Tuple. It has a name, typeid and index. The index is the part position in the set of parts in a parent tuple alphabetically sorted by name. It provides efficient access to a slot position in a tuple representation.

A TuplePartId has no knowledge of its parent Tuple and so TuplePartIds are reused whenever the same combination of name, typeid and index arise.

7.8.9. TemplateParameterId

A TemplateParameterId identifies a template parameter in the ordered list of template parameters in a parent templateable element. It has just an index in the parent list. For debugging purposes a TemplateParameterId has a name such as $0 or $1.

A TemplateParameterId has no knowledge of its parent templateable element and so only a couple of TemplateParameterIds ever exist. Three are statically defined as TypeId.T_1, T_2, T_3.

TemplateParameterId has no knowledge of whether it is a type or value parameter. Pragmatically a TemplateParameterId extends a TypeId. (This design decision may need revision.)

7.8.10. Code Generation

Since the ElementIds are predictable and unique, code generation can assign them for computation once in static variables so that large parts of the costs of model elememnt location can be performed at compile

time. At class load time it is only necessary to construct/share the ElementId object. At run-time the ElementId provides a hashcode to provode rapid lookup.

Chapter 8. API Reference

8.1. Javadoc

The Javadoc for Eclipse OCL 5.0.0 (Luna) APIs may be found by following the [OCL 5.0.0 API Reference](#) link.

8.2. Extension points

There is one extension point, but it is no longer clear that it has any useful functionality. Please consider it deprecated.

[Extension Points Reference](#).

Chapter 9. Building the OCL Project

This section contains some details on the way in which the OCL project is built. This should only be of interest to users creating extension of the project.

9.1. GenModel GenAnnotations

The automated generation of models that form part of the OCL tooling exploits a number of GenAnnotations to influence the auto-generated code.

9.1.1. http://www.eclipse.org/OCL/GenModel GenAnnotation Source

```
<genAnnotations source="http://www.eclipse.org/OCL/GenModel">
 <details key="Use Null Annotations" value="true"/>
</genAnnotations>
```

This GenAnnotation is also used by regular OCL code generation

9.1.1.1. Use Delegates

If the *Use Delegates* key is present and has a *true* value genModel will generate code for OCL expressions that delegates to the run-time interpreter, rather than generating Java code.

9.1.1.2. Use Null Annotations

If the *Use Null Annotations* key is present and has a *true* value the generated code will have *@NonNull* and *@NonNull* annotations.

9.1.2. http://www.eclipse.org/OCL/GenModel/ToString

```
<genAnnotations source="http://www.eclipse.org/OCL/GenModel/ToString">
 <details key="org.eclipse.ocl.examples.codegen.cgmodel.CGElement"
   value="return &lt;%org.eclipse.ocl.examples.codegen.analyzer.CG2StringVisitor%>.toString(this);"/>
</genAnnotations>
```

By default EMF generates a toString() method that identifies all attribute values. This cannot be suppressed, only circumvented.

If the `http://www.eclipse.org/OCL/GenModel/ToString` GenAnnotation is present the default is changed to use an inherited implementation, which must be specified somewhere.

Specific implementations of toString may be provided as the values of detail entries whose key is the qualified name of the interface class. Imports may be encoded with the implementation by enclosing the fully qualified name in `<%...%>`.

9.1.3. http://www.eclipse.org/OCL/GenModel/Visitor

```
<genAnnotations source="http://www.eclipse.org/OCL/GenModel/Visitor">
 <details key="Root Visitor Class"
  value="org.eclipse.ocl.examples.codegen.cgmodel.util.CGModelVisitor"/>
 <details key="Derived Visitor Class"
  value="org.eclipse.ocl.examples.codegen.cgmodel.util.CGModelVisitor"/>
 <details key="Visitable Classes"
  value="org.eclipse.ocl.examples.codegen.cgmodel.CGElement"/>
</genAnnotations>
```

The accept method for an hierarchical visitor pattern may be woven into the code using the `http://www.eclipse.org/OCL/GenModel/Visitor` genAnnotation.

The implementation for class XXXX in the root package is

```
@Nullable R accept(@NonNull RootVisitorClass<R> visitor) {
 return visitor.visitXXXX(this);
}
```

The implementation for class XXXX in the derived package is

```
@Nullable R accept(@NonNull RootVisitorClass<R> visitor) {
 return (R) (DerivedVisitorClass<?>)visitor).visitXXXX(this);
}
```

The direct cast to the derived type assumes that the caller has ensured that the visitor in use supports the visitor interfaces for all objects in use.

The null annotations or omitted unless null annotations have been enabled.

9.1.3.1. Root Visitor Class

The fully qualified name of the visitor class must be specified as the value of the *Root Visitor Class* detail. This class defines the argument type of the accept method.

9.1.3.2. Derived Visitor Class

The fully qualified name of the derived visitor class must be specified as the value of the *Derived Visitor Class* detail. This detail may be omitted for the root package.

9.1.3.3. Visitable Classes

An @Override annotation is generated for all implementations. This leads to an error where the implementation is not an override. The space-separated fully qualified names of all classes for which the accpe is not an override must be specified as the value of the *Visitable Classes* detail.

9.1.3.4. Implementation Details

The support for accept is in `templates/model/Class/insert.javajetinc` where the appropriate code is generated into the implementation file with help from OCLBuildGenModelUtil.

9.1.4. http://www.eclipse.org/OCL/GenModel/CopyAndPaste

```
<genAnnotations source="http://www.eclipse.org/OCL/GenModel/CopyAndPaste">
 <details key="org.eclipse.ocl.examples.xtext.markup.FigureElement"
  value="model/FigureElement.javacopy"/>
</genAnnotations>
```

EMF allows custom code to be added to classes using an @Generated NOT comment annotation or no annotation at all. These additions are preserved during regeneration, but may be lost if the file is deleted and regenerated.

As an alternative, custom contributions may be pasted into class implementation files by specifying a detail entry whose key is the qualified interface name of the class to be customised and whose value is the project-relative name of a file providing text to be copied and pasted.

The copied text should be tab indented so that it matches the tab indentation of the auto-generated code.

The copied text may reference types that may need importing by encoding the fully qualified name in `<%...%>`.

The customization files are conventionally given a *.copyjava file name and are placed in the model folder alongside the *.genmodel.

9.1.4.1. Implementation Details

The support for copy and paste is in `templates/model/Class/insert.javajetinc` where the referenced text is copied into the implementation file with help from OCLBuildGenModelUtil.

9.1.5. Implementation Details

9.1.5.1. `org.eclipse.ocl.examples.build`

The `org.eclipse.ocl.examples.build` plugin hosts the build-time functionality that does not need to bloat the distribution.

Modified JET templates are in the `templates` folder which `.jetproperties` prefixes to the template path. The `.project` has an `org.eclipse.emf.codegen.jet.IJETNature` nature and builder so that the custom JET templates are automatically built to the `jet-gen` source folder. The

`.project` similarly has has an `org.eclipse.xtext.ui.shared.xtextNature` nature and builder so that the Xtend templates are automatically built to the `xtend-gen` source folder. Both these generated source folders are excluded from source control, since they are 100% auto-generated and they do not form part of the distribution.

Custom JET templates are declared by OCLBuildGenModelGeneratorAdapterFactory which creates a OCLBuildGenClassGeneratorAdapter that replaces the normal reference to `org.eclipse.emf.codegen.ecore.templates.model.Class` by `org.eclipse.ocl.examples.build.templates.model.Class`.

The custom build functionality is installed by the `GenModelSetup` workflow component,

9.1.5.2. `org.eclipse.ocl.examples.build.acceleo`

The Acceleo builder and quiescent performance has not proved very satisfactory, consequently the main templates have been migrated to Xtend. The remaining templates are in the `org.eclipse.ocl.examples.build.acceleo` plugin which can be kept closed most of the time allowing operation without installing Acceleo at all.

9.2. ASM 3

OCl project endeavors to maintain compatiobility beyond the latest release, so when Luna moved to ASM 5, there was a problem supporting installation on Juno and Kepler where only ASM 3 were available. Either the codegen.asm3 or codegen.asm5 plugin is used on the relevant platforms.

If you create a Luna installation, ASM 5 is installed and ASM 3 is missing, so you get compiler errors. Unfortuntately Luna does not allow you to directly install ASM 3 from Orbit http://download.eclipse.org/tools/orbit/downloads/ to remedy the deficiency.

If you are very astute, you will install ASM 3 before you install ASM 5, but more likely it's too late, so copy or install e.g. org.objectweb.asm_3.3.1.v201105211655.jar somewhere and then copy it to the installation dropins folder. Restart Eclipse and the errors go away.

Appendix A. Glossary

EMF	Eclipse Modeling Framework
OCL	Object Constraint Language
OMG	Object Management Group
QVT	Query View Transformation
RTF	Revision Task Force
UML	Unified Modeling Language